NTENTS PAGE 2

v, at


can

ying


s up

d to give om-


1,111 TIMKEN bearings to help new Aetna-Standard tube mill boost production



How Timken tapered roller bearings are mounted on main roll necks of a typical Aetna-Standard piercing mill.



Timken tapered roller bearings on piercing mill thrust blocks typical of those used in the new Aetna-Standard mill.



A typical mounting of Timken tapered roller bearings on reducing and sizing mill roll necks.

ANOTHER new seamless tube mill, now being built by the Aetna-Standard Engineering Company for The Colorado Fuel and Iron Corporation, Pueblo, Colorado, will do its job on Timken* bearings. Aetna-Standard knows from experience that Timken bearings on mills like this insure higher speeds, longer life and minimum time-outs for maintenance and repairs. That's why a total of 1,111 Timken bearings are being used on the new mill's roll necks, drives, thrust blocks, and troughing tables.

Today, it is estimated that 95% of America's seamless tubing is produced on mills equipped with Timken bearings. Over 50 years of bearing research and development have made Timken bearings the number one choice of industry. Specify them for the machines you build. Look for them in the machines you buy. The Timken Roller Bearing Company, Canton 6, Ohio. Canadian plant: St. Thomas, Ontario. Cable address: "TIMROSCO".

Here's where the 1,111 Timken bearings are used in the new Aetna-Standard seamless tube mill:

Two 36" piercing mills		0	50
24" plug mill			- 8
Two 30" reelers			26
14-stand 16½" reducing	m	ill	262
7-stand 20" sizing mill.	0		192
3-stand 20" sizing mill.			24
Troughing table rollers	0	0	549
Total Timken Bearings			1,111

TIMKEN

TAPERED ROLLER BEARINGS

Punch press builder insures good lubrication

with Farval

ON this Warco press, there are no grease cups. Nothing is left to the judgment of the man with an oil can. The machine is protected by a Farval Centralized System of Lubrication.

Farval makes it routine to see that every bearing regularly gets the exact, measured amount of lubricant it requires. Each work shift, a few strokes of a hand pump lever provide adequate lubrication and keep the press running at top efficiency.

With Farval, special oilers are not needed, lubricant consumption is reduced, bearing life is extended materially and shutdowns for oiling or bearing replacement are eliminated. In short, with Farval on the job, the purchaser of a Warco press is insured of getting all the value built into the machine by its manufacturer.


Farval is the original Dualine system of centralized lubrication for industrial equipment, proved practical in 25 years of service. The Farval valve has only two moving parts — is simple, sure and foolproof, without springs, ball-checks or pinhole ports to cause trouble. Through its full hydraulic operation, the Farval system unfailingly delivers oil or grease to each bearing—as much as you want, exactly measured—as often as desired. Indicators at all bearings show that each valve has functioned.

In or near your city there's a Farval engineer, ready to discuss your lubrication problems and suggest a proper system to meet your particular needs.

The Farval Corporation, 3252 East 80th Street, Cleveland 4, Ohio.

Affiliate of The Cleveland Worm and Gear Company, Industrial Worm Gearing. In Canada: Peacock Brothers Limited.





KEYS TO ADEQUATE LUBRICATION — Wherever you see the sign of Farval—the familiar valve manifolds, dual lubricant lines and central pumping station—you know a machine will be properly lubricated. Farval manually operated and automatic systems protect millions of industrial bearings.

in

Photo above by courtery Federal Machine and Welder Co.

18,000-lb Mould-Band Made by Welding

This giant ring of steel, weighing approximately 9 tons, is one of three identical mould-bands, made recently for use in a 134-in. ingot-mould. Each band is 15 ft, 4 in. in outside diameter, 22 in. wide, and 4 in. thick. The end lugs are of forged steel. The bands were fabricated in halves.

Welding was done in Bethlehem's Weld-

ments Shop.

Practically any type of mould, press, machine or machine part can be made economically by using Bethlehem Weldments. They eliminate excess weight, without sacrifice in rigidity, often leading to reduction in cost of manufacture. Besides, these weldments are extremely versatile, as they can be produced in a wide range of sizes, either as simple parts or intricate assemblies.

Bethlehem Weldments offer full freedom in product design, because the steel from which they are made can be bent, pressed or otherwise shaped prior to welding, without harm to its physical structure. They can also be combined effectively with forgings or castings.

Perhaps you could use Bethlehem Weldments advantageously. Why not talk it over? Write to the nearest Bethlehem office, and we'll arrange for a Bethlehem representative to see you at your convenience.

BETHLEHEM STEEL COMPANY BETHLEHEM, PA.

On the Pacific Coast Bethlehem products are sold by Bethlehem Pacific Coast Steel Corporation. Export Distributor: Bethlehem Steel Export Corporation





BETHLEHEM WELDMENTS

the ron ge

Vol. 170, No. 22, November 27, 1952

* Starred items are digested on opposite page.

EDITORIAL

Let's Nail	Iŧ	Down						٠						0	0	0	٠		7
NEWS OF		MBHSTI	٠,	,	ı														

*Special Report: Tariffs—High or Low?...... 37

NEWS OF INDUSTRY

*Distribution: Warehouses Expand With Demand	39
*Production: Aluminum—Strip to Welded Tubing	40
*Manufacturing: Stargazers Call on a Shipyard.	41
*Research: Purer Iron from Direct Reduction	43
*Expansion: Steel Capacity Up 7.2 Million Tons.	44
Construction: Housing Unit Costs Dip	46
Labor: Aircraft Tooling is Different	48
*Controls: Industry Asks CMP Exit	49

Personnel: Iron Age Salutes

Iron Age Introduces 97

50

95

NEWS ANALYSIS

Defense Contracts

Newsfront						,										. 3	0.0
*Automotive Assembly Line																	
*This Week in Washington																	
West Coast Report	٠		 	0			0			0		٠			6	. 6	1
*Machine Tool High Spots			 					0	0		0	0	0	0	0	. 6	-
Canadian Comment		0	 		0		0		0				0			. 6)

TECHNICAL ARTICLES

*Foundries Report On Basic Electric Arc Practice	103
*Automation: Forging Costs Down, Quality Up	106
*P Charts Improve Ratio-Delay Studies	110
*Carbide Tipped Hammers Cut Pulverizing Costs	114
Precision Inspection Checks Engine Components	117
*Bar Pointer Improves Spring Production	120

MARKETS & PRICES

* The Iron Age Summary—Steel								
Market Briefs								
*Nonferrous Markets		 						130
Iron and Steel Scrap Markets	0 1	 			0			134
Comparison of Prices		 		0				138
Steel Prices								

REGULAR DEPARTMENTS

Dear Editor																			,		,			9
Fatigue Cracks										0														- 11
Conventions and	1	M	le	9	†	11	10	35			0	D	0	0	0	0	0	0	0	d	0	0	٠	13
Free Publications New Equipment	6					4			6		0	0		0		4	.0						0	74

THE IRON AGE, published every Thursday by the CHILTON CO. (INC.), Chestnut & 58th Sts., Philadelphia 39, Pa. Entered as second class matter, Nov. 8, 1932, at the Post Office at Philadelphia under the act of March 3, 1873, \$5 yearly in United States, its territories and Canada; other Western Hemisphere Countries, \$15 of the Foreign Countries, \$25 per year. Single copies, 35c. Annual Review and Metal Industry Facts Issue, \$2.00. Cables: "Tronage," N. X.

DIGEST of

NEWS DEVELOPMENTS

DO YOU FAVOR HIGH OR LOW TARIFF RATE?—P. 37 Whether an industry is for or against tariffs depends on what products it makes, how it makes them, and where they are sold. Now that the Republican Congress must act on extending the tariff act next year industry had better prepare to make its views felt. Issues will be "adequate" against low duties.

WELDED ALUMINUM PIPE MADE IN QUANTITY—P. 40 Aluminum strip is welded into 3-in. irrigation pipe on commercial basis. Patents pending on process for automatically arc-welding tubing from strip in inert atmosphere. Nearly 3 years of development pays off as product acceptance grows. Four-fold expansion under way by Aluminum Supply Co.

SHIPYARD BUILDS PLANETARIUM PROJECTOR—P. 41 First planetarium projector built in U.S. made by Bethlehem Pacific's San Francisco Shipyard. Some parts of the projector had to be machined within tolerances of 0.001. Work included machining surfaces of two spherical star projector carriers and boring 15 9-in. holes in each.

DIRECT REDUCTION GIVES HIGH PURITY IRON—P. 43
Test heats of direct-reduced iron result in average purity of
99.94575 pct Fe. Aim of Arata Metallurgy was to determine commercial feasibility of electric-arc furnace process. Magnetite
concentrates analyzing 57 to 71 pct Fe were used. Even
higher purity may be made. Military, electronic uses seen.

STEEL CAPACITY UPPED 7.2 MILLION TONS—P. 44
By the end of the year, U.S. steel mills will have installed
7.2 million tons of new ingot capacity. Total capacity in '53
will be about 116 million tons, not far from 120-million ton
goal established last year. Midwest and East lead in steel
expansion. New facilities may speed scuttling of CMP.

ARE THERE ENOUGH GAGES TO GO AROUND?—P. 65 With machine tool shipments steadily rising and cutting tool requirements being filled, it now appears there may not be enough gages to make ends meet. Ways of meeting stronger market demand for gages are a prime concern of industry and government. NPA gets ready to recommend gage expansion.

the Week in Metalworking

ENGINEERING & PRODUCTION

MARKETS & PRICES

TREND TO BASIC ELECTRIC ARC PRACTICE—P. 103
A survey of 25 foundries, representing about 75 pct of the total using basic electric arc furnaces for melting ferritic steels, shows the trends and significant differences in melting practice. Without high grade scrap in many areas the trend is away from acid electric furnace practice.

WAREHOUSE CAPACITY EXPANDS WITH STEEL—P. 39
Growth of warehouse industry matches higher steel needs. Lack of personnel and working capital plus short steel inventories are the main stumbling blocks with emphasis on stocks. But warehousemen are confident of continued good business. Planning extends to 1955 and beyond. All factors considered.

AUTOMATION IS PRACTICAL FOR FORGE SHOPS—P. 106
Automation is just around the corner for forge shops—large and small. Plants once stymied by the limits of operator skill and lack of fast heating equipment, now have new, faster production methods available. Higher output per man hour, improved quality and lower costs are tangible results.

STEEL INDUSTRY TASK FORCE ASKS CMP END—P. 49
The steel industry has asked National Production Authority to scrap all Controlled Materials Plan regulations except for military and atomic energy priorities by April 1. But retention of production directives was recommended to assure meeting defense production needs in tight categories of steel products.

P CHART USED WITH RATIO-DELAY TECHNIQUES—P. 110 If you use ratio-delay techniques for establishing downtime percentages, you can get more accurate results with this simple method. The p chart has been adopted for use with ratio-delay techniques. Result is an improved statistical method for determining downtime and more accurate data.

be

d

E

AUTOMOTIVE SALES DROP BUT PROFITS MOUNT—P. 54
Despite lower sales automotive profits for the first 9 months
of 1952 were generally higher than in '51. Trend to increased
earnings in spite of lowered sales is due mainly to easing of
price controls. Another factor is lessened use of conversion
steel, although the steel strike increased use temporarily.

CARBIDE HAMMERS CUT PULVERIZING COSTS—P. 114 Hammers of pulverizing mills last up to 100 times longer when tipped with tungsten carbide. Overall hammer length, essential to mill efficiency, is maintained for longer periods. Cost for replacement of hammers has been reduced while repair and maintenance downtimes have been minimized.

WILL THE GOVERNMENT GIVE UP BUSINESS?—P. 59
Support for proposals that the government give up some of its
business ventures is growing. Need for new sources of revenue
is main reason these proposals may succeed. GE's Charles
Wilson predicts sale of government dams, generating equipment
and distribution facilities would cut national debt 10 pct.

BAR POINTER RAISES COIL SPRING OUTPUT—P. 120 Addition of a comparatively simple mechanical bar handling and roll feeding device has increased production and cut rejects of pointed steel bars for coil springs in Chrysler-made cars. In addition to providing relief from a monotonous, fatiguing job, the device has improved quality control.

DECONTROL TIMETABLE BEGINS TO TAKE SHAPE—P. 127
Steel industry task force recommendations for decontrol are backed by a market forecast that makes these points: Production next year can be as high as 118.8 million net tons—if needed, No more than 14 million tons will be needed for military, atomic uses. This leaves up to 104 million tons for others.

MAGNESIUM FINISHES FOR AIRCRAFT USE—NEXT WEEK A project was undertaken by Northrup Aircraft, Inc. to evaluate magnesium finishes for production applications. Numerous finishes much better than those used in current aircraft production were developed. The average vinyl-base finish offered British lead market is still leading the U. S. price around regardless of market strength here. First dip of the month caused by London weakness, others may follow. Zinc is still the same but what happens next year will probably be determined in London where private trade will soon be resumed.

better means of corrosion protection.

RESEARCH REEPS B.F.Goodrich



Where B. F. Goodrich grommet belts have outlasted others 8 to 1

B. F. Goodrich grommet V belts cut costs 20 to 50%

E ACH time this machine is started the belts that drive it take a beating. The shock, combined with the heavy pulling load and high speed, caused the first set of V belts used on this drive to fail in only 6 months. Something exceptional was needed, so B. F. Goodrich grommet V belts were installed. That was over 4 years ago, and they're still in use. In fact, the company superintendent says it looks as though this same set of grommet V belts will operate another 10 years. Here's why B. F. Goodrich grommet belts outperform ordinary belts:

No cord ends - A grommet is endless, made by winding heavy cord on itself to form an endless loop. It has no overlapping ends. Because most of the failures in ordinary V belts occur in the region where cords overlap, the end-

4

less cord section in a grommet V belt eliminates such failures.

Concentrated cord strength - All of the cord material in a B. F. Goodrich grommet belt is concentrated in twin grommets, positioned close to the driving faces of the pulley. There are no layers of cords to rub against one another and generate heat; cord and adhesion failures are reduced. And grommet V belts stretch less - only 3 as much, on an average, as ordinary V belts.

Better grip, less slip - Grommet V belts have more rubber in relation to belt size. Without any stiff overlap, they're more flexible, grip pulleys better. Size for size, grommet belts give 1/3 more gripping power, pull heavier loads with a higher safety factor. Because there is less slip, there is also less surface wear.

They cost no more - Grommet V belts cut costs because they last longer, increase production because machines keep running with fewer interruptions, reduce maintenance costs because they need less attention, yet they cost not one cent more. Available in C, D, and E sections. But remember, only B. F. Goodrich makes the grommet V belt (U. S. Patent No. 2,233,294), so to get all these savings, call in your local BFG distributor the next time you need V belts, or write The B.F. Goodrich Company, Industrial & General Products Division, Akron, Obio. (Available in

Grommet V. Betts **B.F. Goodrich** Fast Motor Service Wherever You Are



Factory approved motor service in every industrial area from 97 Allis-Chalmers Certified Service Shops.

Birmingham—Elec. Repair & Serv. Co. Montgomery—Standard Electric

Bisbee—Copper Electric Co. Inc. Phoenix—Daley Electric Company

CALIFORNIA

San Diego—Calif. Elec. Works Los Angeles—Larsen-Hogue Elec. Co. Oakland—T. L. Rosenberg Co. San Francisco—Weidenthal-Gosliner

Denver-Baker Electric Company

CONNECTICUT

Hartford—Charles H. Leppert Waterbury—Elec. Motor Repair Co.

V er.

nes

ns,

iev

ot

nd

F elt

get

G

V

772-

cts

in

E

Jacksonville—Turner Electric Works Miami—Peninsular Armature Works Tampa—Tampa Armature Works

GEORGIA

Albany—Georgia Electric Co. Atlanta—Bearden-Thompson Elec. Co. Columbus—Smith-Gray Electric Co.

Chicago — Chicago Electric Co. Marion—Giles Armature & Elec. Wks. Mt. Vernon—Dowzer Electric

Indianapolis-Scherer Electric Co. Evansville-Evansville Elec. & Mfg. Co

Sioux City-Smith Elec. & Supply Co.

Salina—Cent. Kans. Elec. Mach. Co. Wichita—Tarrant Electric Mach. Co.

LOUISIANA

New Orleans—Industrial Elec., Inc. Shreveport—Shreveport Arm. & Elec.

Brewer-Stanley J. Leen Co.

Baltimore—Keystone Electric Co.

MASSACHUSETTS

Lawrence—Roland B. Glines Co. Roslindale—Ranney Electric Motors Springfield—Elec. Motor Repair Co.

Detroit—Stecker Electric Company Grand Rapids—Grand Rapids Ind. Elec. Saginaw—Banning Elect. Prod. Corp.

MINNESOTA

Duluth—Mielke Electric Works Minneapolis—Parsons Elec. Co.

MISSISSIPPI

Vicksburg-Ludke Electric Co., Inc.

Kansas City — Boese-Hilburn Elec. Co. St. Louis—French-Gerleman Elec. Co. Springfield—Springfield Elec. Serv.

NEBRASKA

Omaha-Omaha Electrical Works

Concord-A. S. Tracy

NEW JERSEY

Atlantic City—Charles A. Buckley Paterson—Elec. Servics Repair Co. Trenton—Lockwood Elec. Motor Serv.

NEW MEXICO

Albuquerque-Electric Motor Company Powell Electric Co.

NEW YORK

NEW YORK
Buffolo—Robertson Electric Co.
Jamestown—A. E. Westburgh
Mt. Vernon—H. A. Schreck, Inc.
New York—Consol. Elec. Motor Co.
Rochester—Vanderlinde Elec. Corp.
Ulrica—Mather, Evans & Diehl Co.
Watertown—Watertown Elec., Inc.

Charlotte—Southern Elec. Service Co. Greensboro—Southern Elec. Serv. Co. Rocky Mount—Hammond Elec. Co.

Cincinnati-Cincinnati Elec. Equip. Electric Service Co.
Akron—A-C Supply Co.
Toledo—Romanoff Elec. Motor Serv.
Youngstown—Winkle Electric Co.

OKLAHOMA

Miami-Miami Armature Works Oklahoma City—Southwest Elec. Co. Tulsa—Smith-Milligan Electric Co.

Eugene—Kalen Electric & Mach. Co. Portland—Milwaukee Mach. Co.

PENNSYLVANIA

PENNSTLVANIA
Johnstown—Universal Elec. Mfg. Co.
Osceola Mills—Mid-State Elec. Eng. Co.
Philadelphia—Elec. App. & Repair Co.
Pittsburgh—Penn. Elec. Coil Corp.
York—Industrial Electric Company

SOUTH CAROLINA

Greenville—Southern Elec. Serv. Co. Spartanburg—Southern Elec. Serv. Co.

SOUTH DAKOTA

Siaux Falls—Electric Motor Repair

TENNESSEE

Columbia — Middle Tenn. Arm. Wks. LaFollette — Standard Arm. Works Memphis — Indus. Elec. & Supply Co.

TEXAS

IEAAS
Amarillo—G. F. Jones Elec. Co.
Beaumont—Elec. Mach. & Repair
Dallas—Industrial Elec. Equipment Co.
El Paso—B & M Machinery Co.
Fort Worth—Central Electric Co.
Houston—Roy A. Berentz Co.
Sweetwater—Sweetwater Electric Co.

HATU

Salt Lake City-Diamond Electric

VIRGINIA

Richmond—Wingfield & Hundley Roanoke—Virginia Armature Co.

WASHINGTON

Spokane-Lee F. Austin Company

Charleston—Charleston Elec. Supply Fairmont—Central Elec. Repair Co.

Wisconsin Rapids—Staub's Electric Co.
Milwaukee—Dieltz Electric Co.
Wasau—Electric Mort Service
Wisconsin Rapids—Staub's Elect. Whs.

Sold . . .

Applied . . .

Serviced . . .

by Allis-Chalmers Authorized Distributors, Certified Service Shops and Sales Offices throughout the country.



CONTROL - Manual, magnetic and combination starters; push but-ton stations and compoents for complete control systems.

TEXROPE - Belts in all sizes and sections, standard and Vari-Pitch sheaves, speed





types from 1/4 in. to 72 in. discharge

LLIS-CHALMERS CERTIFIED SERVICE SHOPS are independent service A shops which have met rigid standards for ability, experience, equipment and business integrity. They use factory approved methods and parts and do your work promptly at a fair price.

Of course, Allis-Chalmers Certified Service Shops give good service on any electrical equipment, of any make. Tear out this ad and save it, or write the name of the A-C Certified Service Shop nearest you in your address book. Allis-Chalmers, Milwaukee 1, Wisconsin.

Texrope and Vari-Pitch are Allis-Chalmers trademarks.

LLIS-CHALMERS




A ring-plate type valve for freon compressor made of Armco 17-7 PH Stainless Steel strip,

"17-7 PH"



Here is how the ringplate type valve is mounted and held in its retaining plate.

Replaces
Carbon Steel
In These
Ring-Plate Valves



This is the way the simple and efficient ring-plate valves operate in the compressor.

In a well-known line of freon compressors, Armco 17-7 PH Stainless Steel has proved its superiority for ring-plate valves and now replaces the carbon steel formerly used.

For these rings Armco 17-7 PH strip, 0.040-inch thick, is purchased in the cold-worked condition. After blanking, only a single low-temperature heat treatment is required for the desired hardness, since cold-working has already transformed the material, Resulting yield and tensile strengths are very high.

This is another case where physical characteristics and low-temperature heat treatment of this precipitation-hardening stainless steel produce a better product in fewer operations. Line check-valve plates and pump-valve discs are among other related applications that have been found most successful.

Two PH Grades

Armco 17-7 PH is made in sheets, strip, plates, bars and wire. Single and double low-temperature heat treatments are employed in hardening. There is also a special bar and wire grade, Armco 17-4 PH, that requires only a single low-temperature heat treatment. If you need good corrosion resistance and high strength combined with ready workability, investigate these two Armco Precipitation-Hardening Stainless Steels. Just a post card will bring you complete information.



alve

SSOF

17-7

trip.

GEORGE T. HOOK, Publisher TOM C. CAMPBELL, Editor

EDITORIAL STAFF

EDITORIAL STAFF
Managing Editor George F. Sullivan
Technical Editor Darwyn I. Brown
News-Markets Editor Wm. V. Pockard
Asst. Technical Editor W. G. Patton
Machinery Editor E. C. Beaudet
Asst. News Editor Theodore Metaas
Associate Editors: H. W. Van Camp,
F. J. Winters, R. L. Hatschek, W. B.
Olson, G. G. Carr; Assistant Editors:
E. C. Kellogg, J. J. Obrut; Art Director: Carl Cerminaro; Regional Editors:
K. W. Bennett, Chicago; R. D. Raddant,
Detroit; Robert M. Lorz, Cleveland;
J. B. Delaney, Pittsburgh; T. M.
Rohan, San Francisco; G. H. Baker, A.
K. Rannells, R. M. Stroupe, Washington;
Editorial Assistants: L. Brass, M. Perrone, C. M. Markart; Correspondents:
F. L. Allen, Birmingham; N. Levenson,
Boston; R. M. Edmonds, St. Louis;
James Douglas, Seattle: Jack Adams,
Los Angeles; F. Sanderson, Toronto; F.
H. Harley, London, England; Chilton
Editorial Board: Paul Wooton, WashIngton.

RUSINESS STAFF CHARLES R. LIPPOLD Director of Advertising Sales

Production Manager B. H. Hayes Director of Research Oliver Johnson Circulation Mgr. William M. Coffey Promotion Manager James A. Crites Asst. Dir. of Research Wm. Laimbeer

REGIONAL BUSINESS MANAGERS

Chicago 3..........Stanley J. Smith 10 S. LaSalle St. Franklin 2-0203 10 S. LaSaire St.
Cleveland 14..... Charles R. Lippoid
1016 National City Bank Bidg.,
Main 1-2263

Columbus 9. Ohio. olumbus 9, Ohlo.... Harry G. Mumm 1849 Franklin Park South, Evergreen 9245

Detroit 2..... 103 Pallister Ave Los Angeles 28......R. Raymond Kay 2420 Cheremoya Ave. Granite 0741 New York 17....C. H. Ober, C. T. Post 100 E. 42nd St. Murray Hill 5-8600 Philadelphia 39 B. L. Herman 56th & Chestnut Sts. Granite 4-5600 Pittsburgh 22......J. M. Spackman 814 Park Bldg. Atlantic 1-1831Paul Bachman Hartford 32-0486

OTHER EDITORIAL OFFICES

San Francisco 3...... 1355 Market St. Washington 4....National Press Bidg. Circulation Representatives: Thomas Scott, James Richardson.

One of the Publications Owned and Published by Chilton Co., Inc., Chest-nut & 56th Sts., Philadelphia 39, Pa.

OFFICERS AND DIRECTORS JOS. S. HILDRETH, President

Vice-Presidents: Everlt B. Terhune, P. M. Fahrendorf, G. C. Buzby, Harry V. Duffy: William H. Vallar, Treasurer; John Biair Moffett, Secretary; George T. Hook, Maurice E. Cox, Tom C. Campbell, Frank P. Tighe, L. V. Rowlands, Directors lands, Directors.

George Maiswinkle, Asst. Treasurer.

Indexed in the Industrial Arts Index and the Engineering Index.









Controlled Circulation Audit

E

Publications

Copyright, 1952, by Chilton Co. (Inc.)



FOUNDED 1855

Let's Nail It Down

66 TT should be noticed we gain nothing with Russia by conciliation or concession." These words were spoken 76 years ago by one of Britain's most brilliant Prime Ministers. They sum up our experience with Russia and Red China today.

Contrast them with the statement of Britain's Foreign Secretary Eden—made last week—that it is not necessary to "nail down" details on India's Korean resolution. America has learned by bitter experience that it is necessary to "nail down" all details before negotiating with the Communists.

Our government has not always been aware of the need for that simple but stark attitude. At Yalta, at Teheran and in Korea many details were not nailed down-much to the sorrow of American, Chinese and Korean people. Now is as good a time as any to tell the world that nailing things down is our policy.


With strong and experienced men joining Mr. Eisenhower's cabinet it is clear that "diplomatic" conciliation and concession at home and abroad are on their way out. People are sick and tired of pussyfoot diplomacy. It has gotten us nowhere.

Communists think nothing of dying for an idea—regardless of its depravity. Russians have always been firm believers that the end justifies the means. To this national inheritance Stalin has added the poison of communism. Together they make a combination that is hard to beat—and almost incomprehensible to Western Europeans and Americans.

The free world is not playing for marbles. We are players in a gigantic game where it is all or nothing. Conciliation, concession and appeasement are looked upon by Russia and Red China as weakness-and a gain for them when we are on the giving side. If we, or any other free nation, assume that Communists will act according to our rules we are in for one after another heart-rending defeat.

The new Administration will be content with nothing less than having things nailed down. That attitude is a must in a world where simple words have to be backed up with the will power to make them stick.


Tom Campbell



Here's how the CARBOFRAX hearth and side baffles looked after 15 months service—practically like new. Since silicon carbide is among the hardest of man made products, a hearth like this can take even the toughest abrasive wear and show hardly any signs of it.

This pusher-type, semi-muffle furnace is used for general heat treating. It is oil fired, operates 5 days a week at temperatures from 1350 F to 2100 F. Alloy trays carry the small parts, larger castings (up to 30 lbs) rest directly on the hearth.

In one year CARBOFRAX refractories saved over 30 days downtime



This same heat-treating furnace was able to turn out far more work, with far fewer shutdowns, simply by changing from one type of refractory to another. Originally equipped with 4" thick fireclay floor and side baffles, the output of this furnace was 6 tons a day (8-hr). At best, furnace efficiency was low, and there was rapid wear on the hearth caused by unevenly shaped castings being treated. Every month, a 2 to 3 day shutdown was required for refractory repairs. And 2 or 3 times each year, the hearth would be beyond repair and need complete replacement.

Then, CARBOFRAX silicon carbide refractories replaced the clay. Because they could be made thinner and because of their far greater thermal efficiency (CARBOFRAX refractories conduct heat 11 to 12 times faster than fireclay), furnace output

immediately jumped from 12,000 to 15,000 lbs a day. A gain of one full day's production every 4 days.

As for refractory maintenance, it all but ceased. 18 months after installation the CARBOFRAX hearth was in perfect condition, still hard and true. Maintenance up to this time: ZERO.

In other words, after 18 months the CARBOFRAX hearth had not only outlasted 3 fireclay hearths, but saved roughly 45 days of downtime. Plus the labor. Plus the materials. Plus the lost production. And, it was still in excellent condition, still helping to deliver an extra 7½ tons of work per week, every week.

To find how these refractories can benefit *your* furnaces simply write to Department B-112, Refractories Division, The Carborundum Company, Perth Amboy, New Jersey.

Use Super Refractories by

CARBORUNDUM

Trade Mark

"Carborundum" and "Carbofrax" are registered trademarks which indicate manufacture by The Carborundum Company.

Dear Editor:

Letters from readers

"A Businessman's Creed"

Sir:

I have no difficulty whatever in subscribing to the creed . . .

E. G. GRACE

Bethlehem Steel Co., Inc. Bethlehem

Sir:

I have taken the pledge to "A Businessman's Creed" so ably presented in your editorial, Nov. 13 issue.

J. SOMERS

Wyckoff Steel Co. Pittsburgh

Sir:

This is just 1000 pct right. I believe in it and will follow it.

C. M. WHITE

Republic Steel Corp. Cleveland

The Customer Again

We were very much impressed with the editorial, "The Customer Is Back," in your Nov. 6 issue.

We would like very much to have 20 tear sheets of this so that we could distribute them through our staff.

J. K. NOEL President

Victor Products Corp. Ranson, W. Va.

Satisfied Reader

ain

iths

on-

RO.

irth

hly Plus

ion,

eek,

ices

ion,

92 V.

GE

Several months ago I wrote to you pointing out certain problems that I had in reading THE IRON AGE Newsfront . . . I have been gratified to find, that from my standpoint, at least, a tremendous improvement has been made . . . I find it very much easier to keep my thoughts in line as I read it and, needless to say, enjoy it very much more. Congratulations on a fine job.

JOHN L. FULLER Manager of Research

The Reliance Electric & Engineering Co. Cleveland

Our thanks go to Mr. Fuller and to readers like him who take the time to pass along their ideas for improving the readability of The Iron Age.—Ed.

Push-Buttons

Please send us 2 copies of your article "Coal: Mining by Push-Buttons" which appeared in the Nov. 6 issue.

MARVIN C. MOFFETT Manager

Moffett Mfg. Co. Coatesville, Penna.

Shell Molding

In the Nov. 6 issue there is a listing of the high spots of the Metal Show held in Philadelphia last month.

On this list is mentioned a 12-station automatic shell molding machine capable of producing 700 molds per

Will you send me the name of the company so that I may request information from them direct.

H. L. BOUWKAMP Chief Manufacturing Engineer Imerican Seating Co. Grand Rapids

The 12-station automatic shell molding machine is made by Mechanical Handling Systems, Inc., Detroit.—Ed.

Bombs Away!

In your issue of October 16 you had a small article headed "Bombings— Plants Are Still There." I clipped this and sent it to an engineer who has had very extensive experience in the investigation of bomb damage in Germany, England and Japan, and who has witnessed and has information concerning the atomic tests in the desert and Pacific Islands. I think you will be interested in his reply which follows:

"The clipping from THE IRON AGE hits an all time high for misinformation and prejudiced line of reasoning. This is the sort of text one does not expect from a reputable industrial magazine. The U.S. Strategic Bombing Survey Publications are available and contain a detailed report by trusted representatives of the steel industry. Their conclusions are diametrically opposed to your aticle."

S. M. MARSHALL. Consulting Engineer

Stewart M. Marshall Palo Alto, Calif.

There seems to be a sharp difference of opinion between the letter above and one of the top Washington people responsible for the publication of the U. S. Strategic Bombing Survey. Iron Age's authority, who verified the story in the first place, was in military service during World War II be-hind enemy lines. He was later associated with Intelligence in a top-echelon post. He says news that the Air Force did not win the war single-handedly may be unpleasant to some Air Force enthusiasts—but it is nevertheless true. Now in an important government position, here is what he has to say about the authenticity of the Iron Age story which dealt mainly with the German steel industry and other heavy fabricating plants:

"The story is excellent. The facts are correct. The 2.5 pct figure of bombing damage has either hit it on the nose or is very close to it. Rust caused far more damage to steel mill equipment than bombs did. What you say about industry becoming more aware of the great dangers resulting from A-bombs is the truest thing in the world. There is too much complacency. People tend to think of a future war in terms of the last war."—Ed.



REDUCE ASSEMBLY TIME

Workmen gain time assembling with Pheoll screws, bolts, and nuts because they are accurately threaded, drive easily, seat rapidly, grip tighter—as-suring stronger assemblies, easier inspection and less rejects.



Save Costs... Increase Profits with these Pheall Fasteners

ASK ABOUT PHEOLL Machine Screws? Machine Bolts • Special Screws and Bolts
Cap Screws • Machine Screw Nuts • Wood
Screws† • Thumb Screws • Wood Thumb Screws Brass Washers Stove Bolts†

†Furnished in slotted and Phillips Recessed Head Types



Another Transfer-matic by Cross

188
Operations
On Tractor
Cylinder
Block

- * Mills distributor boss; drills, bores and spotfaces distributor hole; drills, chamfers and reams tappet holes; drills crankshaft and miscellaneous oil holes; drills and reams oil filler and dipstick holes; drills, chamfers and taps cylinder head, distributor mounting, oil pan and bearing cap holes; taps oil holes.
- * 72 pieces at 100% efficiency.
- * 22 stations—one for loading, 15 for machining, six idle.
- * Cross Machine Control Unit automatically stops machine when tools need changing and pre-set tools reduce down-time.
- * Gravity operated cam clamping.
- * Other features: Hydraulic and electrical equipment to J.I.C. standards with stranded wire; hydraulic feed; automatic lubrication.

Established 1898

THE CO IR 400 SA SA CO

DETROIT 7, MICHIGAN

Special MACHINE TOOLS

Fatigue Cracks

by William M. Coffey

Donnez-moi la plume—Voltaire

We quote from Stevenson: "We know nothing about writing a column; if told to do it, we'll lock ourselves in the bathroom; if made to do it, we'll keep the water running." This is our fifth Fatigue Crack. We started off poorly and have developed progressively worse. We thought last week's pitiful display would surely ease us off the spot. But no word yet from the front office. We're making certain this week, however. We call your attention to the following jokes:

1. A friend whose wife gave birth to twins was asked, "Boys or girls?" "I think one is a girl and one is a boy," the bewildered father answered, "but maybe it's the other way around."

2. Drunk: What's that crawling up the wall?

Bartender: A lady bug. Drunk: Gad, what eyesight.

We challenge anybody to come up with jokes that have so much wince-appeal. If you have any send them along. Maybe yours can get us fired. As Molière said-Le crayon est sur le table.

And Now . . .

. . we're going to put in a deserved plug for your f.f.j. We're not paid, you know, to sit around here and just tell jokes, no matter how new they are. We're going to talk about the Statistical Steel Facts Section that will be a part of the giant Annual Review Issue coming in January. This is the famous section that gives you so many handy facts and figures on metals, raw materials, machinery, markets, etc. A tour of the editorial department where this is being put together would show you some of our best men quietly going mad.

Eight different editors, plus artists, production men, printers. statisticians all have a hand in it. Old figures are being checked against new data: the latest information is being obtained from scores of different sources-trade associations, government agencies, our own research department. Many of the figures are coming from our own mail and phone surveys.

This whole process started six months ago and the by-word is ACCURACY. Progress charts line the walls, phones are constantly ringing, teletype machines are working 24 hours a day. As press-time approaches the tension mounts. An occasional scream is heard over the usual editorial din. Cigarette butts are hourly swept away by a picked squad of janitorial specialists. Ambulances are on the alert. How is it really done? We don't know, but somehow blue sky appears, order emerges and 700 sets of figures in 350 separate tables are packed into 96 pages of the Annual and on the way to you. It's a tremendous job. You'll find it of lasting, usable value. Quelle heure est-il?-

Reader Service Department

Thank you for your inquiry, Mrs. Vogel (Bridgeport, Conn.). annual review issue will be 1" thick. If placed under the shortest leg of your kitchen table :t should certainly take care of that nasty wobble. Suggest you ask Mr. Vogel first, however.


Puzzlers

Typical of many letters received from puzzle fans is this one from Jack Weiller of U. S. Steel, Chicago. He says, "Please send the solution to the 12 silver dollars puzzle before we beat our brains out." To all who have voiced like frustration we say, "At ease! The answer has been dittoed and is in the mail."

Mr. M. E. Pease of Derby & Co., Ltd., London, solved the October 16th puzzle, the 4-digitmultiplied - by - nine - thing. C. L. Ice of the Caterpillar Tractor Co., Peoria, came up with a most interesting solution, but it isn't quite right, old chap. The correct answer is 1089, 10989 and 109989.

Laurels for the week, however, go to George Tuer, Research Assistant at M.I.T., who came loaded with solutions to not only the above digit problem, but also the coconut and gambler's puzzles. Mr. Woody Ulrich of the Perfect Circle Corp., Hagerstown, Indiana, also solved the coconuts.

Here's a new one: Thirteen children dance in a ring holding hands. How many rings may they form without a child ever taking any other child by the hand twice?



Technique of Western Felt production and processing has built an enviable reputation for engineering precision. Chemical specifications must be perfectly met-parts from wool softness to rock hardness are cut to close tolerances. As an extremely versatile material Western Felts are resilient, flexible, compressible. They resist oil, water, heat, age-do not ravel, fray or lose shape. New uses found daily. It pays to depend on Western Felt.

Check Possible Uses for Your Product

- Excluding dirt, grit, dust Retaining lubricants Thermostatic insulation Isolating vibration
- Cushianing shock Padding, packing, seals Air and liquid filters Gaskets, channels, etc.
- Grinding, polishing, etc. Weight reduction
- · Instrument mounts

Sheet and Roll Felt Manufactured for Special Purposes and To Meet All S.A.E. and Military Specifications.





multiple 5 p l i n e d

This Super Service construction stands out in marked contrast to the previously accepted spring dive-key feed mechanism.

The 18 feed changes are made through selective sliding gears, every gear being of heat-treated alloy steel, and every shaft is multiple splined. The superiority of the splined shaft construction is readily seen, with ease of shifting from one feed to another, efficient transmission of power without fear of shearing a key, and lower maintenance cost over long period of time.

For further information on the many other patented exclusive features of the SUPER SERVICE RADIAL, write for Booklet R-29.





THE CINCINNATI BICKFORD TOOL CO. Cincinnati 9, Ohio, U.S.A.

Conventions & Meetings

- Nov. 28-30—Grinding Wheel Institute, annual meeting, Hotel Statler, Buffalo. Association headquarters, P. O. Box 64, Greendale, Mass.
- Nov. 30-Dec. 5—American Society of Mechanical Engineers, annual meeting, Statler Hotel, New York. Society headquarters are at 29 W. 39th St., New York.
- Dec. 2—National Warm Air Register Manufacturers Institute, annual meeting, Cincinnati. Institute headquarters are at 5 E. Long St., Columbus, Ohio.
- Dec. 2—Spring Manufacturers Assn., annual meeting, Biltmore Hotel, New York. Association headquarters are at 249 Main St., Bristol, Conn.
- Dec. 2—Society of Automotive Engineers, Inc., Hotel Statler, New York, Society headquarters are at 29 W. 39th St., New York.
- Dec. 3-4—National Warm Air Heating & Air Conditioning Assn., annual convention, Sheraton-Gibson Hotel, Cincinnati. Association headquarters are at 145 Public Square, Cleveland.
- Dec. 3-5—Society for Experimental Stress Analysis, fall meeting. Hotel McAlpin, New York. Society headquarters are at Central Square Station, Cambridge, Mass.
- Dec. 3-5-National Assn. of Manufacturers, Congress of American Industry Waldorf-Astoria, New York. Association headquarters are at 14 W. 49th St., New York.
- Dec. 4-5—American Institute of Mining & Metallurgical Engineers, Electric Furnace Steel Committee, Iron & Steel Div., annual conference, Hotel William Penn, Pittsburgh. Institute headquarters are at 29 W. 39th St., New York.
- Dec. 7-10—American Institute of Chemical Engineers, annual meeting, Hotel Cleveland, Cleveland. Institute head-quarters are at 120 E. 41st St., New York.


1953

- Jan. 11-13—Institute of Scrap Iron & Steel, Inc., annual convention, Hotel Commodore, New York. Institute headquarters are at 1729 H Street, Northwest, Washington.
- Jan. 12-13—Industrial Furnace Manufacturers Assn., Inc., midwinter meeting, Cleveland Hotel, Cleveland. Association headquarters are at 412 Fifth St., N. W., Washington.
- Jan. 15-17—National Tool & Die Manufacturers Assn., winter meeting, Sorrento Hotel, Miami Beach, Fla. Association headquarters are at 907 Public Square Bldg., Cleveland.
- Jan. 21—American Boiler Manufacturers Assn. & Affiliated Industries, mid-winter meeting, Hotel Cleveland. Cleveland. Association headquarters are at 1571 W. 117th St., Cleveland.
- Jan. 21-22—Steel Shipping Container Institute, winter meeting, Hampshire House and Hotel Pierre, New York. Institute headquarters are at 600 Fifth Ave., New York.
- Jan. 26-27—Compressed Gas Association, Inc., The Waldorf-Astoria, New York. Association headquarters are at 11 W. 42nd St., New York.
- Feb. 16-19—American Institute of Mining & Metallurgical Engineers, annual meeting, Statler Hotel, Los Angeles, Institute headquarters are at 29 W. 39th Street, New York.



LESCHEN

Flattened Strand • Non-Rotating • Slings Preformed • Round Strand • Locked Coil




DISTRIBUTORS IN ALL PRINCIPAL CIT



INCREASE and

LENGTHEN TOOL LIFE



The Pratt & Whitney Cutter and Radius Grinder sharpens almost every type of cutting tool accurately and economically. You will profit immediately by improved work quality, faster stock removal, longer tool life and reduced tooling costs.

Correct angles, radii and tangents are ground on both standard and special milling cutters; end mills; thread milling cutters; lathe, shaper and planer tools; form cutters; die sinking and cherrying cutters; and Keller cutters and tracer points. Straight or tapered flutes and ordinarily difficult jobs — like swinging accurate ball and radius noses on end mills — are easily handled.

The Pratt & Whitney Cutter and Radius Grinder is ruggedly constructed of the finest materials and will retain its initial accuracy through a long life and constant hard use. Two sizes accommodate flute lengths of 4½" and 10" respectively. To assure flute uniformity and concentricity, tools are ground as they are driven — from the shank and not from the centers. Operation is fast and easy.

The P&W Cutter and Radius Grinder is a sound investment in added machining efficiency and tool economy. Send today for more complete information. Write on your Company letterhead for Circular No. S455-6.



Y Lit the PRATT & WHITNEY

Citter and Radius
GRINDER



E

er ol fit er

er ly d. er ils a es

ne

d

d

te

A VERSATILE TOOL SHARPENING MACHINE

- GRINDS THEM ALL . RADII, ANGLES, TANGENTS.
 - STRAIGHT or TAPERED FLUTES.
 - SQUARE, RADIUS and BALL ENDS.

ECONOMICALLY - ACCURATELY

PRATT & WHITNEY


PRATTA WHITNEY
WEST HARTFORD, CONN. US

DIVISION NILES-BEMENT-POND COMPANY
WEST HARTFORD 1, CONNECTICUT, U. S. A.

First Choice (18) for Accuracy

BRANCH OFFICES. BIRMINGHAM - BOSTON - CHICAGO - CINCINNATI - CLEVELAND - DALLAS (The Stones Co.) - DETROIT - HOUSTON (The Stones Co.) LOS ANGELES - NEW YORK - PHILADELPHIA - PITTSBURGH - ROCHESTER - SAN FRANCISCO - ST. LOUIS - EXPORT DEPT., WEST HARTFORD

MACHINE TOOLS . CUTTING TOOLS . GAGES



of

ew facts for your file on U.S.S STAINLESS STEEL

Be sure you are acquainted with the physical properties and fabricating characteristics of grades available to you

Successful fabrication of Stainless Steels calls for a thorough knowledge of the physical properties and fabricating characteristics of each grade that is available to you. Since these properties and characteristics differ from those of plain carbon steel, modified working procedures are often required.

The complete line of U·S·S Stainless Steels covers a wide range of chemical compositions. However, these grades fall into two general classifications—the chromiumnickel Stainless Steels and the straight-chromium grades.

At the present time, nickel-bearing grades are restricted in their use by government order. For certain essential applications you are permitted to use these nickel-bearing

grades, but for the most part you will be working with straight-chromium Stainless Steels.

If your experience has been concentrated on the nickel-bearing grades, it is essential that you know the respects in which straight-chromium Stainless Steels differ. Fabricators who have used these straight-chromium grades as alternates to

nickel-bearing Stainless Steels report no difficulty in handling them when proper methods are used.

No matter what grades of Stainless Steel you are called on to work with, detailed knowledge of the physical properties and fabricating characteristics is a must for satisfactory performance and economical handling.



Detailed information in this FREE book

You'll find a wealth of information on all grades of U·S·S Stainless Steel in our book "Fabrication of U·S·S Stainless and Heat Resisting Steels." If you'd like a copy, write to United States Steel Company, Room 2806-T, 525 William Penn Place, Pittsburgh 30, Pa.

In addition, our representatives will be glad to assist you in selecting steels and fabricating methods where unusual conditions must be met. Feel free to ask for this help.

Type 430 Stainless successfully replaced nickel-bearing grade in this food serving equipment

Mo me Ste

Duke Manufacturing Company, St. Louis, Mo.—manufacturer of food serving equipment—has been using Type 430 Stainless Steel as an alternate material for many months now. In every case, the same

gage was used in Type 430 that had been used in nickel-bearing grades. On the basis of this experience, General Manager J. M. Johnson

reports:

"We find that Type 430 Stainless Steel is entirely satisfactory in appearance, durability and ease of maintenance for our Thermaduke food warmers and cafeteria counters. In every case, we have followed virtually the same fabricating techniques used with nickel-bearing






SHEETS · STRIP · PLATES · BARS · BILLETS · PIPE · TUBES · WIRE · SPECIAL SECTIONS

UNITED STATES STEEL COMPANY, PITTSBURGH - AMERICAN STEEL & WIRE DIVISION, CLEVELAND - COLUMBIA-GENEVA STEEL DIVISION, SAN FRANCISCO
NATIONAL TUBE DIVISION, PITTSBURGH - TENNESSEE COAL & IRON DIVISION, FAIRFIELD, ALA. - UNITED STATES STEEL SUPPLY DIVISION, WAREHOUSE DISTRIBUTORS




"We know how to says George Summer, we



w to handle big ones like this"

UNITED STATES STEEL MACHINIST



If you asked him to tell you about it in his own words, the conversation might go something like this:

YOU: "That's a mighty big forging you've got there. What is it?"

SUMNER: "It's a forged anvil base for a large drop hammer. We started off with a 500,000-pound ingot, but when I'm through with it, it'll ship out at around 300,000 pounds. Right now, it's 14 feet long, 6 feet wide, and 7 feet high."

YOU: "Must be quite a job handling it on the planer."

SUMNER: "Well, it's not exactly child's play. Setting it up correctly is very important. The weight must be spread out properly, because even on this big machine we work down to a few thousandths of an inch."

YOU: "But once you've made the set-up, the planer runs automatically, doesn't it?"

SUMNER: "Sort of, but no planer knows how to think. Take lubrication for instance. We have an automatic oil pump, gages and all that. But when you're cutting the short side of a piece, the table only takes a short stroke, and part of the ways don't get oil. If you keep that up, the ways get hot and they warp, and your accuracy is gone. So the operator—that's me—solves the problem by taking long strokes every once in a while, to spread the oil."

YOU: "In your opinion, what's the secret of making good forgings?"

SUMNER: "Good steel to start with—and good equipment to work it on. We have both. Then you've got to know what you're doing and take time enough to do it right. You can't leave anything to chance. That's the only way you can be sure your customer will get what he's ordered—a quality forging.

When you buy forgings from United States Steel Company, highly skilled men like George Sumner will work on them. We will match their knowledge and experience against the best in the land. For more information on U·S·S Quality Forgings, write to United States Steel Company, 525 William Penn Place, Room 2806-T, Pittsburgh 30, Pa.





New facts for your file on

11-5-5

to

to:

resi

pla

use

or I

me tra tio

few

the

wit

Irr

Bui

like

in o

vary

it hastee

SULV

repa Mar

4 tir

* Bu

EQUIPMENT DESIGNERS CONTINUALLY FIND NEW USES



Hot water tanks weigh 16% less, require 27% less steel, cost 15% less to ship when built with U·S·S COR-TEN steel.

By using U·S·S Cor-Ten steel in place of carbon steel in their famous "Dura-Stone lined" water heaters and water softeners, the Troop Water Heater Co., Pittsburgh, Pa., has been able to reduce shell thickness in some of these units as much as 31%.

This weight saving in the shell, reduces the total weight of the units about 16%, makes them more readily handled and easier to install. Shipping costs are 15% lower—a sizeable saving when distant markets are being served.

In fabrication, the manufacturer reports, U·S·S Cor-Ten steel offers further worthwhile advantages. Because it is stiffer it forms more smoothly in the bending rolls—fluting difficulties disappear. In welding, Cor-Ten steel behaves better than plain steel, does not tend to burn away under the arc, welding is easier and faster.



In cargo trailers designed for air transport U·S·S COR-TEN steel reduces weight 25%.

This general-purpose Army trailer must be able to carry 500 lbs. of cargo at high speeds over open country and to haul 750 lbs. on highways. That means it has to be very strong and exceptionally rugged. But it also has to be as light as possible so it can be readily air transported. To obtain maximum strength with minimum weight, U·S·S COR-TEN steel was used both in the main frame side members and in the towing yoke channels. Weight of these members was reduced 25%, yet they are much stronger, tougher, and have more resistance to fatigue, shock and corrosion than if they had been made of heavier carbon steel. This unit was built by Dunbar Kapple, Inc., Geneva, Illinois.

The reason . . . its proved ability

● When U·S·S Cor-Ten—the pioneer low alloy, highstrength steel—was originally developed we had in mind one particular field for its use, namely, to lift the costly drag of deadweight from every kind of *mobile* equipment.

So at first, U·S·S Cor-Ten steel was used to trim thousands of pounds of useless weight off freight and passenger cars. With it, trucks and buses were built lighter. So were mine cars, cranes, shovels, and earth moving machinery of all kinds. Because this equipment weighed less, it did more work, carried bigger loads, cost less to operate. It also lasted longer. Before long, Cor-Ten steel construction had earned a world-wide reputation for reducing weight and reducing costs in equipment that moved or was used to move other materials.

But design engineers, quick to see other possibilities in COR-TEN steel, rapidly expanded its application to all sorts of *stationary* equipment as well. They figured, and rightly, that when you can *save weight* in any product, you can *save steel*, and *save shipping costs*, too, both on the steel you use and in the manufactured product you ship.

In U·S·S Cor-Ten steel, equipment designers have found a material admirably suited for this purpose. Here is a steel, comparatively low in cost, having good working and welding



Hard working farm equipment built with U-S-S COR-TEN steel does more, lasts longer and is more dependable.

John Deere uses U·S·S Cor-Ten steel in the main axle and in the tractor hitch frame of its famous No. 12-A Combine. Without increasing weight, Cor-Ten steel gives these vital parts maximum strength, maximum toughness and what is of special importance, ensures high fatigue resistance—50% greater than that of plain carbon steel. Racking and twisting strains that could easily cause damage are safely absorbed by Cor-Ten's higher endurance limit . . . and the equipment stays on the job.

cause damage are safely absorbed by COR-IEN'S nigner endurance limit . . . and the equipment stays on the job.

This application is typical of COR-TEN steel's increasing use in farm equipment such as feed trucks, grain trailers, fertilizer spreaders, farm wagons and stake bodies. As one manufacturer puts it, "Because farm equipment takes terrific abuse in the field and is generally exposed to the weather without any protection whatsoever, we have found high-strength steel construction a 'must'."

U·S·S HIGH STRENGTH STEELS
U·S·S COR-TEN · U·S·S MAN-TEN · U·S·S TRI-TEN

S AIGH STRENGTH STEELS



FOR U-S-S COR-TEN HIGH STRENGTH STEEL

to reduce weight, increase durability and cut costs.

properties, with which they can safely and economically reduce weight - but which has the further important advantage of great durability. For Cor-Ten steel not only has a yield point one and a half times that of carbon steel but it has 50% higher fatigue strength, offers superior resistance to abrasion and impact, and in addition has unusually high resistance to atmospheric corrosion-4 to 6 times that of plain steel.

ity

nigh-

lone

ag of

hou-

nger

were

ry of

more

sted

rned

icing

other

es in

sorts

htly,

save 1 use

ound steel.

ding

-TEN

able.

and

bine.

parts pecial that

easily


rance

se in readnd is atso-ust'.''

As a result, U.S.S Cor-Ten steel is now being extensively used, not only in mobile equipment, but to reduce the weight, or to increase the life, of water heating tanks, shipping containers, storage racks and bins, pallets, refrigerator sheets, metal awnings, smoke stacks, shower partitions, floor plates, transformer housings, pole line hardware etc. New applications are constantly being turned up.

In these products, every pound of weight saved has meant fewer pounds of metal to buy-fewer pounds to move-and fewer pounds to ship. That makes for SAVINGS all along

If you want to reduce the weight of your equipment without reducing its durability-or to increase its durability without increasing its weight -get more information by sending for our booklet on U.S.S Cor-Ten steel.



Irrigation and drainage pumps, built of U-S-S COR-TEN steel, operate without repairs, last 4 times as long.

Built by the Couch Manufacturing Co., numerous turbine pumps like this, with a capacity up to 80,000 gallons per minute, have been in operation since 1938 in the South Florida water control develop-

Installed in silty water containing tannic and sulphuric acid in varying amounts, pumps are alternately submerged in the water and exposed to the atmosphere. Under these severe conditions, it has been necessary to make repairs to pumps built of plain carbon steel* which had corroded after 5 or 6 years.

In contrast, all pumps built of U·S·S Cor-Ten steel are still in ervice—during 14 years' operation have never been pulled out for pairs of any kind. "And," says W.W. Kerr, President of Couch lanufacturing, "they are in apparent good condition and should asily last another 10 years. I place their life expectancy as at least times that of carbon steel."

Built during the war when COR-TEN steel could not be obtained.



Portable derrick built 5 ft. higher than before, weighs 800 lbs. less-brake drum lasts 5 times longer-when COR-TEN steel replaces carbon steel.

By taking advantage of U·S·S Cor-Ten steel's greater strength and durability, Hopper Ma-chine Works, Inc., Bakersfield, Calif., were able to increase the height of this portable drilling rig from 47 feet to 52 feet and at the same time reduce derrick weight 800 lbs.

Impressed by Cor-Ten steel's performance in the derrick structure, the manufacturer decided to utilize its superior properties elsewhere. By using 1" COR-TEN steel plates in place of both mild steel and cast steel for brake drums, drum life was increased approximately 5 times.





GET COMPLETE INFORMATION. MAIL THIS COUPON!

F. H. Same	4
	Uni
100	525
	Pitt
-	Plea
0	Nar
The state of the s	Cor
I Loc	Ade
	City

ited States Steel Company William Penn Place, Room 2806-T sburgh 30. Pennsylvania

ase send me a copy of your book "U-S-S COR-TEN."

UNITED STATES STEEL COMPANY, PITTSBURGH - AMERICAN STEEL & WIRE DIVISION, CLEVELAND - COLUMBIA-GENEVA STEEL DIVISION, SAN FRANCISCO NATIONAL TUBE DIVISION, PITTSBURGH . TENNESSEE COAL & IRON DIVISION, FAIRFIELD, ALA. - UNITED STATES STEEL SUPPLY DIVISION, WAREHOUSE DISTRIBUTORS

New facts for your file on U.S.S GARILLOY STEELS

U·S·S CARILLOY steel springs soak up 8 million lb.-ft. torque!

Alloy springs cushion tremendous mechanical shocks in 200-ton short-circuit generators . . . save expense of forgings

 In testing high-voltage circuit breakers, engineers at General Electric Company intentionally short-circuit two huge motor-driven generators. Each of these test generators is normally rated at 125,000 kva, but provides short-circuit currents as high as 182,000 amp, instantaneous peak of the offset wave, corresponding to about 1,625,000-kva rms symmetrical short-circuit duty. Such operation causes tremendous mechanical stresses to build up inside each machine. These stresses create a torque that tries to twist loose the 200-ton stator assembly.


But no damage is done! These powerful machines are mounted on U·S·S Carilloy steel plate springs that cushion the shock and then damp out any vibrations that follow. The springs must absorb these terrific shock torsion loads as often as 40 times an hour; so a tough, very durable steel is needed.

Forged springs were considered first. But GE engineers, with the cooperation of United States Steel metallurgists, found that a rolled alloy steel, U·S·S CARILLOY 4340, provides the required mechanical properties at much lower cost. This steel is

tough, even though extremely hard, and it assures good endurance at 40,000 psi. as required in this application. In addition, it is easy to heat-treat.

This Carilloy steel is giving excellent service. Under the most severe short circuit, developing a whopping 8 million lb.-ft. of torque, frame rotation is about ½" each way at the point of attachment of the springs. And the axial centerline of the machine stays within 30 mils of its normal position. These movements are sufficient to cushion the shock effectively.

Any time you need a steel that will provide high strength and toughness, superior resistance to shock and torsion with minimum weight, or any combination of these properties, look for a Carillov steel. Experienced U·S·S metallurgists will gladly help you choose the one best suited to your requirements.



UNITED STATES STEEL COMPANY, PITTSBURGH - COLUMBIA-GENEVA STEEL DIVISION, SAN FRANCISCO
TENNESSEE COAL & IRON DIVISION, FAIRFIELD, ALA. - UNITED STATES STEEL SUPPLY DIVISION, WAREHOUSE DISTRIBUTORS, COAST-TO-COAST.
UNITED STATES STEEL EXPORT COMPANY, NEW YORK.

It Takes MORE
than a
Collection
of Parts



To Make A
VICKERS
CUSTOM
BUILT
POWER UNIT

e-a

iy ie

of

of

ck

h-

nd.

Improve and Simplify Hydraulic Design

Reduce Installation and Maintenance Costs

A Vickers Custom Built Power Unit is much more than a collection of parts...just as the machines you build are more than the castings, shafting, gears, motors, etc. that go into them.

The Vickers Unit is designed and built with the "know-how" obtained during more than a quarter century of experience in practically every kind of hydraulic operation, plus a thorough understanding of your needs. It is built exactly to your individual requirements. All necessary pumps, valves, intermediate piping, oil reservoir, motors, controls, etc., are in one compact and self-contained "package". It includes all needed hydraulic accessories such as oil filters, air cleaners, oil level gauges, fittings, etc. Hydraulic connections may

be grouped in a conveniently located manifold.

The result is simplification of hydraulic design and important savings in installation and maintenance costs. Vickers undivided responsibility for the entire hydraulic control system is another important advantage to both the machine builder and his customer. • Write for new Bulletin 52-45.

VICKERS Incorporated

DIVISION OF THE SPERRY CORPORATION


1420 OAKMAN BLVD. . DETROIT 32, MICH.

Application Engineering Offices:

ATLANTA • CHICAGO (Metropolitan) • CINCINNATI • CLEVELAND
DETROIT • HOUSTON • LOS ANGELES (Metropolitan) • NEW YORK
(Metropolitan) • PHILADELPHIA (Metropolitan) • PITTSBURGH
ROCHESTER • ROCKFORD • SEATTLE
WASHINGTON • WORCESTER

605

ENGINEERS AND BUILDERS OF OIL HYDRAULIC EQUIPMENT SINCE 1921



Finished steel quality control is the goal of every Steel Maker. Steel finishing under precise atmosphere control is the answer. It assures premium quality at lower ultimate cost. Some applications of these "Surface" generators are described below.

BRIGHT ANNEALING, STRIP

Out at high speeds in this vertical strand furnace. NX or HNX atmosphere can be used.

— Batch bright annealing of coiled strip is accomplished in lift cover furnaces of the type shown. In this single row installation, NX protective atmosphere is used.


CARBON CORRECTION, BAR STOCK

Batch carbon restoration utilizes this lift cover, carbottom type furnace for simultaneous skin recovery and clean annealing. Here again, the reactive carbon medium is enriched RX atmosphere and the protective medium is NX atmosphere.

Continuous production carbon restoration of bar stock is accomplished in this roller hearth furnace in conjunction with clean annealing. Enriched, RX atmosphere, is used as the carburizing medium and NX atmosphere for surface protection.

BRIGHT ANNEALING, SHEET

Continuous bright annealing of stainless clad sheet in this disc hearth furnace with special rapid air quench chamber utilizes a protective atmosphere of DX gas.



The HNX generator, shown here, is one of the five principal atmosphere generator types—RX, DX, NX, AX—built by Surface Combustion. They represent the engineering skill and 'know how' of 40 years standing in serving the nation's steelmakers. They make finished quality steel a practicality.

For complete information on the applications of these atmospheres, write for Bulletin S-52-3.

YOU GET Surface

CONTROLLED ATMOSPHERE

FURNACES AND GENERATORS

Controlled atmospheres have opened up endless possibilities throughout the Steel Industry for the safeguarding of product quality and increasing customer acceptance. Case carburizing...dry cyaniding...homogeneous carburizing...carbon restoration...clean hardening... bright or clean annealing... galvanizing... are among the important finishing operations, which come under its influence. These can be accomplished faster and with far better results using controlled atmospheres than by direct heating methods.

'Surface' has contributed materially to the success of controlled atmosphere in the Steel Industry. 'Surface' Furnaces and Generators have given controlled atmosphere processes full production status at a time when increased tonnage plus an improved product are vital.

Into the design and construction of 'Surface' Controlled Atmosphere Furnaces and Generators have gone the best engineering talent available. Each atmosphere type has been developed to 'shoulder' a definite set of responsibilities in the treatment of steels (or non-ferrous metals) and to do its job well. Nothing has been overlooked to make 'Surface' the "buy word" in dependable controlled atmosphere equipment and its applications.

'Surface', acknowledged as a great name in the Steel Industry for over a quarter-of-a-century—with hundreds of successful Steel Mill installations to its credit—invites you to share in its experience and 'know how' in the interest of quality . . . an improved product at worthwhile savings.

Maker. nswer. me apbelow.

d in lift

bottom nealing.

osphere

is ac-

arburi-

in this

SURFACE COMBUSTION CORPORATION . TOLEDO 1, OHIO


FOREIGN AFFILIATE COMPANIES

BRITISH FURNACES LIMITED—CHESTERFIELD STEIN & ATKINSON, LTD.—LONDON STEIN & ROUBAIX—PARIS, LIEGE AND GENOA WILL L. SMITH, S.A.—BUENOS AIRES



NIAGARA SHEARS

at General Sheet Steel Co., Detroit, Mich.



POWER SQUARING SHEARS

after shearing thousands of tons of steel of all kinds

LET'S LOOK AT THE RECORD!

NIAGARA
Shears are designed for HIGH VOLUME SHEARING ACCURACY DEPENDABILITY LOW MAINTENANCE COSTS

Write for Bulletin 69

SERVICE RECORD

6

Niagara Shears 1945-1952

Total Cost of Repairs

less than \$20 per shear per year


GENERAL SHEET STEEL CO.

NIAGARA MACHINE & TOOL WORKS • BUFFALO 11, N. Y.

Manufacturers of Presses, Shears, Machines and Tools for Plate and Sheet Metal Work

DISTRICT OFFICES: DETROIT • CLEVELAND • NEW YORK • PHILADELPHIA

Dealers in principal U.S. cities and major foreign countries



"We can service this Drive Team faster because all parts are more accessible"

"I'm the fellow who has to live with the gearmotors and controls that we purchase. That's why I'm interested in what it takes to get at the working parts. I don't want equipment that only a contortionist could service.

"Take a look at this Westinghouse Combination Life-Linestarter. It offers both circuit and motor protection all in one enclosure. Every screw can be reached from the front—every part can be removed from the front. This saves me considerable time and effort when I have to service the device or change a heater. Installing these starters is simpler too, thanks to the straight-through wiring and pressure-type connectors. I don't have to guess at wire lengths or hunt for terminals.

"Now look at this Westinghouse Life-Line Gearmotor. The split-case construction really is the answer to getting at the working parts. The upper-half case is easily removed for inspecting gears and bearings. I don't have to disturb the alignment or drain the oil. Removing the motor is a cinch. And look! There is no shimming or motor coupling to realign.

"We've found it's easier to live with our drives when we specify Life-Line Gearmotors and Life-Linestarters." You can do the same. Just call your local Westinghouse representative for full details, or write direct to Westinghouse Electric Corporation, P. O. Box 868, Pittsburgh 30, Pennsylvania.

J-07304





Baker Multi-Operation Machine utilizing standard Baker 7½ x 16 and 15 x 16 units and a 72" six-station power indexing table, performs drilling, chamfering, boring, counterboring, and tapping operations on clutch housings at the rate of 80 partsper-hour at 100% efficiency.

| STATION No. 2 | VERTICAL UNIT | No. Full thru 2 holes | 15/32 | Drill thru 1 hole | 15/32 | Drill thru 2 holes | 13/32 | Drill thru 3 holes | 13/32 | Drill thru 3 holes | 13/32 | Drill thru 2 holes | 13/32 | Drill thru 3 holes | 13/32 | Drill thr

Baker Special Drilling Machines, composed of standard Baker units arranged to suit each individual problem, are designed for productivity. Units arranged in vertical, horizontal and angular planes perform multiple operations faster...better... automatically... with greater accuracy and efficiency. Consult Baker engineers for a better solution to your drilling problems.

... SINCE 1867


BAKER BROTHERS, INC. Toledo, Ohio

DRILLING... TAPPING... KEYSEATING and CONTOUR GRINDING MACHINES

Quick facts about

MORGAN

WIRE BLOCKS



- Air cooling
- Safety devices
 Let us give you the full story



MORGAN-CONNOR WIRE MACHINES

MORGAN CONSTRUCTION COMPANY . WORCESTER, MASSACHUSETTS

November 27, 1952

2

MAGWHWIE



PREformed . . . Internally Lubricated

WIRE ROPE

for all equipment

From Macwhyte's complete line of a thousand and one sizes and types you get rope best suited to your equipment, designed, PREformed, and internally lubricated to provide long, safe service. (Ask for Catalog G-15.)



Wire Rope SLINGS

for lifting and moving materials and equipment in production or maintenance.

There are hundreds of types and sizes of Macwhyte Flat-Braided, Round-Braided, Single-Part, and Grommet Slings. All are custom made in length, capacity, and flexibility to meet your needs. (Ask for Catalog S-8.)



Wire Rope ASSEMBLIES

for machine parts, controls, and operating devices.

Macwhyte Safe-Lock wire rope assemblies are made to order in length, strength, and flexibility desired. Terminals are permanently attached to one or both ends. There are many standard types. (Ask for Catalog 5201.)

Macwhyte Company, 2011 Fourteenth Avenue, Kenosha, Wis. Manufacturers of Internally Lubricated PREformed Wire Rope, Braided Wire Rope Slings, Aircraft Cables and Assemblies, Monel Metal, Stainless Steel Wire Rope and Wire Rope Assemblies. Mill depots: New York • Pittsburgh • Chicago • St. Paul • Fort Worth • Portland • Seattle • San Francisco • Los Angeles • Distributors throughout U.S.A.

Catalogs are available on request to Macwhyte Company or authorized distributor.




1016 SW

THE IRON AGE Newsfront

- CONTINUOUS CASTING OF STAINLESS and alloy steels will be undertaken by Atlas Steels Ltd., Welland, Ont. The continuous casting machine, of 100 sq in. cross-section, was ordered from Continuous Metalcast Co., Inc. It is expected to be operating by Fall of 1953.
- INDUSTRIAL NOISE SUPPRESSION is getting more attention. It's recognized as a factor in worker morale. Potential benefits have persuaded companies to attack the problem scientifically. Advantages often go beyond improvement in worker efficiency.
- GOVERNMENT BAR PURCHASES are expected to continue an upward curve through the second quarter, steel sources say. Materials referred to are shell quality bars.
- BIGGER AND FASTER STAMPING PRESSES are coming up. Where big presses have been operating at six strikes per min, new presses are expected to operate at eight to ten strikes per min.
- LOWER AUTOMOBILE PRICES MAY BE POSSIBLE when and if controls are lifted. Higher production schedules, smoother flow of supplies, absence of expensive conversion deals will lower unit cost substantially. Price cutting could follow tough competition.
- BACKLOG OF WAREHOUSE DEMAND is expected to sustain tight steel market in midyear. One warehouse firm is reportedly holding \$11 million cash earmarked to rebuild depleted steel inventories.
- CONCERN OVER WIDE TENSILE STRENGTH SPREAD of available commercially pure titanium has been expressed by the aircraft industry. The industry considers 20,000 psi tops. But materials producers have trouble limiting the spread to less than 40,000 psi.

 A limit of 90,000 psi ultimate tensile may be set for commercially pure material which is to be spotwelded.
- QUICK TREATMENT FOR BURNS AND CUTS suffered by workers in industry is possible through use of an aeroplast dressing tested by the Air Force. Inexpensive and easy to apply, the transparent plastic forms a coating 0.005 in. thick.
- SHORTAGE OF SKILLED AND SEMISKILLED MEN IN THE CLEVELAND AREA is forcing relaxation of hiring standards. Employers, now recruiting labor outside the area, may use more women, older persons, handicapped and inexperienced workers. Trainee programs are hampered by lack of men in the 18 to 25-year range.
- CIO UNIONS STILL FIGHT technological improvements even though the late
 Philip Murray is on record as saying they have made 20 million
 jobs in steel. CIO unions fight automatic machinery, force
 building of new plants in new areas rather than modernization
 of existing facilities.
- LACK OF ADEQUATE DIESINKING CAPACITY is a major drawback in the Air Force heavy press program. Existing capacity is 40,000 to 50,000 tons annually, mostly in smaller sizes. Annual requirements when the heavy press program gets rolling are expected to be from 50,000 to 75,000 tons.



6 types . . . for savings in services up to 3000F

Because of their quick-heating and low-heat transfer characteristics, Johns-Manville Insulating Fire Brick are efficient fuel-savers for use at operating temperatures up to a full 3000F on the insulation.

Each type of J-M Insulating Fire Brick has the correct balance of thermal and physical properties that assures maximum economies within a specific temperature range. All types are quick-heating...

operating temperatures are reached in a short time, thereby saving fuel.

Identical materials can also be obtained in large size units known as Johns-Manville Insulating Fireblok. Fireblok have the same properties as the brick, but are made in extra large sizes for added construction economies. The large units can be installed faster . . . require fewer joints and less bonding mortar. During rebuilding or re-

pair, furnace down-time is appreciably shortened with Fireblok construction.

A Johns-Manville insulation expert will gladly explain the advantages and economies of using J-M Insulating Fire Brick and Fireblok for refractory linings or as back-up insulation behind other refractory protection. Write to Johns-Manville, Box 60, New York 16, N. Y. In Canada, write 199 Bay St., Toronto 1, Ontario.

	Types of Insulating Fire Brick and Fireblok														
nsity, lb per cu ft ansverse strength, psi ld crushing strength, psi near shrinkage, percent versible thermal expansion, percent	JM-3000	JM-28	JM-26	JM-23	JM-20	JM-1620									
Temperature limit	†3000F	†2800F	†2600F	†2300F	†2000F	‡2000F †1600F									
Density, lb per cu ft	63-67	58	48	42	35	29									
Transverse strength, psi	120	120	125	120	80	60									
Cold crushing strength, psi	300	150	190	170	115	70									
Linear shrinkage, percent	*0.8 at 3000F	4.0 at 2800F	1.0 at 2600F	0.3 at 2300F	0.0 at 2000F	0.0 at 2000F									
Reversible thermal expansion, percent	0.5-0.6 at 2000F	0.5-0.6 at 2000F	0.5-0.6 at 2000F	0.5-0.6 at 2000F	0.5-0.6 at 2000F	0.5-0.6 at 2000F									
500F	3.10	2.00	1.92	1.51	0.97	0.77									
	3.20	2.50	2.22	1.91	1.22										
1500F 2000F	3.35	3.00	2.52	2.31	1.47	1.27									

*24-hr Simulative Service Panel Test; all others 24-hr soaking period.

†Back-up or exposed.


\$Back-up only.



Johns-Manville



INSULATIONS



Sheaffer's new Snorkel Pen created a sensation when it was introduced to the trade. Using air alone, the pen is emptied, cleaned and refilled through the filling tube of the Snorkel Pen with a one-stroke touch-down action.

as

te

Designing the two brass "lungs" comprising the plunger-siphon mechanism called for considerable ingenuity. They must be light in weight, stiff and strong, easy to form and easy to polish and plate.

Formbrite* met all of these requirements and more, With a metal thickness of only .0058", the 2" long cylinders are formed in multiplunger presses in eight successive operations—without annealing of any kind.

Formbrite's superfine grain resulted in a harder, stronger, longer-lasting product with savings up to 50% in polishing costs.

Surprisingly, Formbrite, with all the plus values it offers over conventional drawing brasses, costs no more. See the reverse page for another application of Formbrite. And write for Publication B-39, addressing The American Brass Company, General Offices, Waterbury 20, Connecticut. In Canada: Anaconda American Brass Limited, New Toronto, Ontario, Canada.

*Reg. U.S. Pat. Off. 5295

Cups like this, blanked and formed in one operation from Formbrite strip 1116 x .0058, are magazine-fed into multi-plunger presses. Eight successive operations produce the sleeves illustrated at top of page without annealing. Sleeves at left are finished, ready for chromium plating.

Formbrite ANACONDA PRODUCT

Made by The American Brass Company

You can do this
better
cheaper
faster
If the METAL IS
Formbrite



Comu

da

th

co

th

Pr

ter

ble

ca

de

mo

ex

lin

vo su the Ar

N




In the pressroom of a supplier, the back of a military brush is blanked from Formbrite red brass strip. Since The American Brass Company introduced Formbrite* as a superior drawing brass, scores of stamping shops, polishing and plating rooms throughout the country have changed their thinking.

Comparative tests prove conclusively that the superfine grain structure of this specially processed forming brass means stamped and formed products that are stronger, harder, "springier" and more scratch-resistant. Yet the metal is so ductile that it can be readily formed, drawn and embossed.

Timestudies made of finishing operations have shown that a bright, lustrous finish can be obtained by a simple "color buffing" operation in half the time previously required.

That's why we say you can do it better, cheaper and faster with Formbrite. Millions of pounds of Formbrite sheet and strip have been produced and economically fabricated into hundreds of different products. Want a sample—and more information? Address The American Brass Company, General Offices, Waterbury 20, Connecticut. In Canada: Anaconda American Brass Limited, New Toronto, Ontario, Canada.

"Reg. U.S. Pat. Off.





Formbrite ANACONDA PRODUCT

Made by The American Brass Company



TARIFFS: Do You Want Them Low or High

New Congress must decide on tariff policy by extending duty act... Which industries want a sound tariff wall and which want no wall... How the sides will argue—By T. Metazas.

Whether an industry is for or against tariffs depends on what products it makes, how it makes them, and where they are sold.

Policies of tariff regulation and free trade have been adopted by industry. Economic necessity often shapes them. And they will be exerted on the fresh Republican Congress of next January which must decide on another extension and modification of the Trade Agreement Act of 1934. Since TAA extension is likely and some modification is possible, it would serve manufacturers to consolidate their views on tariffs and then make them felt.

Bones of Contention—The issues will be: (1) Consistent pursuit of an unrestricted or free market through tariff deals with foreign countries. Executive tariff authority would remain with the President, as opposed to (2) Maintenance of a continuing and flexible tariff to safeguard the American market for American manufacturers. The power of duty determination would revert to a more potent Tariff Commission.


Participants in this sometimes extravagantly worded debate which promises world prosperity on one hand and an economically ruptured America on the other are lining up their logic for Congress.

Those industries generally favoring unrestricted trade have such fabulous mechanization in their mass production that high American costs of labor are offset. A free market is wanted to unburden their surplus goods and get raw materials. These expanded industries feel they can compete anywhere on earth.

Costly Manhours—That group seeking continuing tariff protection wants to preserve the home market against unfair foreign competition, methods, and very cheap foreign labor. Inherent in the manufacture of their products is the use of proportionately more

Smoot-Hawley Tariff Act of 1930. TAA gave the President the right to enter foreign trade agreements and to lower or increase duties up to 50 pct. How the tariff trend went depended on interpretation—and the Democratic regimes chose the downward path.

The TAA permitted our entrance into the General Agreement on Trade and Tariffs, an international tariff negotiating body. A most-favored-nation clause auto-



manhours per unit. Mechanization has only partially been able to offset high wage costs.

Today relatively few industries seriously suffer because of high imports. However, protection is sought against future competition and depressed economic times. A flexible and scientific tariff should shift to fit the need and create fair price competition with imports, they say.

The systematic destruction of America's high tariffs began with the Trade Agreement Act of 1934 —really an amendment to the matically extends to all member nations any tariff privileges negotiated by any two parties. We can wriggle clear of specific duty agreements but the other side can impose equivalent retaliatory duties.

High Tariff—Under the 1930-33 period of Smoot-Hawley, average ad valorem equivalents of U. S. duties on taxable imports were 52.8 pct. As of Aug. 1, 1951, this rate had fallen to 12.5 pct. Not only that but almost 60 pct of today's imports get in free. The U. S.

now cannot be called a high tariff country.

The major premise of the "free traders" is that overall American industry has reached such maturity it needs no tariff protection. To impose tariffs is to restrict trade and safeguard tired industries from their own inefficiency. This is contrary to the principle of competition, lowering the world's standard of living and promoting narrow, walled markets, they believe.

For example, the tariff system in Europe has made a large accessible market unavailable to industries there. Mass production of the American stature has been impossible. on foreign imports. Heavier and heavier imports into the U.S. must be balanced by heavier and heavier exports of manufactured goods. If foreign markets are closed to us then we will be spending more than we'll be taking in.

Free traders would also like to see abandonment of foreign discrimination against dollar imports. Nations overseas now set quotas to limit purchase of U. S. goods.

Scientific Tariff—Who are those seeking maintenance of protective tariffs? An influential group are members of the American Tariff League. They propose a flexible and scientific tariff. ATL believes the economic muddle of the world

important diversity of American production and industries essential to war.

ATL maintains the American high standard of living is at stake. Claims that the dollar gap is undermining Europe brings this reply: America can import so much and no more. It is importing as much as it needs, tariffs or no tariffs.

And just how much of a disparity can there be between our exports and imports when it's considered a great part of our exports are free? For that portion there is no drain on Europe's dollar reserves. In any event, imports are determined not so much by tariffs but mainly by America's needs.

H

il

fe

II

d

tl

n

t

Middle of Road—Straddling the fence is a group which does not subscribe fully to either attitude.

This group realizes that swift expansion of free trade is impossible even if desirable. European nations are generally not able to participate beyond a certain extent. Until the time's propitious a moderate tariff system is needed.

Free trade should come through long-term evolution — with the U. S. as the hard-headed protagonist. Some middle-of-the-roaders believe that if the American productive plant were turned loose in a free market the world would soon belong to Uncle Sam. For this reason. Europe and others fear economic domination by the U. S.

European motive in seeking free trade is the need for dollars—and we can't buy all they must sell us to balance their books. Some foreign countries are only now starting on the road to industrialization. A free market would destroy young industries, it's argued.

Restrictive Gimmicks—Although European countries strive for that low tariff look, in many instances it's just gloss. They can detour around GATT agreements on keeping tariffs fixed by imposing embargoes, quotas, and controlling exchange. Result is letting in just so many imports—and no more.

Historical Traffic Levels

On total imports, over the last 40 years, the average ad valorem equivalents of U. S. duties have been:

	Average	rates on
PERIOD OR YEAR	DUTIABLE	FREE AND
1913-22 Underwood Act	27.0 pct	9.1 pct
1922-30 Fordney-McCumber Act	38.5 pct	14.0 pct
1930-33 Hawley-Smoot Act	52.8 pct	17.7 pct
1939 Hawley-Smoot Act	37.3 pct	14.4 pcf
1949 Hawley-Smoot Act	13.8 pct*	5.7 pct*

* Percentage of customs receipts to value of imports. (Source: U. S. Tariff Commission, U. S. Dept. of Commerce.)

They claim free trade would bring more imports to the U. S., make it possible for more exports. The dollar trade gap between foreign nations and America might be narrowed by permitting others to earn our money. Charity shipments abroad waste our substance and create higher taxes.

Perpetual Motion — Only the U.S. can be the aggressor in building unrestricted trade, say the free traders. No one else is economically capable. And to do so our tariff system must be lowered wherever possible. To retain it permanently is to make it self-perpetuating.

America is reaching an era in which its expanded industries and its decreasing natural resources will make us eternal dependents is not easily solved.

Wholesale concessions in trade pacts would be premature, in any case, and would leave us vulnerable to unfair competition. Tariffs are the mildest and most impartial regulators of trade in a world where far more devious devices are used, ATL contends.

ATL opposes the current rigid tariff system. Rates set by agreement cannot be changed until the danger point is reached. Aim of a flexible tariff would be merely to make foreign goods competitive with home products.

Import Gap — The tariff, says ATL, should protect against desperation dumping of imports. It must offset much cheaper wage rates and unfair and monopoly selling. Duties should protect the

WAREHOUSES: Expand With Demand

Growth of steel needs means growth in distribution . . . Lack of personnel and working capital plus short inventory are main hurdles . . . Warehousemen confident—By K. M. Bennett.

Growth of the warehouse industry to meet the expanded steel needs of the nation has lost none of its post-war momentum.

11111

en-

an

ke.

un-

his

80

rt-

or

ity

rts

red

are

no

68.

de-

iffs

the

de.

rift.

os-

ean

to

ex-

ous

led.

gh

the

go-

ers

ro-

in

uld

his

ear

S.

ree

nd

US

or-

rt-

za-

roy

igh

hat

ces

THE

en-

m-

ing

ust

GE

Another link in the chain of the many new warehouses will be that of U. S. Steel Supply Co. It will open its fifteenth warehouse at Houston, Tex., on Dec. 1. Expansion of the Houston metalworking industry has been on the upsurge for decades. In 1920 there were but 62 such plants. Today the number has risen to 321 (see THE IRON AGE, Nov. 20, 1952, p. 65).

Other Plans — Warehousemen elsewhere have the same confidence for a strong and continuing business. At Chicago, Caine Steel Co. will add 130,000 sq ft in 1953. Another firm has scheduled for early 1953 a warehouse to serve the machine tool and farm equipment markets west of Chicago. Atlantic Steel Co. recently opened a new warehouse in Atlanta, Ga.

Milwaukee will get a warehouse of 125,000 sq ft and for the second quarter next year one of the small chains plans a new Philadelphia plant. A Chicago warehouse is being expanded by 94,000 sq ft. At Cincinnati an additional 50,000 ft will be built.

Chief deterrents to expansion at an even faster clip appear to be lack of personnel (both supervisory and skilled), free working capital, and short inventory. Of the three, inventory is proving the hardest nut to crack. "You've got to have steel to sell steel," was one warehouseman's comment.

Not Whole Story — Warehouse stocks have been running at 40 pct of normal levels. Yet even the 40 pct is an inadequate statistic. Cold-rolled sheets, a bread-and-butter item, were below 10 pct of normal supply in a warehouse with overall inventory of 45 pct.

A warehouseman who leans heavily on cold-rolled strip figured that his inventory on that item ran just over 10 pct. His overall inventory "is 30 to 40 pct." Rounds

grapevine reports of planned competitive expansion. While long range planning is subject to change, it would not be dropped entirely in most instances even though business levels fell.

Areas that look particularly good are, of course, the industrial South and Southwest. The East and Midwest still have considerable potential, and growth in these areas can also be expected.



and bars over 1.5 in. are in even poorer shape. A goodly portion of even a 40 to 50 pct inventory may be in slow-moving items.

Most warehouse people don't expect supply relief before mid-1953. When the steel comes, they'll be spending plenty to fill the gaps in inventory. One firm has put away over \$10 million for that specific purpose. This is roughly 1.5 times the value of present stocks. It's certain that several expansions are being postponed by lack of steel to stock the new warehouses.

Quality Surveys—Where a definite expansion plan has been set up, target dates extend to 1955 and even beyond. Surveys are concise, careful, consider business levels for lean years like the 1930's and fat years like '51. They include an area's steel buying potential and are balanced against

Shortages of working capital, siphoned off by higher labor costs, increased taxes, and the steel cost increase, have pinched the warehouse program. A half-way solution is leasing of warehouse space. Handling costs may be higher in a building not designed specifically for warehousing of steel. But leasing offers an out where capital is tight.

Heavier Warehouse Items Praised

New policies of steel and aluminum mills of delivering heavier, wider coils to warehouses has already benefited fabricators, Herbert Barchoff, executive zice-president, Eastern Brass & Copper Co., Inc., said in New York last week.

Distributors who have retooled to handle larger raw material units save the fabricator time and money handling and pre-fabrication preparation of their orders, he stated.

ALUMINUM: Weld Tubes From Strips

Aluminum strip welded into 3-in. irrigation tubing . . . New machine automatically arc-welds in inert gas shield . . . Expansion planned . . . Patent pending—By W. V. Packard.

Nearly 3 years of engineering development began paying off for a small, Spokane, Wash., firm recently when it started commercial production of welded-seam aluminum tubing. The new product caught on quickly, finding a ready market in West Coast irrigation projects.

The enterprising young firm is Aluminum Supply Co. Its tubing is produced from aluminum strip which is arc-welded in an inert gas shield. An expansion program now underway will increase its capacity four-fold. Patent on the process is pending.

How It Happened—The story of this company is dramatic evidence that small firms can still thrive and grow, despite the many hurdles that must be cleared. In this case the ingredients were vision, management, and engineering. The result is a new product finding a ready market.

Aluminum Supply Co. was formed in 1949 by F. B. Cooper and K. M. Holman for production of aluminum building materials and roll-formed shapes. It became best known for original fabrication of patterns of rafter length aluminum roofing sheets.

But strong demand for light weight aluminum tubing interested the management. Messrs. Holman and Cooper became intrigued with the possibility of developing a welding process which might expand their operations into this field of insistent demand.

More than $2\frac{1}{2}$ years later, after hundreds of hours of engineering and development, their faith and efforts were rewarded with success. They manufactured and sold their first thinwall, welded-aluminum irrigation tubing.

An electric-arc welding machine of their own design and construction is now turning out the 3-in. welded-seam tubing at the rate of 27,000 ft per day, according to Mr. Holman.

Production Steps — Production is accomplished in this manner: (1) Aluminum sheet stock is slit into strips of proper width. (2) Strips are submerged into tanks for pre-

by introduction of an inert gas which prevents atmospheric contamination of the aluminum. (6) The tube is then sized and cut to desired length. (7) Finally, each length of tubing is hydrostatically tested.

Expanding — Close control of the weld assures a smooth finish. There is neither an outside bead nor an inside flash on the tube. And uniform wall thickness is maintained along the welded seam.

The tubing is strong, too. When submitted to hydrostatic testing, it withstands pressures up to 1250 psi.

With one machine the company is presently producing 27,000 ft of 3-in. tubing per day. Within the next 6 months capacity is expected to be boosted approximately four-fold, as four additional machines (now being built) are completed. The new machines will weld 2, 4, 5, and 6-in. tubing, thus completing the range of sizes from 2-in. to 6-in.

For the present, at least, the management does not contemplate licensing or otherwise selling rights to the machines. Present efforts are concentrated on completing the four additional machines and expanding other facilities.



ALUMINUM TUBING is seam-welded in inert gas shield. Strip is pre-heated, then formed for welding.

> heating. (3) They then enter the rolling mill where they are formed into tubular shapes. (4) Shapes thus formed are seamwelded automatically by electric-arc method. (5) Welding is made possible

The idea of welding aluminum in an inert gas shield is not new. But Aluminum Supply is believed to be the first firm to produce and market a welded-seam aluminum tube. Its high-speed production line, aided by pre-heating tanks, should be a distinct advantage in serving a ready market.

-Manufacturing-

gas on-(6)

de-

ach

illy

of

ish.

nor

And

in-

hen

, it

psi.

y is f 3-

ext

old, now The and the n.

late ling efoletines

num
new.
eved
and
inum
ction
anks,
ge in


Coast Shipyard Helps Stargazers

San Francisco's new Alexander F. Morrison Planetarium is unique in that, among other things, it contains the first planetarium projector to be made in the United States. All other projectors in this country—and only seven cities have major planetariums—were made by Carl Zeiss Co., Jena, Germany. Zeiss's Jena plant is now in Red hands.


An important step in manufacture was precision machining of castings for the unit. Parts, some of them 40 in. in diam, had tolerances well under 0.001 in. Bethlehem Pacific's San Francisco Shipyard machine shop handled the job.

Work included machining surfaces of two spherical star projector carriers and boring 15 9-in, holes in each. One side of each sphere, which is open, was machined to fit a circular ribbed plate.


A steel inclination casting was shaped to fit a ball bearing, the inside of which is fitted to another circular ribbed plate. Opposite side of each casting was machined to fit other ball bearings, which in turn were fitted to a central ring.




Facing and boring projector carrier to fit inclination casting.



Special fixtures are used to check accuracy of inclination casting.




Machinists inspect planetarium projector after assembly in shop.



Boring a hole for the base plate in one of the two projector spheres. Below, machined central and inclination castings are assembled.





Long continuous fibers through shank and head are the "inside" proof of efficient cold-heading.

The above macrograph shows the uniform strength-giving, grain-flow characteristics in a bolt made from Keystone C1038 Special Processed Cold Heading Wire. Such uniform grain flow assures longer die life, increased production, and a better finished product.

Whatever your industrial wire problems might be, Keystone metallurgical research and testing facilities are available to supply the answers.



International

DEVELOPMENT:

Plan to tap mineral resources of Sahara Desert advanced by French.

France is considering a plan to transform the wasteland of the Sahara Desert into one of the world's richest mineral sources and perhaps even make it a major industrial center in the decades to come.

The plan will be presented to the French parliament by a committee of political, military and scientific leaders, reports Overseas News Agency. In addition to longterm development projects, the plan calls for a change in present political and legal status of the Sahara.

Coal—On the basis of recent investigations, the committee believes the Sahara may contain fabulous mineral resources. Coal is reported to be abundant, in seams as thick as those found in Pennsylvania and Poland. Much of it is said to be mixed with iron ore.

Precious strategic minerals, such as wolfram, cobalt, tin, copper, aluminum, antimony, asbestos, molybdenum, nickel, zinc and lead are also reported plentiful. And there are indications of uranium and oil deposits.

Ownership Problem — Before France can scoop up any of these treasures, it must establish ownership of the Sahara. The government, for administrative purposes, once assigned chunks of the desert to the five surrounding countries—Algeria, Morocco, Tunisia, French West Africa and French Equatorial Africa. Fearing that these countries may someday gain independence and try to keep their assigned areas, the French hope to annex the area.

Mineral ore prospecting in the Sahara is already growing. But the committee regards this as a mere trickle compared to the activity that would result if the area were unified and brought under permanent French administration equipped to develop the area at a more rapid pace.

IRON: Direct Reduction Boosts Purity

Arata concludes tests on commercial feasibility of high purity iron by direct reduction . . . Heats average 99.94575 pct Fe . . . Military, electronic uses seen—By J. B. Delaney.

Arata Metallurgy, Inc., Chicago 37, has concluded a series of test heats indicating commercial feasibility of a process for production of iron approaching the ultimate in purity. (THE IRON ACE, Nov. 20, 1952, p. 72.)

d

The test heats were made in a 6-ton basic lined electric arc furnace leased from Ohio Steel Foundries. Lima, Ohio. Heats were supervised by Dr. V. Arata, president of Arata Metallurgy, who developed the process, and who has been producing the high-purity iron commercially in a 1-ton furnace in Italy.

Four test heats were made. In the first three, Alan Wood magnetite concentrate ore (about 71 pct Fe) was used, along with a carbonaceous reducing agent and lime flux. The heats analyzed 99.94 pct, 99.968 pct, and 99.974 pct Fe, respectively. Charge material for the fourth heat was McIntyre magnetite concentrate containing 57 pct Fe, and 10.6 pct TiO₂. This heat analyzed 99.901 pct Fe.

An Arata spokesman said iron of higher purity than the test heats can be produced under the process.

Low Power — Heats in which Alan Wood ore was used ranged from 5 hr 40 min to 6 hr 42 min. No time was given for the fourth heat. Starting with a cold furnace, power consumption was less than 2000 kw-hr per ingot ton of iron. Recovery on Alan Wood ore was 85 pct.

Dr. Richard S. Cole. Chief. Iron and Steel Div., Munitions Board, who observed the test heats, foresaw defense possibilities for the high purity iron. He added that the metal could be used to conserve strategic materials in an allout defense effort.

It has been used successfully in one direct military application.

In Italy, the metal has been used as a magnetic material in electronic equipment and to make rotating bands for artillery shells. Iron powder is another probability. It could be used in place of copper in some applications.

Armco Ingot Iron, which has been produced commercially in the The metal is scheduled to go to Watertown Arsenal, Watertown, Mass. It is estimated that a carload of ore will yield about 10 tons of ingots which will be rolled into sheet and tubing for further tests.

Ore Treatment Process Developed

A new and revolutionary ore beneficiation process applicable to potash and phosphate as well as to many other types of ores has been developed by International Minerals & Chemical Corp.

Neither re-agents nor water are used. The dry beneficiation method has been named the LeBaron-Lawver Process. The new method of refining ore was developed under the

Arata Iron Test Heat Results

CHEMICAL PROPER	No. 1	No. 2	No. 3	No. 4
C	0.017	0.016	0.013	0.027
Mn	0.01	none	none	trace
P	0.0008	0.001	0.0008	0.0005
S	0.009	0.011	0.008	0.055
Cr	0.01	none	none	none
Mo	0.006	0.004	0.004	0.002
Si	none	trace	trace	0.015
Ni	none	trace	trace	none
Time	5 hr 40 min	6 hr 42 min	6 hr 15 min	

Alan Wood ore was used on first three heats. McIntyre ore on the fourth.

PHYSICAL PROPERTIES

	Forged
eld Point, psi	17,000 to 21,000
ensile strength, psi	40,000 to 42,500
ongation in 5 diameters, pct	40 to 45
eduction of area, pct	65 to 70

Forged & Heat Tr	reated
14,000 to 18,5	00
38,000 to 41,0	00
50 to 55	
75 to 80	

U. S. for over 30 years, has been used as a base material for galvanized products and as motor bases. A typical heat of Armco Iron analyzes 99.91 pct Fe. Armco also makes a high purity iron for magnetic purposes.

On the basis of the test heats, Arata engineers are convinced the metal can be produced competitively from a cost standpoint. They predicted that power consumption per ton will be reduced when larger furnaces are used on a continuous basis.

In preliminary physical tests, a hollow riser from a casting was forged into a solid 1-in. square bar. In a 180° bend test at room temperature, the bar did not break or tear

direction of Dr. Paul D. V. Manning, vice-president, research, and Dr. 1. M. LeBaron, director, research laboratories.

New Plant—A new and larger pilot plant will be built at the present Carlsbad Refinery to operate continuously treating semi-commercial quantities of potash by means of the new method. Plans are also being developed for another shaft and mine on International's new ore body in the Carlsbad basin.

In the dry beneficiation process the ore is ground, dried and given a simple and inexpensive treatment, after which the ground ore is passed between electrodes. As the treated ore passes between the electrodes it separates into various minerals

STEEL: Capacity Upped 7.2 Million Tons

Capacity beginning next year will be about 16 million net tons . . . Early next year expansion will near 120-million-ton goal . . . Midwest and East expand most—By J. B. Delaney.

Steel mills in the U.S. by year's end will have installed almost 7,250,000 tons of new ingot capacity during 1952, increasing national capacity to approximately 116 million tons.

Before the new year 1953 is very old, capacity will be within reaching distance of the 120 million-ton goal established unofficially in early 1951 under the spur of defense requirements, fast tax amortization, and industry confidence in a continuing civilian demand for steel.

More Next Year - Included among this early-1953 capacity will be 1.2 millions at the new Fairless Works of U.S. Steel Co. Some 600,000 tons of capacity was to be brought in at this plant during last quarter of this year.

Other new capacity scheduled for 1953 includes Pittsburgh Steel. 325,000 tons due to openhearth furnace enlargements; Detroit Steel., Portsmouth Plant, New Boston, O., 750,000 tons, 4 new 250ton openhearths; Tennessee Coal & Iron Div., Fairfield, Ala., 200,-000 tons, openhearth enlargements. National Steel Corp., also will bring in new capacity next year. Detroit Steel is scheduled to light a 1400-ton blast furnace at Portsmouth about Feb. 1.

Crane Shortage Hurts-One fly in the expansion ointment has been extended deliveries on cranes, charging machines and other auxiliary equipment. Several companies report they have been unable to fully utilize new capacity due to inability to obtain this equipment. Crucible Steel estimates it will not reap full benefit of expanded capacity until third quarter of '53 for this rea-

Not usually figured in estimates of the effect of last summer's 2month steel strike is the loss due to delay of expansion programs. Some companies set the loss at one day for each day of the strike. A number of programs scheduled for completion this year have been extended into 1953.

Decontrol Argument-New capacity, completed and in the offing, is a potent factor in industry arguments that most controls on steel be removed early next year. An industry task force, in making its recommendations to National Production Authority, said non-military consumers can expect 31 pct more steel in 1953 than they received this year (See

Of the 1952 expansion total, more than 6 million tons is represented by new openhearth capacity, largely due to installation of new furnaces but partly on account of furnace enlargements and technological improvements in operations and materials handling. Balance of the new capacity, over 1 million tons, is due to electric furnace expansion.

When final figures for 1952 are in, openhearth capacity will be over 101 million tons, an increase of 6.3 pct over capacity at start of the year, and 11 pct over capacity at Jan. 1, 1951. Electric furnace capacity will be over 9 million tons, up 13.5 pct from start of the year and 24 pct over capacity at Jan. 1, 1951.

al

M

fu

A

DI

in

m

15 by

th

116

Huge Investment-The industry's newest expansion program involves an investment of more than \$4.5 billion on the basis of Certificates of Necessity approved by the Defense Production Administration. The certificates cover expansion in steel finishing capacity, coal and coke, ferroalloys and ores, blast furnace capacity, foundries, forges, and lake and river transportation as well as steel melting expansion.

Total investment for iron and steel expansion is far in excess of any other industry under the defense plan. Railroads and electric power each are over \$2 billion.

Industry investment in steel works and rolling mills alone will be over \$2.5 billion, of which 61.8 pct will be allowed fast tax amortization. Proposed blast furnace construction will involve spending of \$651 million, while another \$708 million will be spent on iron ore projects. Fast tax write-offs approximate 71.4 pct and 70 pct. respectively.

Big Gainers-Major new capacities to be brought in during the year will include 1.2 million tons of openhearth expansion at the Indiana Harbor Works of Youngstown Sheet & Tube Co.; approximately 900,000 tons by Jones & Laughlin at Pittsburgh and Cleveland: 600,000 tons by U.S. Steel at Fairless Works; approximately

New Blast Furnace Capacity in Net Tons

Company	No. of Furnaces	Annual Capacity Increase (N, T,)	Location	Operation Started
Colorado Fuel & Iron	1	45,0001	Pueblo, Colo.	
Crucible Steel	1	360,000	Midland, Pa.	OctDec.
Jones & Laughlin	1	200,0002	Cleveland	April
National Steel	1	560,000	Weirton, W. Pa.	Sept.
	1	560,000	Detroit	Sept.
Republic Steel	1	560,000	Cleveland	*****
U. S. Steel	1.	600,000	Morrisville, Pa.	Dec.
Youngstown Sheet & Tube	1	580,000	East Chicago, Ind.	(3)

TOTAL CAPACITY 34,650,000

Modernization.
Rebuilt.
Due early in 1953.

800,000 tons by Bethlehem; 800,-000 tons of openhearth and electric furnace capacity by Republic: 504,000 tons of electric furnace capacity by Northwestern Steel & Wire Corp. at Sterling, Ill; 550,-000 tons of openhearth by Lone Star Steel Co., Lone Star, Tex., and 750,000 tons of new openhearth capacity by Inland Steel at Indiana Harbor. Youngstown expansion at Indiana Harbor was offset by scheduled elimination of 330,000 tons of bessemer capacity.

High Rate-The fact that a major part of the 1952 expansion is already in production explains the record operating rate of the industry since the steel strike ended. Industry operating rates are based on capacity at last Jan. 1 of approximately 108.6 million tons.

Geographically, over 3 million tons of new 1952 capacity is being brought into production in the Midwest, while over 2.5 million tons is scheduled for the East.

STEEL:

Cof

C-

ts

ts

n-

C-

re

16

92 rt

a-

ic 9 rt

a-

n-

in

i-

V

91.

a-

18

y,

d

S

d

of

-9

ic

el

.8

r-

e

T

n

S

t.

e

16

9-

8

P -

el

V

E

Building of LeTourneau mill slowed but two furnaces put in operation.

Still waiting in the wings is the Longview, Tex., steel mill being built by R. G. LeTourneau, Inc., to handle plate requirements of its five plants.

Slowed by steel shortages, rolling mill difficulties and climbing costs. LeTourneau, Inc., has still managed to put into operation two electric furnaces, each with 25 ton capacity. A third furnace is scheduled for production late this year. Date for initial operation of the plate rolling mill has not been announced.

Preheated-The furnaces (as reported in THE IRON AGE. June 7, 1951) are "evolutionary," designed by R. G. LeTourneau. A preheating charging tube, 20 ft x 91 in. brings the charge to red heat prior to entry into the furnace.

When operating, the mill will roll plate to 144-in. widths and in thicknesses of 3/16 in. through 12 in.

New Openhearth and Electric Steelmaking Capacity in 1952

(By Company, Type of Furnace and Location, in Net Tons)

Company	No. of	Rated Capacity per Heat	Annual Capacity Increase	Location	Furnace Builder	Operation Started
OPENHEARTH FURNACE	· arraces	110. 017	1141 411			
Bethlehem Steel			000,000			
Colorado Fuel & Iron			165,000	Pueblo, Colo.	Self	OctDec.
			26,570	Claymont, Del.	Self	
Crucible Steel	8	165	105.0001	Midland, Pa.	Self	Oct. Dec.
Inland Steel	4	250	750,000	Indiana	McKee	Sept. Dec.
James W. Lavorbille		050	755 0004	Harbor, Ind.	Loftus	Jan. Apr.
Jones & Laughlin		250	755,0004	Pittsburgh		Jan. Apr.
Laclede Steel	4		12,1552	Alton, III.	Self	Dec. 31
Lone Star Steel		200	550,000	Lone Star, Tex.	Rust	
Midvale Co.	1	100	49,291	Philadelphia	McKee	March
Pittsburgh Steel	3	250	$163,000^3$	Monessen, Pa.	Self	NovDec.
Republic Steel	4	275	672,000	Cleveland	Freyn	
			121,000 ^S			
U. S. Steel	3	275	600.0006	Morrisville, Pa.		
	2	210	300.0004	Fairfield, Ala.		
	1	225	160,000	Provo. Utah		
Youngstown Sheet & Tube	8	250	330,000 tons retired. Net	Indiana Harbor, Ind.		
TOTAL OPENHEARTH C	APACITY-6	109,017	gain 880,000.			
ELECTRIC FURNACES						
Allegheny Ludium	3	2 10	72.000	Watervliet.	Freyn	
Allegneny Ludium	3				rreyn	
		1-10		N. Y.	Date Lan	May
Armco Steel	1	100	150,000	Kansas City	Pgh. Lec-	INIAA
*** ** ** *					tromelt	8.0-
Atlantic Steel	1	60	100,000	Atlanta	Pgh. Lec-	May
					tromelt	_
Babcock & Wilcox	1	60	96,000	Beaver Falls,	Swindell	Oct.
				Pa.	Dressler	
Eastern Stainless	1	20	12,000	Baltimore	American	Sept.
and the same of th					Bridge	
Ingersoll Steel Div.	2	12	43.200	New Castle.	American	
mgerson oteer or.		16	40,200	Ind.	Bridge	
Northwestern Steel & Wire	2	120	504.000	Sterling, III.	Pgh. Lec-	May-Aug.
MOLITIMESTELLI STEEL . MILE	4	120	304.000	Sterning, III.	tromelt	iviny rug.
Timken	3	80	Capacity 275,000. Replaced 3 openhearths.	Canton, Ohio	American Bridge	Sept. Dec.
			Net gain 75.000.			
Vanadium-Alloys	1	12.5	15,000	Monaca, Pa.	American	Dec.

TOTAL ELECTRIC CAPACITY -1.067,200

TOTAL NEW STEELMAKING CAPACITY-7,176,217

- Furnaces enlarged.
 Technological changes.
 Furnaces enlarged.
- 4 Estimated
- includes electric furnace and openhearth reconstruction and technological changes 6 1.2 million tons more due in early in 1953.

Since heavy plate in widths above 72 in. remains tight, the mill expects to be busy.

LeTourneau builds electric motors and generators for earthmoving equipment and is building its own DC electric drive for the roll. The DC generators are powered by natural gas engines and the specifications call for 8000 hp.

Small Firms Share Gear Growth

Companies with not more than 450 employees now have the opportunity of getting a share of \$6 million worth of production expansion in the gear and gear drive field.

Small business was allotted a 33-pct share of the total desired expansion goal, set by Defense Production Administration, of \$20 million in new capital investment, to be reached by Jan. 1, 1954. DPA has already issued certificates of necessity for rapid tax write-off for about \$14 million of the total.

Particularly sought at this time

is increased capacity to produce fine precision gears, gear drives, and speed changers.

Magma Seeks Additional Capital

Additional working capital is to be realized by Magma Copper Co. through sale of some 281,000 odd shares of its \$10 par capital stock, according to a registration statement filed with Securities & Exchange Commission,

Reconstruction Finance Corp. recently agreed to loan San Manuel Copper Corp., a Magma subsidiary, some \$94 million for development of its copper holdings. One condition on the loan was that Magma would contribute \$6 million to San Manuel capital from sale of capital stock.

Net proceeds in excess of the \$6 million needed to retire San Manuel notes will be used for additional aid to San Manuel and to increase Magma's general financial status.



Housing: More Units

Private starts up, with costs down . . . Public jobs the opposite . . . No seasonal decline yet.

Most residential construction was at a slightly lower unit cost; volume of privately-financed building increased and public construction was of smaller volume.

That's the housing story for 1952, based on Washington data covering the first 10 months.

Only a seige of unusually bad weather can now prevent a larger number of housing starts this year than last. And this record probably will be reached in spite of scarcities of building materials, production controls, and earlier stiff government credit regulations.

Best guess now as to the number of housing starts for the year is from 1,110,000 to 1,130,000. Last year's total was 1,091,000 units. 85

fu

in

Through October, approximately 966,500 new permanent non-farm type of residential units were put under construction. This was roughly 10,500 more than for the same period last year, including both private and public housing.

Decline is Late—Usually, a seasonal decline begins after September. But reversing this trend, October starts were reported at 101,000—3000 more than September and 11,000 more than in October last year.

Early reports for November indicated that in almost all parts of the country the seasonal decline had not yet set in. New home construction was going on at a rate equal to or greater than the October rate.

This is in excess of the annual rate—1.2 million—which if continued for 3 months would permit the Federal Reserve Board to put Reg. X into effect once more. But since winter is still ahead, officials are giving little thought to credit curbs.

Indications are that the 1952 trend is toward lower cost construction. Total dollar volume through October was estimated at \$8.6 billion, running \$100 million behind last year, despite the increase of more than 10,000 starts.



Less Cost

EF 11

11

a

d

er

ir

ly

es

n

n-

er

is

st

ly

m

ut

as

he 12

a-

n-

00 nd st

lihe ot

on or

lal nnit ut ut ils lit

52

icgh il. nd

of

GE

None of these figures include farm construction, which is not broken down by types of building. Nor do they include figures for additions and alterations to existing

Farm Building Off-Farm construction for the period amounted to \$1.5 billion, down slightly from last year. Home owners are estimated to have spent \$875 million for renovation, exclusive of maintenance, which is up by \$90 million from the 10-month period last year.

Total expenditure for public housing construction was up by \$90 million from last year. However, the \$550 million spent from public funds so far this year placed only 49,000 units as compared with about 67,000 last year for \$460 mil-

On the other hand, private housing is up 29,000 units while nearly \$200 million less was spent- which should point up a lesson of some

Steel Inquiries and Awards

Fabricated steel awards this week include the following:

525 Tons, Fond Du Lac, Wis., bridges to Worden Allen Co.
430 Tons, New Orleans, La., St. Bernard Ave. overpass for city of New Orleans, to American Bridge Div. of U. S. Steel, Birmingham, Ala.
300 Tons, Lincoln, Neb., oil storage tanks to General American Transporation

Fabricated steel inquiries this week in-clude the following: 1050 Tons, West Chicago, Ill., chemical plant for Lindsay Light and Chem-ical Co.

1000 Tons, Boston, Mass., new Northeastern University gymnasium and physical education building consisting \$1,750,000, on Huntington Ave., Back Bay, through John A. Volpe Construction Co., Malden, Mass., to Groisser and Shlager Iron Works, Somerville, Mass.
771 Tons, Allegheny County, Pac, alterations to existing structures, construction of new substructure and super structure. Pennsylvania Dept. of Highways, Harrisburg, Pa. Bids to Dec. 19, 1952.
300 Tons, Newburyport, Mass., warehouse for Hytron Electronics and Radio Corp., through Leslie R. Porter Co., Beverly, Mass., to Albert O. Wilson Structural Steel Co., Cambridge, Mass.
175 Tons, Cranston, R. L. new Parkview

Mass.

Tons, Cranston, R. L. new Parkview school through Gilbane Building Co., Providence, R. L. to Albert O. Wilson Structural Steel Co., Cambridge,

Reinforcing bar awards this week in-clude the following:


190 Tons, Libertyville, Ill., high school to Carroll Construction Co

AMERICAN CHEMICAL PAINT COMPANY

AMBLER ACP



Technical Service Data Sheet Subject: METAL PRESERVATION AND PAINT PROTECTION WITH ACP PHOSPHATE COATING CHEMICALS



U.S. ARMY PHOTOGRAPHS COURTESY OF "ORDNANCE MAGAZINE"

Typical spray and dip phosphating equipment and some ordnance products that are now given a protective phosphate coating for extra durability under all kinds of severe exposure conditions. Both military and civilian applications of ACP phosphate coating chemicals are shown in the chart below.

SELECTION CHART OF ACP PROTECTIVE COATING CHEMICALS FOR STEEL ZINC AND ALLIMINING

METAL	ACP CHEMICAL	OBJECT OF COATING	TYPICAL METAL PRODUCTS TREATED	GOVERNMENT SPECIFICATIONS
	"GRANODINE" Zinc Phosphate Coating Chemical	Improved paint adhesion	Steet, iron, or zinc fabricated units or com- ponents, automobile bodies, refrigerators, washing machines, cabinets, etc., projec- tiles, rockets, bombs, rifles, small arms, belt links, catridge lanks, welloular sheet metal, bank bolts and links, recoilless guiss, etc.	MIL - S - 5002 JAN - C - 490, Grade 1 JAN - F - 495 U.S.A. 57 - 0 - 2, Type II, Class C U.S.A. 51 - 0 - 1 Finish 22.02, Class C U.S.A. 50 - 60 - 1 I G E (Ships)
STEEL	"PERMADINE" Zinc Phosphate Coating Chemical	Rust and corrosion prevention	Nuts, bolts, screws, hardware items, tools, guns, cartridge clips, fire control instru- ments, metallic belt links, steel aircraft parts, certain steel projectiles and many other components.	MIL - C-16232 U.S.A. 57-0-2, Type II, Class B U.S.A. 51-70-1, Frinish 22,02, Class B Navy Aeronautical M-364 U.S.A. 72-53 (See An-F-20)
	"THERMOIL- GRANODINE" Manganese-iron Phosphate Coating	Wear-resistance anti- galling, safe break-in of friction or rubbing parts. Rust proofing.	Friction surfaces such as pistons, pistons rings, gears, cylinder liners, camchafts, tappets, crankchafts, tocker arms, etc. Smalf arms, weapon components. Hardware items, etc.	MIL-C-16232 U.S.A. 57-0-2, Type II, Class A U.S.A. 51-70-1, Finish 22,02 Class A Navy Aeronautical M-364 U.S.A. 72-53 (See AN-F-20)
	"GRANODRAW" Zinc-iron Phosphate Coating	Improved drawing, extrusion, and cold forming	Blanks and shells for cold forming, hawvy stampings, tubs; tubing for forming or drawing, wire, rod, etc.	
ALUMINUM	"ALODINE" Protective Coating	Improved paint adhesion and corrosion resistance	Aluminum products of similar design such as refrigerator parts, wall file, signs, washing machine fulus, etc.; pararaft and aircraft parts, bazookas (focket launchers), helmets, belt buckles, clothes divers, clothesine, rocket motors, etc., aluminum strip or sheet stock.	MIL-C-5541 (See also QPL-5541-1) MIL-5-5002 AN-F-20 U.S. Ravord O.S. 675 16 E4 (Ships) AN-C-170 (See MIL-C-5541) U.S.A. 72-53 (See AN-F-20)
ZINC	"LITHOFORM" Zinc Phosphate Coating Chemical	Improved paint adhesion	Zinc alloy die castings; zinc or cadmium plated sheet or components; hot dip galvan- ized stock, galvanneal; signs; siding; rodling; galvanized truck bodies; etc.	QP-416 RR-C-82 JAN-F-495 AN-F-20 U.S.N. Appendix 6 U.S.A. 72-53 (see AN-F-20)



WRITE FOR DESCRIPTIVE FOLDERS ON THE ABOVE CHEMICALS AND FOR INFORMATION ON YOUR OWN METAL PROTECTION PROBLEMS



TOOLING: Different For Planes

Short runs, high precision make difference between auto and aircraft tool and diemaking . . . Defense boom has given birth to many independent shops in West—By T. M. Rohan.

In Los Angeles they give tool and diemaking a new twist. Detroit will spend 6 months and \$40,000 on an auto body die and sweat for weeks to cut half a minute off production time. But then they'll use it for 1 million cars. In Los Angeles they always need it yesterday. They rarely spend more than \$2000, throw it away after 100 uses.

Airplane tool and diemaking is strictly a hopped-up affair these days. Production runs are seldom over 100 or 150 parts. Reason: There are seldom more than that many planes of any one type made at present. Even when runs are longer, design changes make tooling obsolete unlike the automotive industry.

Plane body dies are also much more precise than, say, autos. Allowable variations on exterior fuselage contours are only 0.002 in, per 5-in. length. Instrument checking is required while car body variations need only be undiscernable to the eye.

High Tool Pct — Number and complexity in aircraft tooling is also out of proportion. Convair's R3-Y flying boat, for instance, will need about 50,000 separate tools. The industry's rule of thumb is that 10 pct of total cost goes into tooling.

Potential production runs, rates and elapsed time in use govern die design. If a die will be used only 100 times in a year, a form block or drop hammer die is used. This takes some extra time to make but not enough to offset the cost of a mechanical die which would be

good for 1000 or more parts. Fact that speed is secondary to precision is one redeeming factor.

The aircraft program has caused many independent tool and die shops to spring up in southern California, at least 20 in the Los Angeles area alone. Most of these are sorely overloaded but the lure of heavy overtime pay draws many of the best toolmakers.

Aircraft manufacturers shun overtime to keep costs down but will pay outside shops a premium for rush jobs. Planemakers cultivate good will in these shops by giving them jobs in slack times to get return favors at other times.

Good Labor Short — Machinists and tool and diemakers with experience are more than welcome. Lockheed with a total Burbank employment of 29,793 has 2961 in all phases of tool designing, making, inspecting etc. They could use 100 more.

Vacancies are filled by recruiting from other areas of the country and training currently employed men for higher skills. But both programs are only moderately successful. Lockheed's recruiting drives in the Midwest brought in many tool engineers but few highly skilled workers. Detroit craftsmen, for instance, generally get better rates at home although the lure of sunny California without traditional Detroit layoffs is strong for some.

A

01

di

01

to

al

0

11

a

th

SI

Lack of a housing guarantee has been a major drawback for Convair. This company, which has a tooling department of 1900 out of a total work force of 21,000 at San Diego, is currently recruiting in New York, Boston, Chicago, and Memphis. Planemakers generally have a gentlemen's agreement, not to pirate each other's labor.

But Workers Drift—Alternative to recruiting is to develop workers already employed and most plants go in heavily for on-the-job and classroom training. In larger plants up to 100 may be on full-time training while 2000 get on-the-job tutelage.

Labor

William Green Passes



William Green, president of the American Federation of Labor, passed away at his home in Coshocton, Ohio, near the coal mines in which he worked as a boy. In poor health for a number of years, Mr. Green died of a heart attack. He was 82 years old.

Mr. Green headed the AFL since 1924 when he succeeded Samuel Gompers. A bitter opponent of dual unionism, he still had hope of repairing the split between the AFL and Congress of Industrial Organizations at the time of his death.

Born in Coshocton, Mar. 3, 1870, Mr. Green quit school early to work in the

coal mines. In 1890 he joined the United Mine Workers. For a number of years he participated in Democratic politics and served two terms in the Ohio State Senate.

An aggressive and early foe of communism, Mr. Green was also responsible for binding the AFL's millions of workers to an effective no-strike clause during World War II. Author of a book, *Labor and Democracy*, in 1930 he received the Roosevelt Memorial Assn. Medal for service in maintaining industrial peace.

STEEL: Task Force Asks CMP End

Recommends end of all CMP controls except military by Apr. 1... Ask open-end CMP immediately... Directives and priority for military and atomic needs to stay—By A. K. Rannells.

The steel industry has asked National Production Authority to scrap all CMP controls, except for military and atomic energy priorities, not later than Apr. 1.

ie

n

10

Pa

11

11

ut

m

11-

ps

es

S.

its

-Y

ie.

m-

all

ıg,

00

n-

m-

tit

er-

re-

est

ers

rs.

ce.

me

ali-

oit

nas

on-

s a

of

San

and

illy

ent.

ive

ers

nts

and

ger

ull-

on-

GE

It recommended, however, that NPA retain its system of production directives as assurance that defense production needs in tight supply categories of steel products would be met.

The proposal, as expected, follows basically along the lines of a plan submitted by the industry last spring prior to the 54-day steel strike. Officials said the recommendations would be taken under advisement and submitted to the Production Policy Committee about Nov. 24.

Open-End CMP—Meanwhile, Defense Production Administration is going ahead with full programming of controlled disposal of April-June steel production. Second quarter allotments are expected to be issued about Dec. 15.

As a prelude to abandonment of all but priority controls, the industry recommends an immediate open-ending of CMP with respect to steel products. This would permit mills to sell on open market any steel left over after expiration of lead time for CMP steel.

At the same time, steel users would be permitted to buy any of this steel they could get and to use it in excess of CMP production schedules without charging against their allotments.

Recommendations went further than earlier suggestions by industry in that they proposed that construction projects be allowed to pick up any of this free steel without regard to construction schedules.

Industry is convinced now in view of rapid recovery from the strike, together with new capacity coming into production, that such

Steel Market Forecast

The steel industry task group backed up its decontrol recommendations with the following forecast of steel supply and demand during 1953:

(1) The industry can produce as much as 118.8 million net tons of ingots—if needed.

(2) No more than 14 million tons of this output will be required for military and atomic energy purposes, as now planned.

(3) This will leave as much as 104 million tons for all other purposes—one-third more than the probable 80 million tons which will have been available for non-defense uses during 1952.

a step will not dislocate the civilian economy. The task group's report supports this thinking and says that there would be no shortage of consumer goods from lack of steel.

Over the Hump—It is argued that by the end of first quarter mill rollings, some 95 pct of steel mill requirements for the industrial expansion program will have been shipped. From then on, it is held that the steel plants can take care of defense requirements with simple priorities and the directives for assuring particular categories of products.

Just in case something should go sour, it is further proposed that a special assistance group be established within NPA to handle any chance bottlenecks involving specific projects connected with military and atomic energy programs.

A similar group, consisting of industry men, would also be named on a standby basis to assist in quick solutions to such problems, if they developed.

Warehouses would be taken care of during the second quarter by continuing distribution on the basis now authorized in order M-6A with maintenance of inventory restrictions on controlled steel products during second quarter.

But, the committee says, these warehouse shipment provisions as well as inventory controls should be scrapped with the beginning of the third quarter.

The proposals then provide that whenever, in the judgment of the industry advisory committee, it appears that defense requirements can be met without special assistance, all controls should go out the window including directives and setasides.

Raise Coke Ceilings

OPS has approved a ceiling price increase for by-product oven coke and coal chemicals. It averages 3.75 pct and may be spread among various products. An earnings standard survey showed the need for this action.

Authorization is in Amendment 13, Supplementary Reg. 13, General Ceiling Price Reg. and is effective Nov. 21. At the same time OPS allowed pass-through of the boost in delivered costs of coking coal (mostly bituminous) occurring after Oct. 1 as a result of wage increases to the miners.

Tighten Stainless Order

NPA will soon require certification that nickel bearing stainless steel orders won't be used in violation of present restrictions, it's expected. No relief is in sight for nickel in spite of new facilities expected early next year and allocation is in the cards for a long time, says NPA.

Industry Controls This Week

Coal—Amend. 6, CPR 4 raises price ceilings on all sizes of Pennsylvania anthracite.

Coke—Amend. 13, SR 13, GCPR increases ceiling prices on by-product oven coke and coal chemicals.

Construction—Amend. Dir. 6 CMP Reg. 6 concerns non-military authorized controlled materials orders for steel placed by the construction industry.

Copper-SR 125, GCPR raises ceiling prices on products in which primary copper is used. Amend. M-16 permits brass and bronze foundries to self-certify orders for copper raw materials up to certain amounts.

Exports-Amends, 3 and 4, CPR 61 require that exporters make their base period markup reports to OPS district offices and suspend price ceilings on export sales of products on which domestic ceilings have been suspended.

Pass-Through Costs - Amend, 1, GOR 35 prohibits manufacturers who have already received a metals-cost adjustment in a specific order from obtaining another adjustment under the general "pass-through" order.

Scrap-Interp. 2 and 3, CPR 5 and Interp. 1, CPR 43, 46, 47, 53, 54 and 59 concern downgrading of scrap material purchased from the government and scrap brokerage transactions.

Government Appointments

J. P. Coleman, member, National Petroleum Council, DPA;

James C. Crenshaw, director, Water Resources Div., NPA:

George R. Davis, director, Motor Vehicle Div., NPA;

Richard H. Haigh, chief, Coke & Coal Chemicals Sect., Fuels Div.,

N. L. Hammond, Jr., chief, Warehouse Section, Iron & Steel Branch,

Warren Huff, acting deputy administrator and acting chairman. Aircraft Production Board and Production Committee, DPA;

Dr. Jacob L. Keller, chief, Industrial Chemicals, Dyestuffs and Pigments Sect., OPS;

George E. Meyer, director, Industrial Expansion Div., NPA;

Dr. Charles M. Mottley, director, Planning Div., Defense Research & Development Board;

Edward M. Naughton, director, Engine & Turbine Div., Industrial & Agricultural Bureau, NPA;

Joseph B. Skaptason, Chief, Agricultural Chemicals Section, OPS; Charles F. Stanley, director, General Components Div., NPA;

Robert L. Turner, acting administrator, Defense Air Transportation Administration.

RENEGOTIATION:

Remove 60-day interval in filing to speed processing of forms.

Removal of the 60-day interval between the filing of two report forms with the Renegotiation Board is expected to permit greater speed in the renegotiation process.

Amendments to Parts 1465 and 1470 of the Board's regulations, directing elimination of the 60-day delay allowed between filing of Forms 1 and 1B, are applicable to defense contractors with fiscal years ending on or after Dec. 31.

However, a special provision states that if those contractors who must submit reports before Apr. 1 find it impossible to file both forms together they may turn in Form 1 and ask permission to submit Form 1B not later than 60 days after the due date.

Originally, the 60-day delay was allowed to give contractors sufficient time to familiarize themselves with the renegotiation regulations and assemble figures for use in completing their reports. Board Chairman John T. Koehler says that most contractors now are using procedures permitting both forms to be turned in simultaneously, and extra handling by the Board's staff will be eliminated.

All contractors still have 3 months in which to file after their fiscal years close.

Government Inviting Bids

Latest proposed Federal procurements, listed by item, quantity, invitation No. or proposal and opening date. (Invitations for Bid numbers are followed by "B," requests for proposals or quotations by "Q.")

Frankford Arsenal, Philadelphia.

Adapter cylinder cap bushing, var 6 itm, ORD-53-SP-142, Dec. 19.
Relay etc. S/P FCE-AA M33C M33D, var 2 itm, ORD-53-SP-138, Dec. 19.
Housing, var 15 itm, ORD-53-SP-134, Dec. 17.

Ordnance Tank Automotive Center, Detroit. Shackle w/bushing assy, 6009, 53-601B, Dec. 12. Regulator assy, 2628, 53-541B, Dec. 12. Plug, 612, 53-517B, Dec. 12. Lock assy, 100, 53-517B, Dec. 12.

Chemical Procurement District, Chicago, Burster, well, 29100, CM1-11-021-53-38, Dec. 2.

Signal Corps Supply Agency. Philadelphia. Clamp cable suspension, 32000 ea, 117-32CB, Dec. 17. Charger battery 465 ea, 1147-32BB, Dec. 15.

Supply Dept. Procurement Section, Marines, Washington. Saws, woodworking, 100 ea, 432B, Dec. 11.

Bureau of Ships, Washington, Tube tester, 4825, 800-39133-M11, Dec. 11.

Navy Purchasing Office, Washington. Drills, star, hand, 4868, 6819B, Dec. 5. Shackle bomb, 1427, 6773AB, Dec. 10. Punches, vnr. 800 sets, 6815B, Dec. 2. Pliers, brake key, 6900, 6817S, Dec. 3.

Rock Island Arsenal, Rock Island, Ill. in and chain assy, 1400 ea, 11-070-53-294B.

Pin and chain assy, 1400 cm,
Dec. 11.
Body assy, 680 ea, 11-070-53-294B, Dec. 11.
Indicator assy, 660 ea, 11-070-53-294B, Dec. 11.
Knob assy, 740 ea, 11-070-53-294B, Dec. 11.
Kit modification for M20 and M20B1 rocket launchers, 1300 ea, 11-070-53-262B, Dec. 5.
Fork-Holding, 200 ea, 11-070-53-262B, Dec. 5.
Jig-Drill assy, 200 ea, 11-070-53-262B, Dec. 5.
Punch and dies assy, 200 ea, 11-070-53-262B, Dec. 5.

Dec. 5. Saw-Hole-assy, 200 ea, 11-070-53-262B, Dec. 5. Metallic belt-cal 30, 1811194 ea, 11-070-53-327B,

Small Arms Ammunition Center, St. Louis. Ctg ball revolver cal .38, 419,000, ORD-23-196nall revolver cal .38, 200,000, ORD-23-195-53-2B, Dec

Quartermaster Depot, Philadelphia. Buckle web belt brass, 1222200 ea, 88B, Nov. 24.

Clamp, wire rope, 25,784 ca, ENG 36-058-53-46B, Dec. 1. Corps of Engineers, Pittsburgh.

Quartermaster Purchasing Div., Chicago. Tubs, galley, corrosion resistateel, 1300 ea, 53-435B, Dec. 10.

National Bureau of Standards, Washington. Connectors, 600 ea, B1-464-53, Nov. 28. Clip, alligator, 1000 ea, B1-464-53, Nov. 28.

Contracts Reported Last Week

Including description, quantity, dollar values, contractor and address. Italics indicate small business representatives.

Sweeper, rotary, 178 ea, \$155,715, Meili Blumberg Corp., New Holstein, Wis. Spare parts, var. \$39,167, Paragon Gear Works, Taunton, Mass.
Spare parts, var. \$27,670, De Vilbiss Co., Toledo.
Shell, H. E., T64, 76MM, 512000, \$2,817,-636, Colorado Builders & Supply Co., Denver.

ver. Fuze, PD, M52A2, 1742000, \$1,733,638. National Vendors, Inc., St. Louis. Case cartridge M1, 618000, \$10,536,900. Chase Brass & Copper Co., Inc., Waterbury, Conn.

b

f

Chase Brass & Copper Co., Inc., Waterbury, Conn.
Continental tank engines, 450, \$4,007,-277, AVCO Mfg. Corp., Williamsport, Pa.
Continental tank engines, 200, \$1,584,-822, AVCO Mfg. Corp., Williamsport, Pa.
Windshield. aluminum alloy, 149,400, \$35,856, Odel Die Casting Corp., Detroit.
Gages, lot, \$25,557, Greenfield Tap & Die
Co., Greenfield, Mass.
Cylinder assy, 400, \$55,000, Clyne Mfg.
Co., Cincinnati.
Mattocks, pick, 94300, \$177,284, True
Temper Corp., Cleveland.
Hammers. machinist, 38000, \$25,080.
Fairmount Tool & Forging, Inc., Cleveland.
Conveyers, gravity roller, 685, \$51,855.
The Rapids-Standard Co., Inc., Washington.

n. Replenishment for small arms parts, 10, \$27,500, Tool Industries, Inc., Detroit. Replenishment of small air parts, 7000, 17,330, Northfield Research & Mfg. Co.,

Detroit.
Replenishment of hardware, 3395000, \$32,445, Russell, Burdsall & Ward Bolt & Nut Co., Port Chester, N. Y.
Replenishment of hardware, 150, \$35,-625, Ray Whyte Electric Products, East Detroit, Michigan.
Replenishment of hardware, 194880, \$31,930, U. S. Steel, Detroit.
Circuit breakers, air, 3540 ea, \$28,072, Westinghouse Elec. Corp., New York.





Which twin has been Sintered?

When the boss asks you about Sintered parts... be sure you know these money-saving facts

When it comes to tolerance, finish, and physical properties, the above lock cylinders are identical in all respects. Yet, the one on the right...the sintered one ... costs 13 c less than its twin! This saving is one your business can benefit from by turning your small parts production over to American Sintered Alloys.

Despite the tremendous economy and the many other advantages of powder metallurgy, some manufacturers know little about this modern method of mass-producing small parts. Briefly, sinterings are parts made by applying heat to compacts of metallic powders that previously have been compressed in skillfully made molds. For many applications the resulting product requires no additional finishing and is superior

to an equivalent unit made by screw-machining, diecasting or stamping.

If your finished product depends on self-lubricating bearings...structural parts such as cams, motor brush holders, mounting brackets, ordnance items...or similar parts, you can save time and money by contacting ASA, who, now, as a division of Yale & Towne, is better equipped than ever to solve your parts production problems. For free fact folder, write to American Sintered Alloys Division, Dept. A-211, The Yale & Towne Mfg. Co., Bethel, Conn.

Using custom-made metals Sintering complicated designs Control of physical properties Obtaining unusual tolerances


WRITE TODAY

finishing and is superior FOR FREE FOLDER

American Sintered Alloys Division

YALE & TOWNE





Where the application for precision balls require high, effortless, silent speed and minimum torsional resistance, Universal Balls are best by test.

Through continuous scientific research the manufacture of Universal Balls is continuously improved. Today, Universal Precision Balls are made to within ten millionths of an inch perfect spheres. That is only one reason why those who know precision balls best accept nothing less than Universal's high quality.

All Universal Balls are 100% inspected and individually gauged. All small precision balls are slowly inspected under magnification.

Specify Universal Precision Balls when you want unexcelled surface finish, sphericity, size accuracy and extremely fine tolerances.

UNIVERSAL BALL CO.

PRECISION BALLS OF CHROME AND STAINLESS STEEL, BRONZE AND SPECIAL METALS.

WILLOW GROVE, Montgomery County, Pa.
Telephone, Willow Grove 1200

Industrial Briefs

Open House—More than 3000 visitors toured La Belle Works of WHEELING STEEL CORP. during an Open House held recently in celebration of the plant's 100th anniversary.

Build for Coke — WEIRTON STEEL CO., division of National Steel Corp., plans construction of a new coke plant and an extension to the present coke department at Weirton, W. Va.

Expanding — LINDBERG STEEL TREATING CO. has expanded its Los Angeles facilities. It has opened a new plant at 2910 Sunol Drive.

Canadian Rep — LEWIS - SHEPARD PRODUCTS, INC., Watertown, Mass., now is represented by Mussens Canada, Ltd., in Montreal, Quebec.

Appointed — Baker Industrial Truck Co. of Wisconsin, has been appointed exclusive distributor in Milwaukee and eastern Wisconsin, for THE BAKER-RAULANG CO., Cleveland.

New Offices—EAGLE ENGINEERING CO. has opened new offices at 18643 W. 7 Mile Rd., Detroit.

New Plant — NATIONAL MALLE-ABLE & STEEL CASTINGS CO. has approved a \$2 million development at its Capitol Foundry near Phoenix. New plant will be built on a 27-acre site chosen several months ago.

Ordered—LEBANON STEEL FOUN-DRY of Lebanon, Pa., reports its moving picture, "Steel with a Thousand Qualities," will be shown in MSA nations by Mutual Security Agency.

Philippine Steel—The first steel ingot mill in the Philippines is now operating at the MARCELO STEEL CORP. plant. The ingot mill is a unit of the steel melting and rolling plant.

Valve Factory—New factory facilities for the assembly of control valves were recently acquired at Dallas by THE FOXBORO CO., Foxboro, Mass.

Titanium Tour—The Materials Committee of the Aircraft Industries Assn. visited the titanium metal plant in Henderson, Nev., recently. The Henderson plant is that of TITANIUM METALS CORP. OF AMERICA, jointly owned by National Lead Co. and Allegheny Ludlum Steel Corp.

Distributor Named—Nielsen Hydraulic Equipment, Inc., New York, has been appointed an authorized distributor by THE PARKER APPLIANCE CO., Cleveland.

Test Equipment—METCO CORP., a newly-formed company for the development and manufacture of test equipment and related products, has opened offices and laboratories in Dayton.

Change Name — Cleveland Graphite Bronze Co. stockholders, in a special meeting recently, approved the proposal to change the name of the company to CLEVITE CORP.

Pick Dealer—CLARK EQUIPMENT CO., Battle Creek, Mich., has named Towne Industrial Equipment Co., Inc., Dallas, as its authorized dealer in 129 Texas counties.

Elected—A. W. McKinney, executive vice-president, THE NATIONAL SUPPLY CO., has been elected president of the Diesel Engine Manufacturers Assn.

Completed — GENERAL ELECTRIC CO. completed another step in its decentralization program on Nov. 25 with the opening of a multi-million-dollar plant at Linton, Ind. It will manufacture fractional-horsepower motors.

Special Meeting — BLAW-KNOX CO. has called a special meeting of stock-holders for Dec. 15 to vote upon a plan of corporate simplification involving the merger of the company and its operating subsidiaries.

Relighted Ovens — American Steel & Wire Division of U. S. STEEL CO. relighted the rebuilt "B Battery" of 45 coke ovens at the Division's Coke Works.

Aluminum Smelter—First 2-wings of a new aluminum smelter were opened recently for full production by AMER-ICAN ALLOYS CORP., Kansas City.

Company Organized — Wilfred Williams and James W. Robinson, have organized a new company, THE MIDWEST STAMPING & MFG. CO., Bowling Green, Ohio.

Zone Office — WILLYS-OVERLAND MOTORS, INC., has opened a new zone office in Chicago, to be called Willys-Overland Distributors, Inc.

52

THE IRON AGE

The

Martin B-61 Matador pilotless bomber taking off. Made by the Glenn L. Martin Company, Baltimore, Md. In the Air— On Land—Water— Under Water— WHERE REQUIREMENTS ARE SEVERE, Jeep almost completely submerged. Can be CALL REVERE operated in this position at about 9 miles The dramatic pictures on this page show two important per hour. Made by Willys-Overland Mospecial applications of Aerovox capacitors. One is the tors, Inc., Toledo, Ohio, for the Armed Martin B-61 Matador pilotless bomber. It contains an



Generator regulator for the 24-volt system of the submersible Jeep. This is com pletely waterproof and highly resistant to corrosion and fungi. Produced by The Electric Auto-Lite Company, Toledo, Ohio.

Illustrated are two of the many types of capacitors and filters made by Aerovox Corporation, New Bedford, Mass.; an important capacitor supplier to both Electric Auto-Lite and Glenn L. Martin. The unit above is the filter capacitor used in the generator regulator of the submersible ieep while the unit at the right is used in the pilotless bomber.

uas u-E

a

le-

est

as

y-

ite ial 0m-

IT ed

ic. 29

ve L siic-

IC le-25 nvill ver

0.

·k-

in-

ny

&

0.

of

ke

of

ned

R-

ty.

/il-

ave

HE

0.,

ND

ew

led

E

Forces.



"We have had much better welds." . . . Revere is always glad to collaborate on problems concerning copper and its alloys, aluminum alloys, and electric welded steel tube. Call the nearest Revere Sales Office.

Aerovox capacitor, which has to withstand the terrific

acceleration and speed of the craft. The other is the

submersible Jeep. Its 24-volt electrical system is com-

pletely waterproofed, and includes Aerovox filters and

capacitors for suppression of radio interference. Revere not only supplied copper and brass strip for the capaci-

tor cases, but collaborated closely in setting up specifica-

tions, and in addition worked on a welding problem. In

regard to the latter, an Aerovox Project Engineer wrote:

COPPER AND BRASS INCORPORATED

Founded by Paul Revere in 1801 230 Park Avenue, New York 17, N. Y.

Mills: Baltimore, Md.; Chicago and Clinton, Ill.; Detroit, Mich.; Los Angeles and Riverside, Calif.: New Bedford, Mass.; Rome, N. Y.— Sales Offices in Principal Cities, Distributors Everywhere

SEE REVERE'S "MEET THE PRESS" ON NBC TELEVISION EVERY SUNDAY

Sales Drop But Profits Mount

Despite loss in sales auto profits show an increase during first 9 months . . . Easing of price controls and use of less conversion steel the main factors—By R. D. Raddant.

After a whole list of "despites," production controls and a disastrous steel strike, the auto industry is pointing for bigger profits than it made a year ago.

Financial reports for the first 3 quarters of 1952 indicate that as a general rule a lower dollar volnor the amount paid in dividends. A financial statement filed in Massachusetts last week showed, however, that the Ford Motor Co.'s assets at the end of 1951 increased \$115,081,000 over the previous year. This, of course, has no bear-

ing on 1952 earnings.

Automotive Production

III S and Canada Combined)

(0. 3	. ana Canada Co	ombinea)	
WEEK ENDING	CARS	TRUCKS	TOTAL
Nov. 22, 1952	100,804*	28,538*	129,342*
Nov. 15, 1952	114,020	32,805	146,825
Nov. 24, 1951	67,319	18,994	86,313
Nov. 17, 1951	93,744	26,993	120,737
*Estimated		Source:	Ward's Reports

ume of business is accompanied by bigger earnings than in 1951.

Trend toward increased profits in spite of lower sales can be attributed to relaxation of price controls. A second factor is the use of less conversion steel over the 9 month period. After the steel strike there was return to conversion practices, but only in the second half of the year.

These two factors are the major ones behind the optimistic picture indicated at the three-quarters mark. Improved manufacturing methods in many cases have also contributed to the better earnings.

Earnings Up - Of seven car builders reporting, total net earnings after taxes were \$479.2 million against \$453.7 million a year ago. Six companies reporting sales figures show a sales drop of approximately \$246 million from the first 9 months of 1951.

These figures do not include Ford which does not reveal publicly the dollar volume of sales

K-F Loses — Kaiser-Frazer showed a net loss of \$5,688,773 for the period, but reported net earnings of \$344,064 for the third quarter. Profit was attributed to defense production, while automotive losses amounted to \$175,094.

The following statement from Chrysler's third quarter financial statement is significant:

"The relatively improved earnings, despite reduced sales volume, continued increase in costs and higher taxes, resulted in large part from less severe Government price controls than those in effect during the first three quarters of 1951.

"Reduced use of conversion steel, which is far more costly than steel acquired in readily usable forms, also was a factor. The steel strike during the summer, however, for a time so reduced normal steel supplies that we are again compelled to buy quantities of conversion steel for consumption during the last 3 months of the year."

Following are the reports of net earnings after taxes through Sept. 30 for the reporting companies. Nash and Willys reports are through June 30 for the first 9 months of their fiscal year:

COMPANY	1952	1951
General Motors	\$337,030,986	\$372,790,913
Chrysler	59,661,657	50,108,179
Studebaker	9,299,511	8,799,605
Packard	3,094,515	4,922,876
Hudson	6,249,145	*967,379
Nash	8,744,829	12,735,053
Willys	5,192,963	3,393,037

* After tax refund credit of \$1.055.612.

Record Rubber Use - Expanding use of new rubber products and the increased number of automobiles on the highways will bring 1953 rubber consumption to near record levels, predicts E. J. Thomas, president, Goodyear Tire and Rubber Co.

He estimates U.S. rubber consumption will reach 1,288,000 long tons next year, about twice prewar use and second only to 1947 when a tremendous wartime backlog existed.

About 58 pct will be synthetic rubber compared to 42 pct tree rubber. Use of synthetic rubber provides a bulwark against the historic instability of the natural rubber market, Mr. Thomas believes.

Index Cuts Wages - An early fall slump in the Bureau of Labor Statistics index will cut wages of 1 million auto workers 1¢ per hr starting Dec. 1.

The quarterly revision of the auto workers' escalator clause wage scale resulted from a drop of the index from an all-time high of 192.4 on July 15 to 191.5 on Oct. 15.

UAW officials immediately declared that the drop in the index did not represent a long term slump, but merely reflected a seasonal drop in produce prices. The significance of this complaint is that it merely adds more fuel to UAW's current demands that costof-living gains hold firm.

Assembly Problem?

Use Black & Decker Screw Drivers for faster work, tighter assemblies, fewer rejects, less operator strain!



assembly problem. Write for free catalog to: The Black & Decker Mrg. Co., 603 Pennsylvania Ave., Towson 4, Maryland.

"Trade Mark Reg. U S. Pat. Off.

net pt.

es. are

9

,913 1,179 ,605 .876 ,379 5,053 .037

ndcts tovill to J. ire

onng re-

)47

ck-

tic

ree

ber

the

ral

be-

rly

oor of

hr

the

use

of

of

15.

de-

dex

rm

ea-

The

is

to st-

GE

When a high-strength steel is needed

for severe cold-formed shapes like these bumpers



be

its

Va

pi

PRODUCTION: Ford Sharpens Weapons

Readies automated engine plant and modern foundry . . . Hopes to challenge Chevrolet output . . . Plants are in partial production but will not go all-out until controls are lifted.

Two of Ford's newest weapons in the automotive production war are being tuned up in suburban Cleveland. In adjacent plants are Ford's newest automated engine plant and its most modern foundry, each now rounding into production.

The two plants are part of Ford's vast billion-dollar expansion program aimed at challenging Chevrolet's top position in auto production. When controls are lifted and free production is again the rule, Ford hopes to have the tools ready for competition.

New Mercury — The engine plant has already turned out more than 175,000 6-cylinder engines and will start construction of the new Mercury 8-cylinder powerplant when tooling can be completed. When tooling is ready, the plant will have a capacity of 4600 engines daily.

Adjacent to the engine plant is the foundry, now turning out all castings for Ford 6's. In this foundry the traditional dusty, smoky atmosphere is absent. Instead, the air is clean and working conditions are on a par with the best.

Charles H. Patterson, general manager of Ford Engine & Foundry Div., said approximately 15 pct of the foundry construction costs went into the ventilation system. It is capable of circulating 2.8 million cu ft of fresh air a minute.

Four of the foundry's eight molding lines are in operation. At its peak, it can turn out castings for 4600 engines a day, matching the capacity of the nearby engine plant. It can handle 1400 tons of hot metal daily. The Cleveland foundry is nearly equal in capacity to Ford's Dearborn foundry which is also being modernized.

Each plant employs the newest methods of production. The engine line is as fully automated as possible. Transfer Link — The engine block line consists of 42 automatic machines linked by transfers that perform 530 precision cutting and drilling operations on each casting before it is a finished block ready for assembly.

Machining of aluminum pistons requires 25 stations, also tied together with automation equipment. Cylinder heads, crankshafts, camshafts and flywheels are also processed with the aid of automatic handling.

Packards Aim at Two Markets

Packard last week showed its new models, separated into two distinct lines aimed at recovering class prestige while nailing down a share of the medium market. Exterior styling lines were retained but improved interiors and new engineering features were introduced on both lines. The new models confirmed president James J. Nance's promise to hold price lines.

Prices on the Clipper series will range from \$2,534 to \$2,795. Packards will go as high as \$6,900. Custom cars will not be ready for the market until early 1953. Engine hp has been increased from 155 to 180 hp on the Packard; from 135 to 160 hp on the Clipper de luxe models; and from 135 to 150 on the Clipper models. Packard is offering its own power-steering design as well as power brakes, ultramatic transmission and air conditioning.

New President for GM

Harlow H. Curtice will take over as acting president of General Motors Dec. 1, replacing C. E. Wilson, who abdicated from the presidency to become Secretary of Defense.

THE BULL OF THE WOODS

By J. R. Williams





When you have *Texaco Regal Oil* in the circulating system, your back-up roll necks get the best possible protection against heavy loads and high temperatures. *You* get trouble-free performance, longer bearing life, lower maintenance costs.

Texaco Regal Oil is turbine-quality oil that resists oxidation and sludging . . . keeps oil lines and bearings clean for uninterrupted flow of clean, cooling lubricant. There is a complete line of Texaco Regal Oils to meet your exact requirements.

In your enclosed reduction gears, use Texaco

Meropa Lubricant. It has outstanding "extreme pressure" properties, plus high resistance to oxidation, thickening and foaming . . . assures longer gear and bearing life, lower maintenance costs. For similar results on open gears, use Texaco Crater.

A Texaco Lubrication Engineer will gladly help you run all your machinery more efficiently. Just call the nearest of the more than 2,000 Texaco Distributing Plants in the 48 States, or write:

The Texas Company, 135 East 42nd Street, New York 17, N. Y.

TEXACO Regal Oils (HEAVY CIRCULATING OILS)



TUNE IN: On television -- the TEXACO STAR THEATER starring MILTON BERLE. See newspaper for time and station,

Government Industry Yields No Taxes

But private enterprise does . . . That's why some Congressmen change minds about public power, etc. . . . Treasury needs the taxes . . . Cite Wilson sale-to-the-public plan—By G. H. Baker.

New support for proposals that the Federal Government divest itself of some of the business enterprises it has entered into in recent years is building up on Capitol Hill.

Biggest reason why these proposals stand a better chance of being enacted into law in 1953 than at any time during the past 20 years: U. S. Treasury's increasingly acute needs for new sources of revenue.

Even congressmen who have steadfastly maintained that government had a "duty" to move into the electric power business, the telephone business, and the reclamation business now are changing their minds. What's helping them do so is that these projects yield fat taxes only under private industry.

Liquidate Debt—Charles E. Wilson, of General Electric, former defense mobilization chief, predicts that sale of government dams, generating equipment, and distributing facilities alone would permit liquidation of 10 pct of the national debt. Under this plan, government bonds would be exchanged for shares of stock in the new companies which would arise from the existing government agencies.

About \$1 billion a year in new taxes could thus be derived from the new business firms, Wilson estimates.


Unclear Motive? — Question some Washingtonians are asking is what President - elect Eisenhower will do next January to alter the tone of the Federal Trade Commission's "commercial survey" of the steel industry — if a change is needed by then.

It has been unofficially decided by a majority of the FTC to heed President Truman's request for an investigation of every level of the steel field. This would be allencompassing—including production, distribution, and consumption. Ostensible motive is to establish how the American consumer's dollar is spent.

But it has been strongly rumored that there is a method to this seeming innocence. This question has been asked: Will this survey be used as a means of broadening that favorite Democratic pastime of using steel as a whipping boy?

Assemble Data — Public hearings on this broad subject probably will get under way late next month or early in January. In preparation for the hearings, FTC staff members have begun to assemble existing data on how the U. S. sales dollar is spent—how much for materials, how much for labor, how much for overhead, etc.

In addition to the steel industry,



the commission also plans to conduct similar public investigations of some consumer durable goods and food industries.

A-Bomb Architecture—A change in architectural design of industrial and commercial buildings may be desirable in the near future. New types of buildings most suitable to today's unsettled international conditions may be windowless to a large extent. These will not quite match those pictured in science-fiction but they will be built in such a way as to lean or bend under the impact of an atomic blast.

A certain amount of "give" is needed to prevent breaking up.

Reasons are plain. Dispersal has never been more than a partial solution to the defense problem of more devastating atomic attack.

Greater Range—This is pointed up by Atomic Energy Commission's cautious statements and eyewitness reports on the latest atomic blast. Whether it was an A-bomb or an H-bomb, it's now clear that distances of from 5 to 10 miles from the point of explosion are no longer safe except with protective measures.

What then is the next step? A change in architecture and industrial building design, say engineers and architects after long study. They have already come up with new design methods which have been tried and have survived.

Don't Wait—A basic principle calls for as few windows as possible, particularly on the lower floors. Other methods are technical in nature, being based upon usable theories of the Army's Corps of Engineers.

Officials would like to see changes start immediately. The reason is that the building rate is now about \$30 billion annually. About one-half this amount goes into structures in which the nation's labor force spends its working hours.

Why buy costly special equipment?

Convert your standard machines to produce difficult jobs with Twrchan DUPLICATORS

- Now and in the future your plant will be ahead with Turchan's speed and efficiency.
- Users report 80% to 600% savings in costs.
- Intricate profiles and contours made easy.
- No special form tools or skilled help required.
- Greatly expands versatility of the machine.
- Job handling and set-up time reduced over half.

hi

th

th

Al

th


\$1

du of

pe

DI


- Accuracies + .001" and finer surface finish.
- Chance for rejects completely eliminated.
- Instantly reconvertible to manual operation.




While producing this irregular contour, the tracer guides the varying height of table. Result: faster, automatic precision control.



Contouring of unusual shaped washing machine part to close tolerance. Turchan method cut time to $\frac{1}{3}$ of conventional way.



Standard planer gains versatility with the Turchan attachment; machines contours of a blower section as easily as straight work.



Turchan dual 45° attachment machines shaft and faces disc of this jet engine part in the same set-up. Simplifies all difficult jobs.

TELL US YOUR PROBLEMS: Send a blueprint or model of job with specifications for an estimate. Give make and model number of machine. Our engineering department is at your service,

Write for New 20-Page Catalog



ALUMINUM: Name Fifth Producer

Olin Industries, Inc., signs up for 110,000-ton share of third round... Certificates granted... Government may not stop at 200,000-ton goal in this round—By A. K. Rannells.

Potential production figures for primary aluminum rose to a new high of 1,637,000 tons last week as a fifth firm prepared to enter the industry with the blessing of the government.

Olin Industries, Inc., of East Alton, Ill., is to be the fifth and newest aluminum producer. The firm had been mentioned prominently during negotiations for a third round of capacity increase.

Defense Production Administration last week said that two certificates of necessity, covering \$170 million worth of construction, had been issued to Olin.

Raw and Finished — One certificate was for \$123 million for construction of facilities for producing an additional 110,000 tons of primary aluminum. The government will allow fast tax write-off for 85 pct.

A second certificate was issued for \$46 million worth of facilities for production of sheet, plate, and extrusions. It allowed only 50 pct coverage for tax amortization purposes.

From these facilities are expected to flow about 40,000 tons of wide, high strength aluminum sheet and an estimated 12,000 to 15,000 tons of extrusions.

No other government aid except probable materials priorities is to be given the new entrant to the field, DPA says. Facilities are to be built entirely with private financing at a location yet to be decided.

On Oct. 1, the DPA had revealed that after months of indecision it had finally decided another round of aluminum expansion was needed.

This new target called for 200,-000 tons in new capacity. It was to be reserved for new entrants to the field. And a little later, DPA said it had received six or eight "firm and sound" proposals.

May Exceed Goal—The new certificates give Olin the major portion of the proposed new capacity. However, it was not expected that DPA would hew strictly to the line in its new goal but might approve facilities somewhat in excess of the remaining 90,000 tons.

In fact, there is talk of a fourth round of aluminum expansion. This may range from 200,000 to 400,000 tons.

With Olin's entrance into aluminum basic capacity increases to a potential 1,637,000 tons. This includes capacity in place, under construction, or planned.

About 430,000 tons is now under construction, or projected.

The Line—Existing and projected capacity is roughly divided up as follows:

Aluminum Co. of America, eight plants, 654,000 tons; Reynords Metals Co., six plants 415,000 tons; Kaiser Aluminum & Chemical Corp., three plants, 408,000 tons; Olin Industries, Inc., 110,000 tons; and Anaconda Aluminum Co., one plant, 50,000 tons.

Expansion by the "big three" is nearing the final stages while the Anaconda program is scheduled for completion next year. No estimated date had been set last week for Olin.

Atomic-Powered Carrier Planned

Likelihood grows that the first atomic-powered aircraft carrier will be built at Newport News, Va., where the super-carrier Forrestal is under construction.

The Forrestal itself and a sister ship being built at the New York Naval Shipyard will have conventional engines. However, Newport News Shipbuilding & Drydock Co. has recently been named as subcontractor to Westinghouse Electric Corp. in handling a project for development of an atomic engine "for a major warship such as an aircraft carrier."

New Cabinet Appointments


Secretary of State — John Foster Dulles, 64, experienced government advisor on international affairs. Engineered the Japanese Peace Treaty. Held his first diplomatic post in 1917.

Secretary of Defense—Charles E. Wilson, 62, president of General Motors since 1941. Earned \$566,200 last year to rank as the nation's top paid business executive. He is opposed to the closed shop but originated the escalator wage plan.

Secretary of Interior—Douglas McKay, 59, former Senator and present Governor of Oregon. Favors development of natural resources but is opposed to present administration's method.

Secretary of Treasury— George M. Humphrey, 62, is present chairman of M. A. Hanna Co., Great Lakes ore shipping concern. He is also an official of four other major companies. In 1948 and 1949 he served as chairman of the Industry Advisory Committee of the Economic Cooperation Administration.

Attorney General — Herbert Brownell, Jr.. Nebraska - born lawyer and New York political leader. Received law degree at Yale, practiced profession in New York, specializing in civil rather than criminal phases. Member of State Assembly from 1933 to 1937. Has been key advisor to Gov. Dewey since 1942. First action after being named to cabinet post was to request that J. Edgar Hoover be retained as FBI head.



QUICK ••• economical replacement of worn bearings in machine tools and industrial machinery with Bunting Standard Stock Bearings in 854 sizes.

EASY ••• installation of new bronze bearings in electric motors with Bunting Electric Motor Bearings in 324 sizes.

• • • economical production of special bronze bearings and parts with Bunting Precision Bronze Tubular and Solid Bars in 263 sizes.



Bunting Ads win 1st award in contest sponsored by Industrial Distributors Associations.


Life of production equipment and machinery is prolonged, and down time avoided by the ease and speed with which Bunting Standard Stock Bearings, Electric Motor Bearings and Precision Bronze Bars can be obtained and employed.



BRONZE DEARINGS - RECISION DIRECTOR

IN STOCK EVERYWHERE

Bunting products are instantly available in all markets, from the stocks of leading industrial distributors and distributors of specialized industrial items. Ask your distributor or write for catalog.



THE BUNTING BRASS & BRONZE COMPANY . TOLEDO 1, OHIO . BRANCHES IN PRINCIPAL CITIES

ke

by

30

Gi

pe

T

Coast Shipbuilding Stages Comeback

Bethlehem Pacific lays keel for first of five Maritime Commission freighters . . . First seagoing ships to be begun in West Coast yards in 8 years—By T. M. Rohan.

Shipbuilding in the West came back to life last week. Bethlehem Pacific at San Francisco laid the keel for the first of five Maritime Commission cargo ships—the first oceangoing vessels to be started in the West in 8 years. Long delayed by the steel strike, reshuffling schedules and priority snarls, the 30-ton assembly of 1-in. plate was swung into place with brief ceremonies.

The \$9.5-million, 12,900-ton Golden Mariner will be the first of five Maritime Commission transports to be built in a \$47 million program at Bethlehem Pacific. Thirty others will be built in eastern yards.

Shipyard Manager T. C. Ingersoll said the Golden Mariner, already well under way in subassemblies, will be completed in a year. Heavy plates, which must be brought from the East, are now coming through fast enough for orderly production and "we'll probably be getting all we need by the second quarter." Shipbuilding employment is now about 400 and will hit 2500 by December, 1953, with a 3500 peak later on.

New Aluminum Plant-Harvey Machine Co. of Los Angeles got its foot a little farther in the door of the aluminum production picture last week. Through a Defense Production Administration application, news got out and was confirmed by L. A. Harvey, vice-president, that the firm hopes to build a \$45 million aluminum reduction plant near Dalles, Ore., 80 miles east of Portland on the Columbia River. Annual capacity would be 54,000 tons and construction would start immediately on granting of a certificate.

Harvey already has a piece of the 72,000-ton Anaconda-Harvey plant at Kalispell, Mont., scheduled to start in 1953. The current Harvey bid is the only western one of four others hoping to get in on the 200,000 tons added U. S. capacity that D.P.A. wants.

Harvey reports private financing has been arranged. In view of the government program a fast tax write-off is probable. Options have reportedly been taken for 80,000 kw from Bonneville Power Administration and two local utility districts plus 60,000 kw interruptible from Bonneville. Power would come from the new McNary dam, 100 miles up the Columbia River.

Local Opposition—Some opposition has already been registered from power-starved local industrial leaders who last week got ready for another cut.

Defense Electric Power Admin-



istration queried industries in Seattle and Portland on how additional 10 pct cuts in December, January and February would affect them. Most agreed it would mean a 3 or 4-day week. Many have already stopped all overtime and Saturday work and layoffs by aluminum producers are widespread. Chances for defense work exemption appear slim because of the preponderance of these in the area.

"No Gas, No Water"—North of the border the British Columbia land minister came up with a power play. Robert Sommers said if the U. S. wants water rights to build a dam at Libby, Mont., for more power, Seattle interests must stop opposition to importation of Peace River, Alta., natural gas.

The proposed dam would back up the Kootenay River into Canada and a water rights controversy has ensued. Mr. Sommers said British Columbia "holds the trump card in this international poker game and if the Americans don't take the gas they don't get the water."

Some Predictions—Western steel warehousemen got some food for thought last week from H. G. Batcheller, Allegheny-Ludlum's board chairman who made a western swing with E. J. Hanley, president; Clark King, vice-president, and Walter S. Doxsey, American Steel Warehouse president.

Some Batcheller observations and predictions in San Francisco:
The U. S. will need 150 million ingot tons output in 20 years.

Depletion of high grade Mesabi ores doesn't present an insurmountable crisis but a challenge which is developing new ways of utilizing lower grade ores and forcing more efficient use of other mineral resources.

New era of physical metallurgists will not end steel age but improve alloys and utilize metals such as germanium, gallium, and titanium.

GE





The ultra modern Lucas plant is being used to full capacity with work in process and rough castings waiting to be machined.



m to

st

de er


of n

86 A

Lucas machines at work making components for more Lucas machines, in our plant and in the shops of many outside suppliers.



Still no sacrifice of Lucas standards. Ultra modern production methods, but still the skilled hand craftsmanship for which there's no satisfactory substitute.



More shipments than ever, but, of course, defense priorities dictate who gets what. Perhaps this is the machine we originally scheduled for you.

Your inquiry and your order are as welcome as ever at Lucas. Today's conditions won't last forever and your Lucas Horizontal Boring Milling and Drilling machine will always be a time saving money maker.



LUCAS MACHINE DIVISION . THE NEW BRITAIN MACHINE CO. . CLEVELAND 8, OHIO

Gage Supply Indicator Hits Low

Capacity not sufficient to match machine tool needs . . . New weapons and skilled labor shortage increase pressure . . . Capacity expansion goals examined—By E. C. Beaudet.

To put a metalworking defense plant into production three fundamental items are needed: Machine tools, cutting tools and gages. The three go hand in hand. Without one the others are of little value.

With machine tool shipments steadily rising and cutting tool requirements being filled, it auddenly appears there may not be enough gages to go around. Ways of meeting the growing gage demand is one of the major concerns of government and industry right now.

Facts and figures are being assembled by National Production Authority's Metalworking Div. in preparation for recommendations to Defense Production Administration on the amount of gage capacity needed to meet defense requirements. Recommendations on additional capacity will be submitted to the top brass shortly.

How Much?—Two key officials concerned with the matter say a minimum of \$25 million worth of new capacity is needed. But some claim the gage industry is far too small for a big defense program and think twice as much capacity is required for reasonable safety.

There is no shortage of standard gages at present. However, "selective" or special types are in extremely short supply. Deliveries on these specialized items are running from 60 days to 6 months or more behind requested delivery dates.

The Reasons — Reason for this holdup is two-fold. First, it is largely a shortage of special gage capacity for military applications. Constant changes in specifications as new weapons are developed add strength to demand. New weapons force use of more gages of finer

precision so that faster production can be obtained.

Second factor entering into the problem is manpower shortages. Additional skilled labor at present would have to come from the tool and die industry. In an emergency, this is a "rob Peter and pay Paul" policy.

Intensive Study — The expected recommendations for greater capacity are being made only after a long and extensive survey of the industry. This has included studies of both industry and government arsenals. Comments and recommendations as to how the expansion should be achieved have been sought from both.

It is expected that the recommendations will call for greater governmental participation than in most other expansion programs. Reason for this is that a substantial portion of new capacity will be for production of the special types of gages needed to boost military output. They will have little or no application to nonmilitary production.

Labor Supply—In addition, it is believed the recommendations will suggest that new capacity be developed in areas where gages are not being produced at present. This would include such areas as New England, rather than Detroit and the Midwest, because it would be easier to obtain and train workers.

New Plan—Construction of a \$5 million plant for production of heavy special machine tools weighing as much as 250 tons was begun recently by Kearney & Trecker Corp., Milwaukee. More than \$25 million worth of machine tools will go into the 173,000 sq ft of manufacturing space in the new plant. Completion is expected around mid-1953.

Primary purpose of the plant is to meet the needs of the Air Force's \$400 million heavy press programs. Growing out of the aircraft press program is need for new tool capacity to machine die blocks used in the presses and the forgings made on them. Some of these die blocks weigh over 10 tons. Forgings are as long as 20 ft.

Civilians, Too—Francis J. Trecker, president of the company, pointed out that although Defense Dept. would have first call on the new plant's capacity, a great part of it will be available for civilian producion. This is due to the fact that the government is now interested in additional defense capacity to be called upon in an emergency rather than in immediate production.

The plant will have crane facilities to handle machine parts weighing up to 50 tons. When in production it is expected to employ about 400 workers, 80 pct of whom will be skilled machinists and assemblers. Many of these will be transferred from the company's West Allis, Wis., plant.





Manufactured by — THE MOTCH & MERRYWEATHER MACHINERY [O. —

Builders of Circular Sawing Equipment, Production Milling, Automatic and Special Machines

M

PRODUCTION - WITH - ACCURACY . MACHINES AND EQUIPMENT

1

U. S. Looks North for Nickel

To meet new nickel goal of 190,000 tons in 1955, U. S. will have to rely on Canada . . . May have to share in expansion expenses . . . New mines a must—By F. Sanderson.

A new nickel supply goal of 190,000 short tons annually, set by the U.S. Defense Production Administration for 1955, has swung more interest to nickel deposits in Canada. The U.S. goal represents an increase of 58,000 tons over the 1954 mark set earlier this year and is 89,000 tons more than the 1950 supply of 101,000 tons.

The U.S. is a small nickel producer and must depend on outside sources for the big jump in its supply goal. Last year the U.S. produced only 762 tons of new nickel and obtained 88,000 tons from Canada.

Main Source-While the U. S. will obtain nickel from other countries outside Canada, it can be taken for granted that U.S. purchasing agencies are depending more on this country than any other to fill its 1955 target.

The Canadian mining industry is aware of the part it must play in providing America's record nickel supply. It is acting accord-

er's

es a

me

um

oot

you

sav-

oer-

AGE

While Sudbury, the home of the world's greatest nickel producers, is rapidly expanding, the search for new deposits is extending across the Dominion. Known deposits that produced in a limited way many years ago or received only slight exploratory attention are being gone over carefully as new-producer prospects.

Meet the Tab-If the U.S. wants Canada to be the prime supplier in the new nickel program, it may be required to foot the much larger bills entailed in developing new properties here.

U.S. has already made some important financial deals with Canadian ply-with Sherritt-Gordon, Falconbridge Nickel, East Rim Nickel, Milnet Mines. Others are said to be pending. They will boost annual supply available to the U.S. by some 15,000 tons. Production from these companies should have a stimulating effect on U.S. supplies next year. But to meet the full requirements Canada will have to go much farther along the road of discovering new deposits. Increased production so far arranged represents only about 15 pct of the additional U.S. supply suggested for 1955.

International Nickel Co. of Canada has been proceeding with an extensive program of mine development to enable it to maintain production at its current level. So far the company hasn't announced plans to substantially increase output. Falconbridge Nickel is stepping up production but the

companies for increased nickel sup-

"You really take rest period seriously,

majority of other producers seem to have about reached the limit.

It appears that any big supply increase must come from new mines. Consideration must also be given to the problem of establishing plants for ore concentrating and metal refining.

Output Boosted-Barvue Mines Ltd., which has a contract with a U. S. Steel Corp. subsidiary to supply 175,000 tons of zinc concentrate, is gradually stepping up production. Last week the company put its second unit into operation and is now handling 2400 tons of ore daily. A third unit is expected to start this week which will permit an increase to 4000 tons daily.

Fourth and final unit will go in as soon as sufficient power is made available, possibly early next year. With all four units operating, the mill will handle upwards of 6000 tons a day. Concentrates now being turned out average between 59 and 60 pct zinc. Already nine carloads have been shipped.

Construction-Iron Ore Co. of Canada Ltd. is making good progress on various construction operations associated with its big iron ore production program in the Quebec-Labrador area. The company can begin its 10 million tons a year production and shipping set-up in 1954, but to reach the larger objective of 20 million tons annually, the St. Lawrence Seaway will be necessary to provide shipping facilities.

More than half the grading for the 360-mile railway has been completed and the first 80 miles of steel has been laid. At Seven Islands on the north shore of the St. Lawrence River, three-quarters of the giant ore docks have been completed.

When the mine actually goes into production a train carrying 10,000 tons of ore will arrive at the Seven Islands port every three hours for 6 months each year.



Complete line equipment with latest improved operating features. Maximum volume production with minimum floor space requirements. If you are interested in a new installation or improving your present equipment why not investigate the Youngstown Line!

- Coil Box with Strip Opener.
- ☐ Triple Processor with Roller Leveller.
- ☐ Flash Welding and Mechanical Stitching.
- Single Cycle Up-Cut Shears.
- Heavy Duty Rubber Covered, Brick Lined Steel Tanks.
- ☐ Magnetic Loop Control for Acid Tanks.
- ☐ Fume Exhaust System Roto Clone Scrubber.
- Automatic Control System for Temperature and Acid Proportioning.
- ☐ Side Trimmer with Scrap Cutting or Balling.
- Up-Coiler with Strip Oiling System.
- ☐ Entry and Exit Coil Conveyors.

Youngstown Foundry

OVER SIXTY YEARS OF SERVICE TO THE STEEL INDUSTRY

Youngstown, Ohio

ne

It

an

M ne

ha

th di m Ty

st

Fi hy

ha

M

ru

T

te

ga

te

fu fo

PUBLICATIONS

These publications describe money-saving equipment and services . . . they are free with no obligation . . . just circle the number and mail the postcard.

Lubricating oil

High temperatures encountered in industrial operations emphasize the need for a lubricant that is heat resistant. Dag Colloidal Graphite meets this requirement effectively. It is inert and clings stubbornly to sliding or rubbing friction surfaces and retains its lubricating properties even under high pressures. In addition, Dag is economical to use. More information is available in a new folder. Acheson Colloids Co.

For free copy circle No. 1 on postcard.

Lathes

Lodge & Shipley's 30-in. T-Matic Lathes, covered in a new bulletin, have been designed for fast, precise automatic duplication of short, thin-walled section work of large diam. The lathes come in three models, Type X for contour facing, Type Y for contour facing and straight rough and finish turning, and Type Z for contour facing and straight rough and finish boring. Fully automatic, the T-Matics are hydraulic-tracer-controlled and have infinitely variable speed drive. Lodge & Shipley Co.

For free copy circle No. 2 on postcard.

Furnaces

Marshall tubular furnaces have been specially designed for the research engineers working on stress-rupture, creep and tensile tests. These furnaces provide uniform temperature distribution over the gage length of the specimen. Closelimit temperature control can be maintained in short or prolonged tests. More information on the furnaces is contained in a new folder. Marshall Products Co.

For free copy circle No. 3 on postcard.

Signals chart

Macwhyte Co. has made available a handy wall chart which lists crane signals and suggestions for proper use of slings. On the reverse side of the chart are tables listing strengths and safe loads for Atlas 8-Part Braided Slings and Monarch Single-Part Slings. Sling strengths range from 2/5 tons to 243.4 tons. Macwhyte Co.

For free copy circle No. 4 on postcard.

Castings

The Rolle method of casting magnesium and aluminum is outlined in an interesting new bulletin. Source materials, production and control techniques, and product analysis are all covered in the publication. In addition there is a section on the company's fiberglass laminated plastics. Rolle Mfg. Co., Inc.

For free copy circle No. 5 on postcard.

Turn Page

use postcard below

Postcard valid for 8 weeks only, information may be secured subsequently by separate letters fully describing each item wanted, including company name.

PERMIT No. 36 (Sec. 34.9 P.L.&R.) New York, N. Y.

BUSINESS REPLY CARD

No postage necessary if mailed in the United States

POSTAGE WILL BE PAID BY

THE IRON AGE

Post Office Box 77 Village Station NEW YORK 14, N. Y.

						use own								
1	2	3	4	5	6	7	8	9	10	11	12	13	14	1
6	17	18	19	20	21	22	23	24	25	26	27	28	29	3
1	32	33	34	35	36	37	38	39	40	41	42	43	44	4
16	47	48	49	50	51	52	53	54	55	56	57	58	59	6
AG	Ε			. PRO	DUCT									
	Ε			·····										
AG	Ε													_
OL	IR NA	ME								TITLE				
01	IR NA	ME						****	****	TITLE				

Continued

Wheelbarrows

Outlined in a new specification sheet is a wide variety of wheel-barrows designed to meet many different needs. Among the units described are heavy duty contractors' barrows, large capacity concrete barrows and medium capacity contractors' barrows. Kilbourne & Jacobs Mfg. Co.

For free copy circle No. 6 on postcard.

Pumps

A complete line of English pumps and related equipment is described in a new booklet issued by Pulsometer Engineering Co., Ltd., which is planning to open an office in New York. Covered are an extensive group of centrifugal pumps, rotary, reciprocating and vacuum pumps, refrigeration units and other equipment. Pulsometer Engineering Co., Ltd.

For free copy circle No. 7 on postcard.

Regulators

A revised 22-p. application booklet on Rototrol rotating regulators for the steel industry is available from Westinghouse Electric Corp. This edition presents up-to-date information on Rototrol's functions, applications and accomplishments as a control unit for steel producing and processing equipment. Fourteen different applications for steel mills are described. Westinghouse Electric Corp.

For free copy circle No. 8 on postcard.

Drills

Carlton radial drills feature centralized controls, low-hung drive and power-operated mechanical clamping of arm, head and column. Detailed in a new bulletin, complete specifications of the company's five drill models are given. Carlton Machine Tool Co.

For free copy circle No. 9 on postcard.

use postcard below

Postcard valid for 8 weeks only. Information may be secured subsequently by separate letters fully describing each item wanted, including company name.

Posto	ard val	id 8 w	eeks on	y. Aft	er that	use own	letter	head fi	ally des	cribing	item w	anted.	11/2	7/5
Circ	le nun	nbers	for Fr	ee Pu	blicat	ions or	info	rmatic	n on	New E	quipm	ent:		
1	2	3	4	5	6	7	8	9	10	11	12	13	14	13
16	17	18	19	20	21	22	23	24	25	26	27	28	29	3
31	32	33	34	35	36	37	38	39	40	41	42	43	44	4
46	47	48	49	50	51	52	53	54	55	56	57	58	59	6
PAG	/E	****	****	.FKO	DUCI	* * * * *	* * * * *		* * * * *		*****	* * * * *		
PAG						****								
rol	IR NA	ME				* * * * * *				.TITLI	E		* * * * *	
COL	MPAN	Y												
-01														
		RESS												
co.	ADDI													

FIRST CLASS PERMIT No. 36 (Sec. 34.9 P.L.&R.) New York, N. Y.

BUSINESS REPLY CARD

No postage necessary if malled in the United States

POSTAGE WILL BE PAID BY

THE IRON AGE

Post Office Box 77 Village Station NEW YORK 14, N. Y.

Burner assemblies

For the most satisfactory results on furnaces requiring a constant condition of furnace atmosphere and high combustion efficiency, tunnel burners with sealed-in nozzles are particularly satisfactory. Hauck tunnel burners are completely assembled units consisting of a sealed-in gas burner nozzle, a flanged burner mounting box and a refractory tunnel block. The company's burner assemblies and gas burner nozzles are comprehensively covered in a new leaflet. Hauck Mfg. Co.

For free copy circle No. 10 on postcard.

Pins, springs, bolts

Producto dowel pins, die springs, stripper bolts and cap screws are conveniently listed in an 8-p. catalog recently published by Producto Machine Co. Each product is illustrated and described in detail with technical drawings, specifications and easy to read price tables. Producto Machine Co.

For free copy circle No. 11 on postcard.

Handling equipment

Proper handling of parts in metal-working plants is a vital factor in speeding operations, stepping up quality and reducing costs. A new catalog describing Rolock fabricated alloy handling equipment has just been released. Of particular interest to manufacturers of steel shell cases are the new-type work-holder baskets which serve through automatic cycles of many operations, Rolock, Inc.

For free copy circle No. 12 on postcard.

Coil holders

Acme Steel Co.'s coil holders improve wire stitch operations because wire feed is uniform and smooth. Wire is prevented from overrunning due to the coil holder's positive brake action. As wire begins to feed the long spring arm moves with the wire instead of against it. The coil holders are available in 25 and 50-lb models. More information is contained in a new folder. Acme Steel Co.

For free copy circle No. 13 on postcard.

Turn Page

YOU

Ne

it doesn't look like a turret lathe, BUT...

nt

re

y,

ozry.

m-

ng

le,

nd

he

re-

et.

gs,

tacto
usith
ons

talin
up
new
brihas
ular
teel
orkugh
era-

d.

imbeand rom ler's bearm of are


dels.

rd.

- It sets up fast-like a turret lathe.
- It uses turret lathe tools.
- It machines turret lathe lots, on an automatic basis, without the usual penalties of automatic operation.
- It will combine certain operations not possible in accepted turret lathe practice, thus reducing machining time.
- It will automatically change speeds and feeds under cut to assure more efficient performance of your cutting tools.
- It requires less skill to operate—and one man can handle two or more machines.

... it is the Warner & Swasey 1-AC Single Spindle Automatic Chucking Machine.

With today's emphasis on greater production, there are undoubtedly certain jobs in your shop that could be machined faster and better on the 1-AC. Call in your nearest Warner & Swasey Field Engineer—he'll show you exactly how it can improve your operation.



YOU CAN MACHINE IT BETTER, FASTER, FOR LESS WITH WARNER & SWASEY TURRET LATHES, AUTOMATICS AND TAPPING MACHINES

November 27, 1952

71

Free Publications

Continued

Millers

Designed primarily for quantity production of small intricate parts, Multi-Millers have also proved profitable in the milling of such parts in small lots. The automatic table cycle of fast approach, cut at desired speed and fast return to loading position enables a single operator to handle a battery of machines. U. S. Tool Co., Inc.

For free copy circle No. 14 on postcard, p. 69.

Presses

Information on Lake Erie Engineering Corp.'s complete line of hydraulic bulldozers is contained in a new leaflet. These heavy-duty presses simplify numerous hot and cold bending and forming operations, cut die costs, save time on setups and are ideal for work on long pieces. Lake Erie Engineering Corp.

For free copy circle No. 15 on postcard, p. 69.

Metal washing

A new illustrated bulletin on metal washing equipment has just been prepared by Despatch Oven Co. The bulletin illustrates and describes typical Despatch washers from single stage units for simple wash jobs to multiple stage machines used to prepare metal for fine finishes. Despatch Oven Co. For free copy circle No. 16 on postcard, p. 69.

Dehydrators

Water vapor in moisture - laden gases affects product quality and causes operational difficulties due to condensation. Selas dehydrators are designed to remove this moisture to protect products from corrosion and freeze-ups. More information is available in a new booklet. Selas Corp. of America.

For free copy circle No. 17 on postcard, p. 69.

Metalworking saws

A combined slitting and grooving saw, the North American Woodsman, designed for the metalworking industry, is outlined in a new mailing piece. Carbide-tipped, the saw is reported to hold its size, cut faster, give longer service and finer finish. North American Products Co.

For free copy circle No. 18 on postcard, p. 69.

AGNAFLUX

Now Announces, Spotcheck

a simple SPRAY-ON DYE PENETRANT inspection

ity rts. ved ich tie at to gle na-

gi-

of in uty and ra-

> on on

er-

. 69.

etal een Co.

de-

ers

ple

ma-

for

. 69.

den and

due

tors

ois-

corforclet.

0. 69.

ing

ods-

ork-

new

the

cut

iner

ucts

p. 69.

GE



END GUESSWORK ARGUMENTS!

Use it to Locate and Mark **Defects Open to the Surface** in Metals—Carbides—Plastics -Ceramics-Practically any Non-Porous Solid



Spotcheck crack indication revealed in inspection of local area of punch press frame.

Spotcheck is a new, lowest cost inspection tool for use where remote location, small surface areas, limited volume or the cost of disassembling equipment makes use of fixed inspection equipment impractical. The complete kit is as easy to carry as a

A new member of the world's best known Magnaflux family of inspection methods, Spotcheck finds and indicates cracks, porosity, laps, seams, etc., clearly and unmistakably. It takes the guesswork out of countless sampling inspection jobs.

Used for maintenance inspection, local and routine Spotcheck tests will help you to prevent costly on-the-job failure of production machines. SPOTCHECK IS IDEAL FOR INSPECTION OF CARBIDE TOOLS AND OTHER TOOL CRIB USE!

SPOTCHECK INDICATIONS









TIGHT CRACK OR PARTIALLY WELDED



How Spotcheck shows

up non-visible crack

in carbide tool. Correct grinding! Avoid

failure after set-up!

Complete Spotcheck Kit No. S

8 12-oz. cans; 4 of Cledic 2 each of Penetrant and Developer, together with carry-ing case, plus instructions and accessories.

LOW IN FIRST COST E 00

> plus \$1.00 packing and shipping



CORPORATION

5902 Northwest Highway, Chicago 31, Illinois New York 36 • Cleveland 15 • Detroit 11 • Dallas 9 • Los Angeles 58 Export Distributor: Curtiss Wright Corp.
In Canada: Williams & Wilson, Ltd.

MAIL NOW

MAGNAFLUX CORPORATION
5902 Northwest Highway • Chicago 31, Illinois

Type SK-1 SPOTCHECK KITS @ Please send \$35.00 each, plus \$1.00 each, packing and shipping cost.

- CHECK ENCLOSED. Amount: \$.....
- Send, on our P.O. Number ☐ Send only FREE illustrated Bulletin, now ...


Name Title

Company Address

City Zone State

NEW EQUIPMENT


New and improved production ideas, equipment, services and methods described here offer production economies . . . just fill in and mail the postcard on page 69 or 70.



Horizontal broach has high operating speeds

A new mechanically-driven horizontal broaching machine features an operating speed of 150 fpm or more, to remove a large amount of material in the shortest possible time. It is rugged, heavy, and rigid and can be equipped with drives up to 200 hp for powerful, high-speed broaching. Offered with strokes ranging from 66 to 200 in., the machine is built around a special electric drive to give it great

flexibility. On its reciprocating table, there can be mounted whatever type indexing may be required to suit any size or shape of disks and wheels now being made for jet engines. Suitable hydraulic units are built within the base of the machine, but actual operation of the main work slide is done mechanically. The machine has dual speed. Lapointe Machine Tool Co. For more data circle No. 19 on postcard, p. 69.



New drilling machine for jet engine housings

Five-way drilling machine for jet engine housings features interchangeable multiple drill heads on two of the five stations. This enables the production of several types of housings having a variety of bolt circle specifications on faces with identical radial locations. Loading, clamping and indexing of the housings in the fixture is done manually and indexing between operations is manual. The table can be indexed in a clockwise direction only. Eight stations and 9 operations complete the drilling and tapping of holes. Modern Industrial Engineering Co.

For more data circle No. 20 on postcard, p. 69.



Girth welding machine for tank production

A press and girth welder is engineered to make fillet and burn-through circumferential welds. It features a built-in 5-ton hydraulic press for the assembly of parts prior to welding. A two-pressure hydraulic system is incorporated with high pressure for assembly and low for holding parts during

welding. The press is under pushbutton control and the eject and reload cycle is automatic in operation. Manual longitudinal and radial positioning of the welding heads is provided to cover the machine range. Capacity is 9 to 24, 12 to 36 or 18 to 48 in. diam, to 96 in. long. Morton Mfg. Co.

For more data circle No. 21 on postcard, p. 69.



Transfer unit machines 75 cylinder blocks per hour

An 18-station automatic transfer machine performs 110 machining operations in 38.3 sec. Drilling, reaming, boring, counterboring, and core-drilling operations are performed in machining the banks, sides, and starter-mounting pad of the blocks. Cylinder blocks are

received with pan-rail up. A turnover fixture at the first station raises, rotates and deposits the block pan rail down in which position it remains during machining operations. Greenlee Bros. & Co.

For more data circle No. 22 on postcard, p. 69 Turn Page

whatuired disks or jet units the n of medual l Co.

done n ope can

ction

peratapstrial

p. 69.

push-

and

pera-

d ra-

lding

ma-

4, 12

6 in.

p. 69.

our

turn-

ation

the

posi-

ning

p. 69

AGE

To.

"Bill, making or losing money today can depend on

The Turn of a Screw!"

"Stop pulling my leg," Bill retorted skeptically.

"I'm not exaggerating. You can't afford to take your fasteners for granted," Bob insisted. "I'm saving time—and time is money—just by following the RB&W man's suggestion to use another kind of screw in my TV sets."

"What kind?" asked Bill.

"RB&W's new SPIN-LOCK Screw," answered Bob. "It has a patented feature—ratchet-like teeth under the head—that not only locks into the surface and holds tighter, but also speeds assembly. It does away with extra parts and special handling. Bet your switches could use 'em, Bill."

MORAL: Look to your fasteners for an often overlooked opportunity to reduce costs, and strengthen your competitive position. New fasteners may prove more efficient than the ones you're now using. Or you may save by the stepped-up production you get from using the finest fasteners . . . RB&W bolts, nuts, rivets and screws of uniform accuracy, dependability and physical properties.

Let RB&W help you make the most efficient use of fasteners on your assembly line. Address RB&W at Port Chester.


RB&W—The Complete Quality Line. Plants at: Port Chester, N.Y., Coraopolis, Pa., Rock Falls, Ill., Los Angeles, Calif. Additional sales offices at: Philadelphia, Pittsburgh, Detroit, Chicago, Dallas, San Francisco. Sales agents at: Portland, Seattle. Distributors from coast to coast.

RUSSELL, BURDSALL & WARD BOLT AND NUT COMPANY

RB&W 107 YEARS MAKING STRONG THE THINGS THAT MAKE AMERICA STRONG

November 27, 1952

Continued



Versatile saw cuts stacked sheet metal

Fifty to 70 stacked galvanized sheet metal sheets can be cut at the rate of 15 ipm with an improved, heavier model sheet metal saw having all cast frame. It is an all purpose 14-in. ball bearing band saw, with blade speeds from 125 to 2200 fpm, quickly adjustable for cutting metals, plastics, wood, iron and steel castings and forgings, and other materials, without blade chatter. Intricate cutting jobs encountered in ductwork fittings can be done on this saw in a fraction

of the time necessary for hand-cutting. The 20 x 22 in. table permits handling of large work. Case hardened guides with carbide back-up bearing assure positive blade control and cutting accuracy. Flanged wheels control blade for smooth radius cuts and perfect straight line cuts. Complete equipment includes a set of 4 sheet metal clamps and riser bar insert to match for cutting stacked sheet metal. Bett-Marr Mfg. Co.

For more data circle No. 23 on postcard, p. 69.



Tumbling barrel boosts production

A flask-type, direct motor drive, tilting tumbling barrel is said to give better work action for deburring and burnishing precision parts both ferrous and nonferrous. The machine may use all types of deburring and burnishing media; is available for loads ranging to 750 lb. The flask-type barrel is constructed of continuous welded sections of heavy steel plate. A ¼-in. lining of abrasion resistant rubber or neoprene vulcanized to the bar-

rel provides effective insulation to give longer life to the barrel shell while protecting parts against nicking and scratching. Direct drive is provided with a 1 hp motor mounted directly above the worm segment for balance and space economy. A heavy cast iron base and special high-strength alloy pedestal supports capacity loads in continuous service. Barrel speeds can be as low as 17 rpm. Hupp Corp.

For more data circle No. 21 on postcard, p. 69.



Die puller has 30,000 lb capacity

Improved operator vision and better maneuverability characterize this die pulling truck. This line of equipment, available in 10,000 to 50,000 lb, is intended for handling stamping and forging dies on and off press beds; they are frequently used as load carriers and for machinery moving. A power operated

cable winch located on the uprights pulls heavy loads on the load platform. When looped over sheaves at the end of the platform it will push load off the platform. Motive power is supplied by either a storage battery or gas-electric unit. Elwell-Parker Co.

For more data circle No. 25 on postcard, p. 69.



Compact bench mill accomplishes heavy work


Heavy work ordinarily requiring larger, expensive mills can be done on a new, compact bench mill of sturdy design and great rigidity. Work requiring a 12-in. in length. 9-in. vertical and 5-in. cross travel is possible on the 5 x 20 in. table surface. The large diameter spindle supplied with a No. 10 B&S or No. 4 Morse taper and operating at 15 separate forward or back-

ward speeds is equipped with large Timken bearings. All ways are dovetail type and are hand scraped; table and knees are exceptionally wide. Milling of table T slots from solid insures inflexible anchoring of work itself. Work is power fed at 0.003, 0.006 or 0.012 per spindle revolution. Rotex Punch Co.

For more data circle No. 26 on postcard, p. 69

Turn Page

HYNES STEEL for WAREHOUSE STEEL STRIP - SHEET - PLATE



HOT ROLLED, PICKLED & OILED & COLD ROLLED STRIP STEEL

SIZE RANGE

Slit Edge-Coils

utits rd-

up onred oth ght. in-IDS for

69.

to ell kis ed

nt

ial p-

us

as

69.

ts

11es

ill

ve

it.

69

d

9

11 ga. (.125) to 28 ga. (.015) 1/4" to 24" wide

Slit Edge-Cut Lengths

7 ga. (.187) to 26 ga. (.018) 3/4" to 24" wide

Round Edge-Coils or Cut Lengths

11 ga. (.125) to 16 ga. (.062) %" to 3" wide

Deburred Edge-Coils or Cut Lengths 11 ga. (.125) to 24 ga. (.025) 36" to 3" wide

Shearing Sheets and Plates up to 3/8" in thickness - 12' lengths

Our complete facilities are devoted to the warehousing and processing of steel in sheet, strip and plates.


Hynes has the most modern equipment for shearing, slitting, edge rolling, roller leveling and cutting to length.

Normal inventory includes Cold Rolled Strip and Hot Rolled Strip in Coils and Cut Lengths, Hot Rolled and Cold Rolled Sheets and Hot Rolled Plates.

Non-ferrous metals can be processed to your size and specification.

Twenty-six years of progressive growth and experience is at your service.

Check now on our warehouse stock. Phone, wire or write.



Continued



Abrasive blades

To simplify cutting tough building and industrial materials such as stone, metal, plastic, and synthetic hardboards, a new set of equipment consists of a high-speed, kick-proof electric saw and three types of abrasive blades. The blades are reinforced and semi-flexible to reduce danger of breakage. The abrasive edge is said to produce a quicker, cleaner cut, and the side of the blade can be used as a grinding wheel to deburr, bevel or polish. Blades are color coded, available in 6, 7 and 8-in, diam, Porter-Cable Machine Co.

For more data circle No. 27 on postcard, p. 69.

Dust-free coal

Spraying coal prior to shipment with a special chemical solution known as Compound M allays dust. The preparation is nontoxic and harmless. The treatment in no way affects the burning qualities of the coal and is said to eliminate more effectively the annoyance of coal dust in shipment, handling, and storage. Johnson-March Corp. For more data circle No. 28 on postcard, p. 69.

Carbide gage block

Gage blocks made of chrome carbide (Croblox) have superior corrosion resistance, plus a remarkable similarity to steel blocks in the coefficient of expansion. Croblox expanding in nearly the same degree as steel makes it easier to use. Room temperatures can be ignored. The blocks can be exposed to a wide range of atmospheric changes without a trace of rust. Surface finish of 0.1 microinch is attainable. Two. 3 and 4-in. blocks are provided with bakelite finger grips to shield blocks from body heat. Webber Gage Co. For more data circle No. 29 on postcard, p. 69.

Turn to Page 83



OR close-knit strength and added life, here's a combination you just can't beat-Shenango centrifugally cast parts of Meehanite Metal. It is double assurance of finer, more uniform, pressure-dense metal, plus freedom from blow holes, sand inclusions and other defects!

So check with Shenango on your

need for symmetrical or annular parts-semi-finished if you wish, or machined to your precise specifications in the modern Shenango shops. Get all the facts. Like others you'll probably find you can save time, money and trouble.

SHENANGO-PENN MOLD COMPANY

Centrifugal Castings Division Dover, Ohio Executive Offices: Pittsburgh, Pa.



Sharon STAINLESS STEEL

SHARONSTEEL

SHARON STEEL CORPORATION

SHARON, PENNSYLVANIA

SHARON '430' STAINLESS IS IN GOOD SUPPLY AND IS AVAILABLE WITH FEW RESTRICTIONS

Sharon has prepared a fully illustrated booklet primarily for those who had been using one of the metals now in short supply. It is intended to introduce or reacquaint the reader with the possibilities of Type 430 Stainless Steel as a highly satisfactory primary or alternate material. The booklet contains basic fabrication information compiled to aid manufacturers in their consideration of this metal.

This booklet may contain the answers to your problems. Write for it today or contact the Sharon representative nearest you and ask him to see that you get your copy. Sharon district sales offices listed on back of next page for ready identification.


In today's economy Type 430 Stainless Steel is assuming an ever-increasing importance to producers of metal products. Government control over other metals has multiplied the difficulties of those fabricators who produce primarily for civilian consumption.


Sharon '430' Stainless is in good supply and available with few restrictions as to end use. It contains about 17 percent chromium with no nickel and has been the most popular ferritic grade of stainless steel. It comes the nearest to meeting the all-around requirements for general use. It was used before the chrome-nickel stainless steels and has a remarkable history of successful application. Absorption towers, used in the manufacture

of nitric acid, made of this type in 1926 are still in service. In the automobile industry it has been especially popular. Large tonnages go into trim and window moldings where the material must meet demanding requirements, both in complex fabrication and in abusive service conditions.

Sharon '430' possesses good mechanical and physical properties and a ductility about three-fourths that of deep drawing quality carbon steel. Extra deep drawing requires more power, more clearance and more carefully selected lubricants than for ordinary steel. Intermediate annealing and pickling may be necessary.

Sharon straight chrome stainless may be





welded for certain applications. Sharon also produces a titanium modified grade of 430 (430 Ti) which has superior bending qualities, is a better welding steel, and has superior corrosion resistance to that of regular 430.

A thin adherent scale is formed at temperatures as high as 1550°F. Formation of this protective scale, which does not crack away

and reform, permits the use of Sharon '430' in intermittent heating operations.

Sharon '430' is suitable for a great many applications in products generally manufactured of other steels and metals. If the shortage of critical materials has threatened your production, consult with the Sharon office nearest you...'430' may be your answer.

TYPICAL APPLICATIONS for Sharon 430 Stainless Steel.

AUTOMOTIVE

Grilles

Horn rings Hub caps

Mufflers

Panels

Trim

Wheel rings

Wheel covers

Windshield wipers

CONSTRUCTION

Decorative trim Down spouts Electrical hardware

Flashings

Gutters

Kick plates

Lighting

Mouldings

Roofing

Screens

Sheathing

Spandrels

Store fronts

Tile and trim

Window frames, channels and guides

RAILROAD

Diesel grilles Kick and push plates Refrigerator car parts Trim and decorative parts in passenger cars

HOUSEHOLD APPLIANCES

Clothes driers Floor waxers and polishers Heating and cooking appliances

Home and farm freezers Ironers and irons

Lamps

Ranges and stoves

Refrigerators Refrigerator dishes

Sewing machines

Shavers, electric

Toasters Vacuum cleaners

Washing machines

KITCHEN

Egg beaters

Food serving trays

Juicers

Knives

Mixers and mixing bowls

and spoons

Potato mashers

Pots and pans

Salt and condiment

containers

Spatulas

REFRIGERATION AND AIR-CONDITIONING

Bottled beverage coolers Carbonated water systems Drinking fountains

Fountainettes

Frozen food cabinets Ice cube makers

Malt beverage dispensing

Refrigeration evaporators Refrigerator shelves and

trim Room air conditioners

Sandwich units

Thermostats

GENERAL

Ash trays

Automatic vending machines

Bar equipment

Buttons and button parts

Cheese slicers, commercial

Cocktail shakers and accessories

Cup holders

Flatware

Furniture

Garden accessories

Irons

Jewelry

Ladles

Paint brush ferrules

and rivets

Radio and TV antennae

Railings

Refuse cans

Rulers

Soda fountains and

equipment

Utility cans

Water pitchers and

drinking cups

Weather stripping



pov

and

in.

thr

five

all

var

are

mei

ran

For

Be

AI

ten

live

SVS

wel belt fro bul

dis

a ce

rec

mai

Reg

For

G

Gla blu or

to


the

lon

Con

For

N



In these unsettled times you need all the information possible regarding materials and their use. Be sure to get your copy of this latest Sharon bulletin giving you up-to-the-minute information about Sharon '430' Stainless Steel. Contact one of the Sharon offices listed below or write direct and your copy will be in the return mail.

SHARON STEEL CORPORATION GENERAL OFFICES - SHARON, PENNSYLVANIA

CHICAGO 4, ILLINOIS Phone: Harrison 7-2526

CINCINNATI 2, OHIO 2407-08 Carew Tower Bldg. Phone: Main 1718

CLEVELAND 14, OHIO 1809 Union Commerce Building Phone: Main 1-3135

DAYTON 2, OHIO 1801 Hulman Building Phone: Fulton 5012

DETROIT 8, MICHIGAN Phone: Tiffany 6-1500

INDIANAPOLIS 4, IND. 425 Chamber of Commerce Building Phone: Lincoln 7318

LOS ANGELES 13, CALIF.

CANADIAN . REPRESENTATIVES

MILWAUKEE 2, WIS.
716 First Wisconsin
National Bank Building Phone: Broadway 2-7450

NEW YORK 18, N. Y. 500 Fifth Avenue Phone: Pennsylvania 6-8744 PHILADELPHIA 3, PA.

1138 Broad St. Sta. Bldg. Phone: Rittenhouse 6-098 MONTREAL 3, QUEBEC 80 Prince Street Phone: University 6-5761

ROCHESTER 4, NEW YORK 503 Genesse Valley Trust Building Phone: Baker 2540

SAN FRANCISCO 5, CALIF. 902 Monadnock Building Phone: Garfield 4335

WASHINGTON 4, D. C. Munsey Building Phone: National 4874

TORONTO 17, ONTARIO

Continued from Page 78



Angle-type drills

Three new angle-type drills are powered to drill holes in aluminum or brass from 9/16 to 3/4 in. diam, and in mild steel from 1/2 to 11/16 in. diam. The series comprises three different speed motors and five different angle attachments—all interchangeable—so that fifteen variations of speed and chuck size are available to meet any requirement accurately within the stated range. Keller Tool Co.

For more data circle No. 30 on postcard, p. 69.

Belt weighing system


A new conveyer belt weighing system is capable of electronically adding, subtracting and recording the tons per hour of material delivered to one or more points. The system developed jointly by Trans-Weight Co. and Minneapolis-Honeywell Regulator Co. is applicable for belt-conveyed materials ranging from low-grade ore to very fine bulk materials. Measurements can be transmitted over considerable distance, to a foreman's office or to a central control panel board. Chart records are also automatically maintained. Minneapolis-Honeywell Regulator Co.

For more data circle No. 31 on postcard, p. 69.

Glare reduction

Glare-Out, a clear, transparent blue-green coating, can be sprayed or rolled on windows or skylights to cut down heat and glare from the sun. It is permanent and will not peel, chip or wash off. One gallon covers 400 sq ft. Fade-Proof Corp. of America.

For more data circle No. 32 on postcard, p. 69. Turn Page



-Your Guarantee
of Longer Life

PITTSBURGH



Trademark Registered U. S. Patent Office

ARMORED GEARS are made only by PITTSBURGH GEAR from an exclusive formula perfected by PITTSBURGH engineers. It covers metal, machining, and a method of heat-treating that hardens the wearing surfaces but leaves the core tough, ductile, and shock-resistant.

All PITTSBURGH gears are made to extremely close tolerances to fit perfectly right from the start. They are guaranteed to give you <u>five</u> times the life of untreated gears, one to one and one-half the life of oil-treated gears, and equal or longer life than any other gear in identical service.

You can readily identify **Armored Gears** by their distinctive corrosion preventive coating —"**Pittsburgh Purple**."

You'll save money if you use PITTSBURGH Armored Gears. Send your specifications to us today. We'll quote promptly on one or any quantity of gears you need. MITRE.
HELICAL
HERRINGBONE
WORM GEARS
REDUCERS
CRANE WHEELS





ITTSBURGH GEAR

COMPANY

27th & Smallman Streets Pittsburgh 22, Pa. Phone: ATlantic 1-9950

subsidiary of BRAD FOOTE GEAR WORKS, INC. . CICERO 50, ILLINOIS

Continued



Torsion machine tests tool joints

Tool joints on oil well drill pipe are tested on a new torsion machine which measures torque in either direction of twist. Open chucks permit any length and size drill pipe to be run through the machine when doors on the drive unit are open. Torque up to 600,000 in.-lb can be measured. The machine is used solely for screwing up and unscrewing tool joints. Baldwin-Lima-Hamilton Corp.

For more data circle No. 33 on postcard, p. 69.

Descaling of steel

An alkaline electrolytic process for derusting metals is said to accomplish effective and complete scale removal by the use of periodic reverse current. The cathodic treatment removes rust without any attack upon the base metal. Also it reportedly produces a better surface for hard chromium plating with less danger of hydrogen embrittlement than when acid descaling is done. Enthone Compound 134 is used in a concentration ranging from 1 to 3 lb per gal. Current densities can range from 5 to several hundred amperes per square foot. Enthone, Inc.

For more data circle No. 31 on postcard, p. 69.

Precision measurement


Variables in temperature of gage blocks or work or both can be quickly checked with the new Temp-Check. Reading is obtained by placing the probe on the object to be measured and within minutes the actual temperature of the piece will be shown on the instrument dial. Standard model is calibrated from 60° to 100°F. Temp-Check is the size of a snapshot camera. Webber-Gage Co.

For more data circle No. 35 on postcard, p. 69.

Die adapter

The same die can be used for many different resistance welding operations by means of the Nu-Twist die adapter. A quick change of electrode inserts is all that is necessary to adapt the die to various operations such as spot welding, projection welding, electrical upsetting and electro-brazing. The unit reduces to seconds the time necessary to change a welding machine die setup from one operation to another. P. R. Mallory & Co., Inc. For more data circle No. 36 on postcard, p. 69.

Turn Page




PITTSBURGH, PA. 530 Wm. Penn Place Atlantic 1-4674

EDWARD GRAY, President

GENERAL OFFICES: 12233 Avenue O, Chicago 33, III. BAyport 1-8400

Treadwell



Three-High Mill for rolling precision rounds and squares up to and including 5" round or square. The mill is equipped with motor operated screw-downs for both top and bottom rolls.

Shop view of the roll stand with spindles

Manipulators, Mill, etc.
Mills, Blooming & Billet
Mills, Merchant & Bar
Mills, Rod
Mills, Strip (Cold)
Mills, Strip (Hot) & Skelp
Mills, Vertical Edging
Tables, Mill
Tables, Tilting & Lift
Tables, Transfer
Transfers

Coilers & Reels Conveyors, Coil Drives Ejectors, Furnace Gauges, Shear, Saw, etc.

Beds, Cooling Beds, Inspection Bumpers, Furnace

Pushers, Furrace Repeaters

Handling Equipment (Kick-offs, Pliers, Cradles, etc.)

Steel and Iron Castings Ni-Hard and Ductile Iron Castings



readwell Engineering Company

EASTON, PA.

SALES AND ENGINEERING OFFICES:

208 S. LA SALLE STREET CHICAGO 4, ILL. CEntral 6-9784 140 CEDAR STREET NEW YORK 6, N. Y. WOrth 4-3344 1217 FARMERS BANK BLDG. P!TTSBURGH 22, PA. ATlantic 1-2883

0 g

9.

r

le e-t-t-tr-graden

n

9.

re e py to es

it

ed is

a.

59.

13.

aie c-

s-1s g, p-

ne ne

n

c.

69.

E


What's New in New Jersey



ONE of the most significant developments in New Jersey's industrial history has been the rapid progress of crude oil refining.

Today, despite its small size as a state, New Jersey ranks sixth in the nation in terms of capacity of oil refining. In fact, the capacity of New Jersey refineries is about equal to that of the United Kingdom, the largest refining center in Free Europe. Six nationally known oil companies operate refineries here, and one of them operates the largest along the entire Eastern Seaboard.

There are specific reasons why the oil companies locate important refining centers at the Crossroads of the East, where industry succeeds. If you want to know what these reasons are . . . if you want to know what's new in New Jersey . . write today for our brochure about New Jersey, the Crossroads of the East.



Write Box F, Public Service Electric and Gas Company, 70 Park Place, Newark, N. J., for your copy of "An Industrialist's View of the Crossroads of the East".

PUBLIC SERVICE
Taxpaying Servant of a Great State

Is Your Plant "Well Informed"?

- ★ Keep your entire plant abreast of the latest developments in the Metalworking Industry by distributing extra copies of THE IRON AGE to all department heads.
- An extra subscription or two will make the vast storehouse of information provided each week in THE IRON AGE available to many additional employees in your organization.


Additional subscriptions \$8 per year
Write: CIRCULATION MANAGER

the Iron Age

100 East 42nd St., New York 17, N. Y.

New Equipment

Continued



Toggle clamps

Advantages of two lines of toggle clamps are fast action, long life at all pivot points because of hardened steel bushings, and precision manufacture. Merriman replaceable, hardened steel bushings, installed at all pivot points have a serrated surface that cuts its own bearing points. Minute shavings dislodged by this process wedge the bushings in tightly so there is no danger of their coming loose. The Thayer clamp provides holding pressure up to 2500 lb. The La-Ko lightweight clamp affords holding pressure to 650 lb. E & E Engineering Co.

For more data circle No. 37 on postcard, p. 69,

Spiral reamer

New spiral reamer cuts inside burr from pipe and conduit clean and fast with minimum effort or pressure; cuts holes in sheet metal also, smoothly and without chatter. Reamer capacity is ½ to 2 in. Ridge Tool Co.


For more data circle No. 38 on postcard, p. 69.

Rotary table

Designed for mounting small precision work, a new rotary table can be used on a drill press, milling machine, shaper or surface grinder. Accurately spacing drilled holes, indexing clutch teeth, milling circular grooves or T slots, machining square and hexagon shapes are some of the operations that can be performed on the table. Work table measures 41/2 in. diam and rotates by worm gearing having a graduated collar and ball crank. Table edge is graduated 360°. A clamping lever locks the table in position. South Bend Lathe.

For more data circle No. 39 on postcard, p. 69.

Turn Page



SURROUNDED BY PLUS VALUES THE LEES-BRADNER "40" THREAD MILLER

It takes precision plus to thread shell cases accurately for the reception of delicate fuse mechanisms. Speed, easy loading and semi-automatic operation are other important considerations.

That's why the Lees-Bradner Model "40" Thread Miller was chosen to perform this highly important operation.

You, too, can get unusual accuracy at high speed and with a minimum of scrap on precision threading operations. Just contact your Lees-Bradner representative and ask him for all the details on this remarkable machine.

The LEES-BRADELL
CLEVELAND 11, OHIO, U.S.A. COMPANY



New Equipment-

Continued



Bridge-crane hoists

New deck-type Cable King electric hoists are designed for top mounting in double-girder bridge cranes. Units, available from 1 to 15 tons, feature compactness of design; triple-reduction, spur-geared drive; totally-enclosed, fan-cooled motor; rugged heavy steel suspension frame; and pushbutton-operated heavy-duty contractor. For safety, hoists are equipped with two brakes. Control station can be in the crane or remotely located. Yale & Towne Mfg. Co.

For more data circle No. 10 on postcard, p. 69.

Indicator points

Durable carbide indicator points are available in convenient, time-saving sets. The wear resistant carbide tips take sudden gaging shocks and friction of rapidly revolving cylindrical pieces with ease and assure more precise gaging for longer periods. Each set has five standard shaped points: flat face, ball point, needle point, conical point, convex. Sets of six of any one shape are also available. Eastern Tool Co.

For more data circle No. 41 on postcard, p. 69.

Push-on fasteners

A push-on fastener is available in four types, each featuring a non-slip grip that bites deeper with use into the surface of the stud. Biting action is said to hold equally well on soft plastic, metal, fiber, or polished and ground studs, straight or tapered. The fastener will handle variations of 1/64 in. in stud dimension. *Prestole Corp.*

For more data circle No. 42 on postcard, p. 69.



An

ria

ele

no

Us

is ru

af

a



at your Service for...

ELECTRICAL EQUIPMENT

HOUSEHOLD APPLIANCES TRANSPORTATION

INDUSTRIAL EQUIPMENT

> FARM IMPLEMENTS

Lansing Stamping Co.
LANSING 2 "ESTABLISHED 1914" MICHIGAN

nessen, Pa., Atlanta, Chicago, Denver, Detreit, Los Angeles, New York, Philadelphia, Portland, San Francisco, Bridgeport, Conn. Continued

Liquid rust inhibitor

Anarust, a liquid rust inhibitor for wet blasting machines, is a material of organic composition, containing no chromates. It is soluble in hard or soft water, produces a clear colorless solution, is odorless, nonirritating to the skin, and not subject to bacterial decomposition. Used at ½ oz per gal of water, it is an effective agent in retarding rust on cast iron or steel parts which are being cleaned and washed after wet blasting. American Wheelabrator & Equipment Corp. For more data circle No. 43 on postcard. p. 69.

New press control

A versatile type of control, available on the Denison Multipress, is a servo-type valving in the oil hydraulic press circuit that through its linkage with the hand control gives instant response ram action. Any pattern of ram action can be initiated by the operator himself. Rapid down pressure gives rapid ram traverse; quick up and down hand movement gives vibratory action. Minimum ram stroke is 1/16 in.; maximum, 6 to 15 in., depending on the model Multipress. Denison Engineering Co.

For more data circle No. 44 on postcard, p. 69.




Industrial trailer

With a capacity of 120,000 lb and equipped with eight, solid rubbertired wheels, this heavy duty industrial trailer has a body framework of I beams and channels, with a deck surface of smooth steel. Two styles are available; one with fifth wheel on the front axle only; the other with fifth wheel on both front and back axles for extra maneuverability. Wide wheel base and low center of gravity prevent tipping. Basic size is 7½ ft wide x 12 ft long. Phillips Mine & Mill Supply Co.

For more data circle No. 45 on postcard, p. 69. Turn Page STANDARD AND SPECIAL WASHERS

AND SMALL STAMPINGS



More than 30 years of experience in designing and producing Special Washers and Small Stampings . . . more than 12,000 sets of tools at your disposal. Any metal . . . any quantity. Your inquiries will receive prompt and careful attention.


THE MASTER PRODUCTS CO.

6400 Park Avenue

Cleveland 5, Ohio

LAY IN A SUPPLY OF . . .

MCDANEL COMBUSTION TUBES




FEWER FAILURES: MORE DETERMINATIONS

McDanel Refractory Porcelain Co.
Beaver Falls . . . Penna.

McDANEL PORCELAIN SPECIALTIES

Your Porcelain requirements—large or small—are considered important by McDANEL.




Fixed center boring mill has automatic cycle

The No. 3 boring unit is basically a fixed center horizontal boring mill with automatic cycle, having the following specifications: horsepower, 5 to 10; spindle speed, 33 to 500 rpm by pick off gears; diameter of spindle, 3 in.; Morse taper of spindle No. 5; length of bar stroke, 10 in. The boring unit body is heavily proportioned and

box ribbed semi-steel casting. Feed mechanism is operated by a hydraulic pump and fluid motor. A system of valves and piping will allow cycle adjustments within the range specified. Feed changes are controlled by adjustable dogs contacting limit switches. W. K. Milholland Machinery Co.

For more data circle No. 46 on postcard, p. 69.




Bench unit checks external gears

Size, eccentricity and roll smoothness of spur and helical external gears can be checked on a new Model 602 bench type rolling fixture. It features a heavy cast iron base, scraped ways and hardened and ground ball ways. It can be used with an automatic recorder to place all readings on permanent charts. The gear to be checked is


loaded on a vertical arbor that is moved into mesh with the master gear by an eccentric lever control. Turning the gear manually causes a 0.0005-in. indicator to show size, eccentricity and smoothness variations. Center distance of fixture is adjustable from 2 to 10 in. Michigan Tool Co.

For more data circle No. 47 on postcard, p. 69.



Furnace Cars

Electric furnace car mounted on electric transfer car for completely automatic continuous heat treating system.



EASTON CAR & CONSTRUCTION COMPANY - EASTON, PA. - NEW YORK - PHILADELPHIA - PITTSBURGH

Loading dock shelters

Rugged canvas loading dock shelters extend outward on a collapsible steel framework to shelter truck or freight car loading doors of any size. They collapse flush against the building when not in use. Precision-constructed canvas wall curtains for use indoors as effective windbreakers, to stop cold drafts and heat loss also feature steel framework and the same rugged construction. They can be rolled up, shirred up or drawn aside quickly and easily. Atlas Products Co.

For more data circle No. 48 on postcard, p. 69.

Air blow gun

Positive two-stage throttling action of Tu-Flo air blow gun gets away from the danger and discomfort of having a cloud of dust, dirt, grit blown in the operator's face the second the air valve is released. For 9/10ths of the control button travel only a small volume of air is permitted. Operator pulls the button all the way if he wants the full blast. He has a choice. Supreme Machine Products Co.

For more data circle No. 49 on postcard, p. 69.

A BIG INGOT with a

BIGGER FUTURE!



The bigger the job and the more exacting the specifications, the more important it is to let Midvale do it.

This 499,000-lb, steel ingot—one of a number of this size—will be forged by Midvale craftsmen, heat-treated and machined into long-lasting precision parts for industry.

Midvale precision and performance can supply all your needs for heavy equipment in industry. Pressure vessels for the petroleum and chemical industries . . . Rolls for the paper industry . . . Rings for turbines and gears . . . Forgings and heat and corrosion resistant castings for all industries. If the job is big and the specifications exact, you need the services of Midvale engineers and craftsmen.

THE MIDVALE COMPANY

NICETOWN • PHILADELPHIA 40, PENNA.

OFFICES: NEW YORK • CHICAGO • PITTSBURGH
WASHINGTON • CLEVELAND • SAN FRANCISCO

Custom Steel Makers to 9ndustry

PRODUCERS OF FORGINGS, ROLLS, RINGS, CORROSION AND HEAT RESISTING CASTINGS

eed auysow

onict-

69.

is ter rol. ses ze, iaare hi-

69.

s nel-

ble

ack any

nst

re-

ur-

ive

fts

eel

ged

led

ide

cts

. 69.

ets omirt, ace sed. ton r is

full

. 69.

GE

newera in welding!



Heavy-Duty CHAMPION

500-, 400- and 500-Amp. Production Welding Models. The extra years of service built into these machines make these models real welding champions.

The CHALLENGER

200-, 500- and 400-Amp. Production Welding Models featuring wide amperage range for adaptability to more jobs in any production welding shop.

The AUTO-MAN

650-Amp. Model. For Automatic or Manual Operation, singly or in multiple set-ups. Offers unusual flexibility for your welding requirements.

The UTILITY

An all-purpose Utility welder with 25 to 180 Amp, range for repair-shop, maintenance and farm use, and featuring production welder construction.

Made by Welders . . . for Welders

Production proved by one of the world's largest users of welding products

Now A. O. Smith advanced design . . . new plus features . . . give you the latest in welding machine efficiency



D. C. WELDING MACHINES

The D. C. RECTIFIER

200-, 300-, and 400-Amp. heavyduty Production Welding Models for all d.c. jobs. The one rectifier-type welder designed to eliminate stack failure!

The FIELD KING Gasoline-Engine

200- and 300-Amp. Models. The most advanced of all enginedriven welding machines! Built for rugged jobs in the field. Welds with new speed and ease

Redesigned to match today's welding requirements, A. O. Smith advanced design welders offer you the advantages of improved construction, top welding performance, and more operat ing benefits. A. O. Smith welders put you in the best position to cope with today's requirements and costs. Whether your welding is manual or automatic, A. C. or D. C., A. O. Smith welders assure you of having the finest power source available anywhere.

Ask your A. O. Smith representative, your A. O. Smith distributor or write us, for full details about these advanced design welding machines. They merit your study: A. O. Smith Corporation, P. O. Box 584, Milwaukee 1, Wisconsin.

Tooling or Re-tooling?


L&N FURNACES HELP TOOLS PRODUCE MORE

• Shown here are the tools and dies of some of the literally hundreds of firms that have found how to cut tool costs with Vapocarb-Hump Hardening and Homo Tempering Furnaces.

Butcher & Hart Co., Toledo, for instance, gets the uniform heating it needs to avoid distortion of the recessed head of cold-heading dies like the one shown.

The special gears of Sonoco Products Co., Hartsville, S.C., are heated with the uniformity needed to preserve their firm, true-running fit.

Towle silverware dies leave the Vapocarb-Hump furnace with never a particle of scale in their intricately carved detail—need none of the stoning and other time-consuming hand finishing that would be required if scale had developed.




Heat-Treating Costs Least, Adds Most to Tool Life

A cost analysis of the simple punch and die set shown above gives a picture of the relative costs of tool-making and of heat-treating, in producing a complete tool.

The toolmakers who shaped and assembled the punch and die used machine tools worth \$31,000, beginning with the cutting off of the steel and ending with the final filing. And, the tool-making time was 21 man-hours.

The heat-treater, on the other hand, used Vapocarb-Hump Hardening and Homo Tool Tempering equipment costing, complete with controls, only \$5,500; and he did both jobs in 3 hours.



In other words, heat-treating represents only one-sixth of the total tool cost, yet it is largely responsible for the future performance of the tools. This is a typical example of the familiar fact that it pays to give the heat-treater precision equipment in both furnaces and controls. Whether you're tooling or re-tooling, the heat-treat's comparatively small cost can make a big difference in tool life.

A letter or call to our nearest office, or to 4956 Stenton Ave., Phila. 44, Penna., will bring complete catalog information or put you in touch with an experienced heat-treat engineer, as you wish.

CAREER OPPORTUNITIES AT L&N

Expansion program of this long-established firm has many features to attract outstanding recent graduates in engineering and science. Opportunities are in sales field engineering, product and application engineering, research, advertising, market development, Widely-respected policies assure recognition of progress and achievement. Address Personnel Manager for preliminary interview at nearest of 17 L&N offices.



the Iron Age

SALUTES

James P. Growdon

This pioneering engineer led Alcca's Taiya Valley planning . . . Building dams is his hobby.



WITH the exception of time out for two World Wars, Jim Growdon has spent 44 years in hydro-power engineering. The last 27 were with Aluminum Co. of America and he's had a hand in most of the company's large hydro-electric developments. Capping the list is his leadership in planning Alcoa's proposed Taiya Valley, Alaska, aluminum smelter.

On the side Jim has served as consultant for the Army, Navy, several foreign governments, public utilities, and firms of engineers and contractors.

Born in Pioneer, Iowa, in 1884, he has taken the name of his home town for a creed and led the way in many engineering developments. He is largely credited with adapting the vibrator principle to pouring concrete—now an almost universally used method.

He pioneered development of earth-faced rock-filled dams. The Navy's underground oil storage installation at Pearl Harbor is an achievement of his for which he won a Certificate of Merit. The list is long.

During World War I he rose from lieutenant to major in the Army Engineering Corps and was decorated with the Distinguished Service Cross and France's Croix de Guerre. As a colonel in World War II his abilities were invaluable on such jobs as reconstruction of bombed out power facilities in Italy.

Jim is extremely well known and liked in the engineering world. He is a very active member of the American Society of Military Engineers. Asked about the colonel's hobbies, one friend remarked "building dams." Now residing in Pittsburgh, the colonel does manage to play golf and is highly respected for his talents at bridge.

AGE

BURNER BLOCKS

Kaocast lasted
3 to 6 times as long as
previous refractory.
Still going strong.



DOOR LININGS


Kaocast lasted 3 to 6 times as long as previous refractory—cut installation cost in half.



TUNNEL KILN CAR TOPS

Ordinary fireclay crumbled after few trips. Kaocast lasted 30 trips without deterioration.

.......................



SPECIAL SHAPES

Kaocast special shapes cast over week-end to meet production demands.

BOILER FURNACE REPAIRS

One power plant keeps a ton of Kaocast on hand for miscellaneous repairs because it is so versatile.

There's no end to the uses of economical



The list of plants who are discovering new, cost-saving uses of versatile B&W Kaocast keeps growing all the time. The reasons? This unique 3000 degree refractory castable can be molded in a hurry... cast directly in place... applied with a cement gun. It eliminates the need for a large inventory of special shapes. It has high resistance to spalling, low volume change, practically no reheat shrinkage. Want to know more? Ask your B&W Refractories Engineer—or write for Bulletin R-22.



B&W REFRACTORIES PRODUCTS — B&W Allmul Firebrick • B&W 80 Firebrick • B&W Junior Firebrick • B&W Insulating Firebrick

B&W Refractory Castables, Plastics and Mortars • OTHER B&W PRODUCTS—Stationary & Marine Boilers and Component Equipment . . .

Chemical Recovery Units . . . Seamless & Welded Tubes . . . Pulverizers . . . Fuel Burning Equipment . . . Pressure Vessels . . . Alloy Castings

the Iron Age

INTRODUCES

Stanley M. Vermeil, appointed secretary of the executive committee, KEYSTONE STEEL & WIRE CO., Peoria.

Edward R. Devlin, elected vicepresident, THE ATLAS IRON & STEEL CO., INC., Philadelphia.

B. W. Kinderman, elected comptroller, DEWALT, INC., Lancaster, Pa.

Frank E. Myers, appointed vicepresident of operations, SALEM-BRO-SIUS, INC., Pittsburgh; John R. Wickwire, named assistant to the vicepresident of operations; Thomas E. Lloyd, named manager of sales; and Carl J. Westling, appointed chief engineer.

E. M. Slonaker, elected executive vice-president, WILLARD STORAGE BATTERY CO., of California. He succeeds Chester H. Starr, who is retiring.

Louis J. Sarosday, appointed vicepresident, Engineering, J. B. BEAIRD CO., Shreveport, La.

es of

sons?

l in a

n. It

It has

ly no

efrac-

irebrick

ent . . .

astings

AGE

Oscar W. Heimberger and Robert M. Wallace, elected vice-presidents, THE GRISCOM-RUSSELL CO.

Robert I. Roth, appointed vice-president in charge of western sales, WHITE-ROTH MACHINE CORP., Lorain, Ohio.

W. E. Santoro, appointed head of the Research Div., THE MONROE SANDER CORP., Long Island City, N. Y.

George P. Krumlauf, appointed metallurgical engineer, Pig Iron and Coal Chemicals Sales Div., REPUBLIC STEEL CORP., Cleveland. He succeeds the late T. G. Johnston.

Ernest O. Ohsol, named director of chemical engineering, PITTSBURGH COKE & CHEMICAL CO., Pittsburgh. H. W. Tuttle, Jr., becomes executive vice-president, H. W. TUTTLE & CO.; Herbert A. Speerstra, named vice-president and director of purchases; Warren A. Stuckey, becomes vice-president and works manager; and Max Rosenstein, named vice-president in charge of electronic research.

R. F. Ledford, appointed director of sales and research, INDUSTRIAL FILTER & PUMP MFG. CO., Chicago.

Harry L. Reynolds, promoted to treasurer, THE THEW SHOVEL CO., Lorain, Ohio, and Waid V. Clark, named controller and secretary.

B. Frank Quintilian, elected vicepresident in charge of engineering, GEROTOR MAY CORP., Baltimore.

Thomas J. O'Donnell, named head of the Physics Section, Ellectromechanical Div., ATLANTIC RESEARCH CORP., Alexandria, Va.; Edwin F. Abrams, becomes physical chemist; and George C Pierce, becomes sales and planning engineer.

Paul R. Rauch, appointed assistant chief inspector ,THE YOUNGSTOWN SHEET & TUBE CO., Youngstown.

Charles Carr, Sr., named manager, Steel Works Dept., WEIRTON STEEL CO., West Va.; William McGarrity, becomes assistant manager; and Robert Allard, promoted to assistant to the manager of the Steel Works.

John F. Bishop, appointed assistant general manager, Instrument Div., BECKMAN INSTRUMENTS, INC., South Pasadena, Calif.

Herbert C. Salzer, appointed assistant to the director of purchases, MOTOR WHEEL CORP., Lansing, Mich.



DANIEL T. WELLMAN, appointed president, The Wellman Bronze & Aluminum Co., Cleveland.



ROBERT S. SWEENEY, named vicepresident and general manager, The Watson-Stillman Co., The Hydraulic Press Div., H. K. Porter Co., Inc.




WILLIAM P. CAROTHERS, appointed vice-president in charge of production, United Tube Corp., Cleveland.

November 27, 1952

97



To aid you in solving industrial finishing problems, The Erie Enameling Company offers free of charge this detailed 16-page booklet on industrial porcelain enamel. It describes the various characteristics of porcelain enamel . . . presents proven examples of their effectiveness in industrial applications . . . provides basic information on how to design for porcelain enamel . . . tells you how to submit your finishing problem to Erie for expert analysis.



Personnel

Continued

Paul J. Isvolt, appointed Cincinnati district sales manager, Acme Steel Products Div., ACME STEEL CO. He replaces Neil L. Anderson, who was transferred to Chicago offices as manager of the Steelstrap Dept.

Russell L. Sylvester, appointed manager of engineering and chief engineer, Equipment Div., NATIONAL RESEARCH CORP., Cambridge, Mass.

James R. Mohr, named manager of merchant products sales dept., Chicago office, American Steel & Wire Div., U. S. STEEL; Charles P. Greenlee, named assistant manager of sales Detroit.

E. C. Freeman, appointed factory manager, Trenton Michigan plant, CHRYSLER CORP.

John N. Allen, appointed district sales manager, THE AMERICAN BRASS CO., Cedar Rapids, Iowa, new district sales office.

John G. Holschuh, named manager newly created market research section, ELASTIC STOP NUT CORP. OF AMERICA, Union, N. J.

Allan F. Ives, named Pontiac Motor Div. Midwest regional manager, of GENERAL MOTORS CORP.

John E. Giere, appointed to Cleveland regional sales staff, UDYLITE

C. A. Walmsley, appointed district manager in charge of the St. Louis Car Plant, AMERICAN CAR & FOUNDRY CO., succeeding T. G. Shipley, who has retired.

E. W. Hazzard, appointed Corporation export manager, GAR WOOD INDUSTRIES, INC., Wayne, Mich.

Setrak K. Derderian, appointed assistant general manager, METAL-HUDRIDES, INC., Beverly, Mass.

Richard Schermer, named manager of pump sales, THE DURIRON CO., INC., Dayton.

A. V. DeYot, transferred to Plastic Metals Plant in Johnstown, Pa., as manager, by THE NATIONAL RADI-ATOR CO.

Ernest H. Wyche, joins KENNETH TATOR ASSOCIATES, Coraopolis, Pennsylvania.

Carl E. Swift, appointed distributor for JESSOP STEEL CO., Washington, Pa.



R. D. HILL, appointed executive vice-president and treasurer, Taylor-Wharton Iron & Steel Co.



H. ALBERS, named chief engineer in charge of the U. S. A. F. heavy press program, Loewy Construction Co., Inc., subsidiary of Hydropress, Inc.




CHARLES T. EVANS, JR., appointed manager of high temperature metals, Universal-Cyclops Steel Corp., Bridgeville, Pa.



H. H. LENTZNER, named manager, Special Machinery Div., Kearney & Trecker Corp., Milwaukee.

alloy steel drive gears for M-47 tank hob better with GULF ELECTRO CUTTING OIL!



Operation—cutting involute teeth on alloy steel spur gears, Gould and Eberhardt Gear Hobbers; results with Gulf Electro Cutting Oil—Hob life increased 20%, scuff marks eliminated on gear teeth, and hob grinding costs reduced.

Here's the important reason why Gulf Electro Cutting Oil produces outstanding results like these: Thanks to a special Gulf process of combining sulphur, it provides greater sulphur activity over the entire range of a cutting operation.

This means longer tool life and better finishes.

Call in a Gulf Sales Engineer today and arrange to use this quality cutting oil on your tough machining operations, or send the coupon below for additional information.

GULF	hing	Gulf Oil Corporation · Gulf Refining Company 719 Gulf Building, Pittsburgh 30, Pa. Please send me, without obligation, a copy of your pamphlet "Gulf Electro Cutting Oil."
	SERVES	Name
	INDUSTRY	Company
		Title
		Address

AGE



FIRST

with MECHANIZED

BATCH — TYPE

CONTROLLED

ATMOSPHERE

FURNACES

NOW GIVES


YOU A

SMALL FURNACE

WITH THESE


OUTSTANDING

FEATURES—



2 Fan (5000 cfm) removable from outside and heat capacitors provide positive directional flow of atmosphere.

3 4 Vertically mounted Radiant tubes with 600,000 BTU per hour input with built-in generator.



MODEL "J"

The Dow Model "J" is a small mechanized furnace for production carbonitriding, gas carburizing, clean hardening, carbon restoration and bright annealing. It is the ideal furnace for small heat treaters and manufacturers where flexibility is required. Size: 7'10" wide, 14'4" long—head room 15'. Production capacity: 250-350 lbs. per hour on light case work.



OPTIONAL FEATURES

Hot Oil Quench system—provides exceptional distortion control, Large gas fired immersion tubes supply heat at low intensity thus minimizing oil breakdown.

Slow Cool Chamber permits cooling of a full furnace load in atmosphere and reloading without loss of time,

DOW FURNACE COMPANY

12045 WOODBINE . DETROIT 28, MICH.

Personnel.

Continued

Robert D. Stottlemyer, appointed assistant division manager, Casper Wyoming, THE NATIONAL SUP-PLY CO.

George Chipley, appointed Wisconsin representative, CONOFLOW CORP., Philadelphia.

John B. Ottman, appointed television-radio sales promotion manager, ADMIRAL CORP.

Philip C. King, appointed purchasing agent, METALS DISINTE-GRATING CO., Elizabeth, N. J.

Vic Hassell, appointed midwestern sales representative, THE KAYNAR CO., Los Angeles.

Charles E. Sharp, becomes manager of customer service, AMERICAN WELDING & MFG. CO., Warren, Ohio

Alan P. Benson, appointed extrusion sales representative, Michigan-Ohio territory, WISCO ALUMINUM CORP. of Detroit.

ORITUARIES

Leopold E. Block, 83, one of the founders of Inland Steel Co., Chicago. in St. Luke Hospital, Chicago.

George H. Fobian, president, The Oilgear Co., Milwaukee, recently.

Ben H. Knipe, 63, president, The Markle Steel Co., Houston, after a brief illness.

Edward L. Greene, 68, president, National Better Business Bureau, suddenly in his home at Mamaroneck, N. Y.


Paul B. Morgan, chairman of the board, Morgan Construction Co., Worcester, at his home there recently.

Arthur K. Higgins, 44, assistant director of research, Allis-Chalmers Mfg. Co., Milwaukee,

Russell R. Roeller, 60, general sales manager, Pennsylvania Salt Mfg. Co., in the Phoenixville, Pa., hospital after a brief illness.

Frank J. Clark, 72, pioneer salesman, Hanson-Van Winkle-Munning Co., Matawan, N. J., recently in Plainfield, N. J.

Apologies to John M. Glasgow who recently retired as manager of land department, Tennessee Coal & Iron Div., U. S. Steel, and whose name mistakenly appeared in this column.



That's McCormick Steel of Houston, Texas! By installing an Airco No. 50 multi-torch cutting machine, they've boosted steel orders with an entirely new type of service . . .

Here's how it works: customers supply an outline drawing or paper cutout of the required part. An "electronic eye" traces the guide with hairline accuracy. Irregular shapes, inside and outside square corners, obtuse angles, slim slots and intricate contours — the

Airco No. 50 Travograph takes 'em all in stride. Circles up to 12 feet in diameter — thicknesses up to 6 inches! By keeping all 8 torches in operation, McCormick mass produces intricate shapes so accurately that further machining is, in most cases, unnecessary.

The Airco No. 50 Travograph cuts light plates, heavy slabs, billets or forgings . . . to minute tolerances . . . with virtually no limit on shape or size. Complete details are available by contacting your nearest Airco office.



Co.,

ently.

stant

mers

sales

. Co.,

after

alesining lain-

who

land Iron name

umn.

AGE

AIR REDUCTION

AIR REDUCTION SALES COMPANY - AIR REDUCTION MAGNOLIA COMPANY - AIR REDUCTION PACIFIC COMPANY REPRESENTED INTERNATIONALLY BY AIRCO COMPANY INTERNATIONAL

DIVISIONS OF AIR REDUCTION COMPANY, INCORPORATED

at the frontiers of progress you'll find



Our customers know that Inland









keeps steel quality consistently high.









These checks...made all through









production...demonstrate how.



INLAND STEEL COMPANY

38 South Dearborn Street, Chicago, 3, Illinois



Foundries report on BASIC ELECTRIC ARC PRACTICES

By T. N. Armstrong

Development and Research Div. International Nickel Co., Inc. New York

A survey of 25 foundries, representing about 75 pct of the total using basic electric arc furnaces for melting ferritic steels, shows the trends and significant differences in melting practice. Some foundries use the same furnaces for melting stainless and high alloy steels. Not included in the survey are foundries making stainless, heat-resistant and Hadfield's manganese steel castings exclusively. Without high grade scrap in many areas, the trend is away from acid electric furnace practice. As a move in this direction, some foundries have already converted to basic furnaces while others are considering such a step.

Current requirements for cast steel parts of military equipment have imposed problems not usually encountered with industrial castings. Many military castings must be resistant to shock loading of high magnitude at extremely low temperatures. In addition, these parts are required to function as structural members subject to high static and cyclic stresses. It appears

that sulfur and phosphorus limits must be more restrictive than for commercial steel castings if these severe requirements are to be met consistently.

The need for steel of low sulfur and phosphorus content and the absence of high grade scrap in some areas have revived an interest in basic electric steel for castings. This trend is

AGE

Operators rate capacity on the average weight of the charge rather than on the shell diameter . . . Widely used furnaces are 3 and 6-ton sizes . . . Most foundries operate on a full scrap charge . . .

shown in the chart in Fig. 1. Several foundries already have converted one or more furnaces from acid to basic and others are considering the move.

In basic electric arc practice, most operators rate capacity on the average weight of the charge rather than on the shell diameter or the melting rate per hr. Of fifty furnaces from 1600-lb to 25-ton capacity, no one size predominates but 3 and 6-ton sizes are most widely used. Fig. 2 shows a modern 6-ton electric Pittsburgh Lectromelt furnace. Newer furnaces have removable tops and are charged mechanically, as shown in Fig. 3, whereas older furnaces with fixed tops generally are charged by hand, aided by a chute.

Seven foundries prepare the furnace bottom by sintering; the remainder use rammed magnesite and burn in the entire bottom in one operation. The trend is away from silica to high alumina brick for roofs. Some operators use high alumina brick in the outer courses and silica brick in the center because in continuous operation silica brick roofs spall excessively.

No standard sidewall

There seems to be no standard practice for side wall construction. Silica brick is used most frequently above the slag line but some operators prefer magnesite brick. A few shops use rammed ganister linings with success.

Three general practices are used for melting steel castings in the basic arc furnace. Most common is the conventional two slag process in which steel is melted down under oxidizing conditions, the slag skimmed and the melt finished under a slightly reducing white slag. The reducing slag consists of a mixture of lime and fluor-spar with an addition of carbon or silicon or aluminum. The two slag process is still used in more than 60 pct of the foundries operating basic as it is the most effective practice for reducing sulfur and phosphorus. Both sulfur and phos-

phorus will usually be under 0.020 pct in the double slag process and, with a high grade of scrap, sulfur may finish as low as 0.010 pct.

Next is the single slag process in which the charge is melted under an oxidizing slag but the slag is converted to a reducing condition for finishing by the addition of crushed ferrosilicon and sometimes a small addition of carbon in the form of crushed coke or crushed graphite. Phosphorus drop is negligible with this practice but there is a reduction in sulfur. Final sulfur is usually under 0.025 pct.

The third practice is a single slag process in which the slag is always on the oxidizing side. Toward the end of the melt, oxygen content of the slag drops and the color after cooling is brownish. Claims are made for a slight reduction in both phosphorus and sulfur, the drop for each being not more than 0.005 pct. The principal advantages of this practice appear to be the relative low cost and improved fluidity of the melt.

Most foundries operate on a full scrap charge. About 1 pct ore is added with the charge and the bath on meltdown is about 0.10 pct above the final desired carbon. If necessary, ore may be added to bring the carbon down to the desired level. Some operators prefer to knock the carbon down to about 0.10 pct below the desired level and recarburize. About 25 pct of the foundries use oxygen either as regular practice or on occasional melts.

Deoxidation practice varies considerably. Most final additions of ferromanganese and ferrosilicon are made in the furnace. All but about 6 shops add aluminum to the ladle. About 50 pct of the foundries add a calcium-manganese-silicon alloy to the ladle. A few also add ferrotitanium, usually in conjunction with the calcium-manganese-silicon. Only 1 foundry uses zirconium. At least 3 foundries using calcium-managanese-silicon and titanium do not use aluminum and report no dif-

WHAT IS POPULAR AMONG FOUNDRIES USING BASIC ELECTRIC ARC FURNACES?

Furnace capacity	Most use 3 to 6-ton capacity
Furnace bottoms	72 pct use rammed magnesite
Furnace roofs	Trend is from silica to high alumina brick
Side wall construction	Silica brick is most common
Charging	
Melting	
Slag reduction	
Refining	Most add ferromanganese and ferrosilicon in furnace
	76 pct add aluminum to ladle
	50 net add Ca-Ma-Si allow to ladle

ficulty with pinhole porosity in castings poured in green sand molds. All use a double slag practice and may add some aluminum to the reducing slag.

Melts made in the basic furnace and finished under a reducing slag usually do not have as good fluidity as acid melts, but melts finished under an oxidizing or brown slag are said to be equally as fluid as acid steel. However, lack of adequate fluidity is no longer a major foundry problem with basic electric steel. About 20 pct of the foundries are shanking their basic melts.

Most of the furnaces start with a meltdown voltage of around 200 and finish the melt at around 100 v. The highest voltage is 250 v and the lowest 90 v.

Meltdown time varies considerably but the average is about 2 hr. The shortest time is 70 min and the longest is 3 hr.

Total furnace time under power also varies widely even with the same size furnaces and with the same practice but time is shortest with the single slag process. Several shops use a single slag tap regularly 2 hr after power is turned on. Average time with double slag is about $3\frac{1}{2}$ hr while longest time is $4\frac{1}{2}$ hr,

Average 515 kw-hr per ton

Power consumption per ton of metal poured differs among the foundries due to a number of factors. The lowest consumption, 475 kw-hr per ton, is in a shop using oxygen and a single slag, but finishing with the slag in the reducing condition. The highest consumption, 750 kw-hr per ton, is in a 10-ton furnace apparently overcharged or underpowered. The median is about 515 kw-hr per ton for single slag and about 550 kw-hr per ton for double slag.

The reasons advanced for using basic practice are to control sulfur and phosphorus and to recover oxidizable alloys. Many foundries, some of which use both acid and basic practice, have less cracking and the steel is cleaner than acid steel.

ALL TIME

TOTAL CASTING PRODUCTION

ELECTRIC FURNACE CASTINGS

ALLOY STEEL CASTINGS

1943

1945

1947

1949

1949

1951

Rureau of Census

FIG. 1—Steel casting tonnage from 1943 to 1951.

Some consider the basic process more flexible. Basic furnaces are used for melts that must meet exacting specification requirements and the acid furnaces for the general run of castings. In these foundries the phosphorus and sulfur content of the foundry return scrap is maintained at a considerably lower level than in shops operating with acid practice exclusively. Foundry scrap, when mixed with purchased scrap, helps keep sulfur and phosphorus within tolerable limits in the acid melts.




FIG. 2—A modern 6-ton capacity basic electric arc furnace in normal operating position.




FIG. 3—An electric arc furnace having a removable top is charged by a drop bottom bucket.

AUTOMATION

Cuts forging costs,



By E. G. de Coriolis Director of Research



J. D. Nesbitt
Development Engineer
Surface Combustion Corp.
Toledo

Automation is just around the corner for forge shops—large and small. Plants once stymied by the limits of operator skill and lack of fast heating equipment, now have new, faster production methods available. Faster forging machines, fed by high speed heating furnaces, and use of modern transfer equipment have made automation in the forge shop practical. Higher output per man hour, improved quality, and lower costs resulted.

Principles of automation generally applied in automotive machine shops, press departments and even in the foundries, have not been widely applied in forging practice.

Limiting factors preventing applications of automation to the forging industry have been:

1—Predominant use of forging hammers requiring highly skilled operators. Operating speed was, therefore, dependent on the skill and capacity of the hammerman as well as equipment speed limitations.

2—Use of manually fed and discharged batch type furnaces which were frequently the bottleneck in production. In recent years forging machines (vertical presses and horizontal upsetters) have taken over a large number of operations in the forging industry. Practical production limits for such equipment are set only by ability to supply hot billets, transfer from one die station to another and remove forgings to auxiliary equipment such as trim presses and other forming equipment.

However, scale is not removed from billet surfaces by press or upsetter forging. The scale is either embedded in the surface of the forging or remains in die cavities causing excessive die wear and requiring frequent shutdowns for die maintenance.

These factors have resulted in a need for the development and application of high speed heaters capable of delivering uniformly heated steel to forging equipment on a fixed cycle setting the pace for the operation. Attainable production rates with this type of heating have surpassed the ability of crew members to handle the billets—thus the possible application of automation principles to modern forging equipment.

Since automation in the forge shop will be less costly than in machine and press shops, both small job and large production forge shops will find full or partial automation a practical approach to the problem of increasing output, maintaining quality and lowering costs.

Semi-automatic automation increases production but retains the same number of men. But automation permits one man to perform two functions, thus increasing output. One man places heated work pieces on the first press die station and also loads cold stock on a conveyer which automatically feeds the furnace pusher.

A leading automotive forge shop has increased production of ring gears nearly 100 pct by this type of application, Fig. 1. An unskilled worker loads billets on a conveyer and also delivers heated billets to the first die position in the forging press. A continuous supply of uniformly heated steel to the operator is assured. Hundreds of steps every day and much physical lifting is eliminated.

"Increases production and reduces manpower . . . High speed heaters used . . . stock is delivered by gravity to upsetter . . ."

Improves quality

Semi-automatic installations can also reduce manpower. Hopper type feeders for two or more furnaces are supplied from a single point or by one man. This eliminates one man from each crew but one. Most forge shops estimate saving from elimination of one man per shift at \$8000 to \$12,000 per year. In most cases automatic equipment of this type can be amortized in one year or less, on a single shift operation. Savings for three shift operation are correspondingly higher.

An outstanding example involves a battery of high speed heaters used in upsetting automotive door hinges. Each furnace, with hopperfeed and gravity discharge, is designed for operation in pairs. As shown in Fig. 2, one man loads both hoppers. Heated stock is delivered by gravity to upsetter operator. Output per usetter has been more than doubled by this arrangement.

Fully-automatic operation both increases production and reduces manpower. Stock is loaded in bundles to feeding device or fed singly from preceding operation. Furnace is completely mechanized and discharges to indexing position from whence it is automatically fed to forging or hotforming operation.

Steel bars, for example, are now being fed automatically into a new slot type 4-zone, high speed heating furnace. The furnace is 21 ft long and capable of heating from 200 to 2400 pieces per hr, Fig. 3. For lower rates, individual sections of the furnace are shut down. This particular application is fully automatic from shearing chamfering and heating to the flying "slitter."




FIG. 1—Barrel type high speed gas furnace with automatic conveyer system for charging and discharging ring gear billets. One operator loads billets, feeds presses.




FIG. 2—Pair of high speed heaters, with hopperfeed and gravity discharge, are fed by one man. They discharge in opposite directions to upsetter operators.

ADVANTAGES FOR FORGE SHOPS

Advantages claimed for a forging operation in which high speed billet heating is combined with automatic materials handling:

I—Greatly increased output per man-hour without increasing present investment in forging equipment.

2—Steady flow of uniformly heated material to the operator is controlled by the furnace cycle, permitting maximum ortput of quality forgings.

3-Greater output per sq ft of floor space.

4—Savings of as much as one-half in investment as

compared with some other fast heating methods.

5—Increased die life, resulting from comparative freedom from scale and uniform temperature of the heated billets.

6-Low maintenance expense.

7.—Outstanding adaptability to stock size changes. In many cases, only the materials handling fixtures outside the heating furnace need to be changed.

8-Gas or oil firing can be used.

9—Furnace heat can be kept away from the operator.

"Entire bar is heated in a high speed heater . . . Five pieces may be forged without reheating . . ."

Conveyer speed is interlocked with "slitter" action.

The trend toward automatic upsetter operations is well advanced. In one installation, bars are cut into short lengths. The entire bar is then heated in a high speed heater and as many as five pieces may be forged to shape without reheating. Eventually, this may become one of the most widely employed applications for high speed heaters.

Fully automatic handling of bars or billets from the bar yard to the finished forging are not yet entirely practical although such installations are being considered.

High speed furnace design can be adapted efficiently to either overall or selective heating. Barrel and split barrel, with single nozzle burners and slot type with impact line burners designs are in use.

Barrel-type furnaces have sectional cylindrical heating chambers. Each section consists of a refractory lined steel shell, equipped with tangentially firing burner ports on relatively close centers, Fig. 4.

Lining thickness up to 7½ in. minimizes heat losses and heat storage. Portions of the furnace exposed to maximum temperatures are lined with high temperature castable refractory. These elements include heating sections, the charge openings, a portion of the exhaust stacks and skid support piers.

Billets can be charged on one or more rows in the barrel type furnace, by means of a hydraulic




FIG. 3—Four-zone slot type high speed heater fully automated from stock feed shearing, chamfering and heating to flying slitter operations.

pusher. A wide range of stock lengths can be accommodated without adjustments. Pusher stroke length is self adjusting. Where production requirements permit, fixed stroke mechanical pusher systems are sometimes used.

Another type of high speed heating equipment in common use on automated applications consists in opposed or overfired water cooled slot type burners. This type of equipment is usually used for selective or partial heating as shown in Figs. 2 and 3. Opposed firing, as shown in Figs. 2, is generally used for heating flat work pieces. The slot burner-impact bed combination, Fig. 5, is used for bar end heating. The latter equipment is readily adaptable for small diameter slug heating.

A fairly wide range of stock sizes can be accommodated by a single rail spacing and any desired range can be handled by use of alternate rails as required in the barrel type. Any part size which will fit in the heating chamber and allow adequate clearances for uniform radiation and circulation of combustion products will be properly heated in both barrel and slot designs.

Raising the furnace permits feed by gravity to the forging hammer or press at any desired elevation and location of auxiliary equipment beneath the furnace.

Unusually rapid heating

The principle of high thermal head operation makes possible unusually rapid heating. Whereas a conventional fuel-fired furnace will require 20 to 30 min per inch of billet thickness to raise the temperature to the forging level, and a rotary type furnace will require 15 min per inch of thickness, a fuel-fired high speed furnace requires only 2^{4} ₂ to 3 min per inch of section.

The combination of high velocity and centrifugal action causes the heated gas-air mixture to hug the refractory surfaces where combustion is extremely rapid and complete. Partially burned gases do not contact the work surfaces.

Using this method of combustion, the inner surface of the refractory lining becomes a radiant burner face capable of imparting heat energy at great intensity on all exposed work surfaces.

High furnace operating temperatures can be reached very quickly.² A typical furnace may be heated to 2500°F within 30 min. Maximum temperature of 2700°F can be attained in an hour. In the high sped type furnace, the furnace temperature is held in the range 2600° to 2700°F. Cycling time is determined by the time necessary to raise the temperature of the billet to the desired level. "Soaking" time, in the furnace, is eliminated.

While the surface of the billet may cool rapidly when first removed from the furnace, the fact that the temperature of the core is still rising as the piece leaves the furnace helps to maintain billet temperature. Also, because of the short time at the forging temperature, grain growth is less than for conventional heating and scaling is considerably reduced. Fine grain, it is believed, con-

tributes to the reduced forging pressures required in shops using high speed fuel-fired heating.

Uniform temperature of the rapidly heated biliets undoubtedly contributes to improved forging die life reported by forge operators. In addition to more uniform heating, a slightly higher billet temperature is permitted without endangering the heating equipment or causing excessive grain growth.

15

11

2

le

is

g.

8-

te

d

0

le

f

S

d

96

e

ľ.

IS

n

162

SS

E

Billets up to 10 in, thick weighing over 1000 lb have been heated successfully by the high speed method. Larger automated installations are now being planned for both ferrous and nonferrous forging.

The high temperatures required for forging create special problems, involving the expansion and contraction of metals and refractories. The new furnaces are designed to meet this situation. Most of these furnaces are anchored to structural framework at the charge end. The entire cylindrical steel furnace rests on rollers with the hot end of the furnace spring loaded. As the furnace is heated, it expands against the springs—in some cases as much as I in. As the furnace cools off, the spring action forces it back to its original position.

There is no appreciable expansion in the water cooled rails. The barrel type furnace shown in Fig. 4 has 40 burners, arranged 20 per side in groups of five, firing tangent to the inner periphery of the refractory lining. Work is carried through the furnace at the approximate center of the heating chamber.

Close control of the air-gas mixture is maintained with either premix or nozzle-mix firing. For premix installations, gas is completely premixed before it is supplied to two manifolds which are located on each side of the furnace structure. The mixture is then forced through burner connections made of flexible steel tubing for distribution to each burner. Mixture pressure entering the manifolds is 2 psi.

Nozzle mixing burner equipment is also available which will give the same operating results and performance as previously described premix firing. It has the additional advantages of elimination of premix manifolds, simplified and more economical piping, greater turndown and is more readily adaptable to oil application. Control of fuel-air ratio is achieved in both cases by balancing gas pressure against air pressure upstream of supply line orfices. Eventually many forge shops will operate with much less manual effort. Fig. 6 shows a schematic layout for a theoretical Forge Shop of Tomorrow.

References

¹ W. G. Patton, Automated Forging Line Boosts Output, Cuts Costs, The Iron Age, Oct. 2, 1952, p. 93.

² L. J. Stanbery and J. M. Brennan, Rapid Billet Heating With Gas, The Iron Age, Aug. 26, 1948, p. 82.




FIG. 4—Cross section through width of typical high speed barrel type furnace used in automated forging setup.




FIG. 5—Cutaway view of slot type high speed heater with water cooled line burners and impact refractory bed.




FIG. 6—Layout for "Forge Shop of Tomorrow." Entire operais automatically controlled, actuated.

P CHARTS improve METHODS FOR DETERMINING DOWNTIME



By G. Nadler Assoc, Professor of Industrial Engineering Washington University St. Louis, Mo.



D. H. Denholm Production Engineer Chase Bag Co. St. Louis, Mc.

If you use ratio-delay techniques for establishing downtime percentages, you can get more accurate results with this simple method. The p chart, long a handy quality control tool, has been adapted for use with ratio-delay techniques. Result is an improved statistical method for determining downtime, and more accurate data for use in development and application of incentive plans.

Application of an incentive plan to a job or group of jobs can usually be reduced to a formula, if time study allowances can be accurately determined. All the usual allowances such as personal time or incentive are generally empirical with the exception of the percent downtime, which can be more accurately determined. Finding this downtime for a group of machines, however, can become a real headache.

The ratio-delay technique is widely used to quickly, accurately and economically determine percentage downtime for a group of similar machines using similar materials. Although the technique is derived from statistical bases, its application is relatively simple. Essentially, ratio-delay is the same as p, or fraction defective charts used in statistical quality control. For all parts produced from the same combination of

man, machine and materials, a certain percentage is defective. If we consider machine downtime as being defective the same thing holds true. Then, of all the observations made of a man-machine relationship, a certain percentage would be downtime. This percentage is then applied as a downtime allowance in a time study.

An important step in the quality control procedure for a p chart is investigation of data as it is collected. When a fraction defective for all material has been determined, a p chart is constructed showing the limits of variation of the fraction defective of an individual inspection group. These limits distinguish the expected-by-chance fraction defective dispersion of a subgroup from fraction defective in the entire lot. When an inspection group fraction defective falls outside the upper or lower limits, some as-

signable cause is indicated. The next step is to find the cause and isolate it.

This charting procedure has been used advantageously with ratio-delay. Although the p chart can be advantageously used, the authors have found that the chart is not actually constructed in industry as data is being collected. This should be done to check on the basic background of the ratio-delay method. As the following example shows, not making the chart can easily lead to inclusion of information that does not belong in the downtime allowance.

After selecting the group of machines on which the ratio-delay study was to be made, it was necessary to determine the approximate number of observations needed for a satisfactorily accurate downtime figure. To calculate the number of observations required, three assumptions were made which had no bearing on the final results. These, used only for preliminary purposes, were: An estimation of downtime for the group of machines; degree of accuracy desired for the percent downtime; level of confidence required for the degree of accuracy. Downtime was estimated as 10 pct and desired degree of accuracy was 2 pct. It was also decided that 2 pct accuracy of the downtime percentage would be sufficient 95 pct of the time. This was incorporated in the formula: desired accuracy = $2\sqrt{\frac{n'(1-n')}{n'}}$ where p' = estimateddowntime and N = required number of observations.

The substitution is shown in the equation

$$0.0_{-}=2\sqrt{\frac{0.10~(0.90)}{N}}$$
. Solving for N, 900 was found to be the required number of readings.

Recording observations followed the normal ratio-delay procedure of taking readings at random intervals during the day. Rest periods and lunch hour were excluded. The remainder of the time, the observer was in the plant as often as possible. Code numbers were assigned to all the possible conditions in which the equipment might be found. As random observations took place, the code numbers were noted. All other precautions were exercised as noted in other treatises on ratio-delay.

After about half of the time thought necessary for the complete study had elapsed, the chart for fraction-defective was started. Downtime observations were totaled. Dividing the downtime observations by total observations gave an estimate of the fraction downtime or \overline{p} . This value, $\overline{p}=0.161$, was substituted in the formula.

$$\vec{p} = 3 \sqrt{\vec{p} \cdot (1 - \vec{p})}$$

The formula gives the upper and lower control limits for the p chart. Upper and lower control limits were found for each week, using the p calculated before, when the proper total number of observations for that week was substituted for N. The calculations of the upper and lower control limits for each week are given

Can YOU Use Ratio-Delay?

Ratio-Delay is a statistical technique for determining what portions of machine delays are avoidable and what are unavoidable.

Advantages of Ratio-Delay

Observer's work may be interrupted any time without affecting the study. Taking study is not tedious for the observer.

Operators do not object to ratio-delay studies since no stop watch is used and operators are not under long observation.

Cost of ratio-delay study is much less than that of production or all day time studies.

More representative period of time is covered by ratiodelay as compared to all daytime studies.

More accurate delay allowance possible.

Points out areas where work simplification can be applied.

Responsibilities of staff functions, such as maintenance, stockroom are more apparent.

Provides facts, instead of opinions, about delays and irregular occurrences.

How Ratio-Delay Works

Observations at random intervals of time during days and weeks are taken on a machine's status—running or idle.

There must be enough time between observations to give independent readings.

if enough observations are taken, the percentage number of readings which show a machine idle tends to equal the percentage time the machine is actually idle. Should be applied only to operators doing similar work or to a machine or group of machines doing similar operations. Observations on the machines of a group should be in random order.

Data are more reliable if readings are taken over a long period of time. A thousand readings give fairly accurate results. Over 3000 readings give very accurate results. But accuracy without p-charts can not be stated because of possible observation errors.

As the percentage of delay time increases, more observations are needed for a given accuracy.

nt-

m-

ue.

na-

be

as

ro-

as

for

is

of

ec-

ex-

of

ire

ive as-

GE

"Interest was centered on unavoidable stoppages which are inherent in a production run..."

in Table 1. The p chart for these first weeks, Fig. 1, shows the individual values of fraction downtime, plotted with the \bar{p} as a center line and the control limits drawn on either side of the center line.

Each week's fraction downtime was found by dividing the observations of downtime for the week by the total number of observations for the week. Although the actual p obtained is now the same as the original estimate p', none of the above or following calculations are affected

The chart, Fig. 1, showed immediately that weeks 2, 8 and 9 produced fraction downtimes outside the control limits. The natural questions asked were, "What was the cause of these points being beyond limits?" and "Could anything be done to correct that cause?"

Legitimate machine stoppages

A check of the records and reasons for recording downtime, showed some of the values included in the total observations and some values recorded as downtime included legitimate machine stoppage for which a man was paid separately. For example, makeready and roll change, separately paid for, were included in the total observations; and such separately paid categories as breakdowns, proof check, run proof, wait for instructions, etc., were also included as downtime.

In determining the percent downtime allowance to use in establishing the time study rate, interest was centered mainly in those unavoidable stoppages which are an inherent part of an actual production run. Some unavoidable situations encountered were bad plates, mechanical trouble, trouble with material, waiting for material, machine adjustment, etc. The ratio-delay being conducted was confined purely to the run or production phase of this operation on the bank of machines.

When a group of complicated machines are run on incentive, establishment of separate legitimate downtime interruptions must be made for the rate to work fairly. Recognition of those that are paid for separately and those that are included in the time study rate are sometimes difficult to judge. This difficulty was clearly demonstrated by the control chart procedure. Reviewing the figures indicated that there were many such occurrences where the stoppage was remunerated separately. A check on the daily work cards confirmed this.

After eliminating those observations which were clearly paid for separately from the down-time observations and the total number of observations and then recalculating the p and control limits, it was found that the basic information concerning the upper and lower control limits was that presented in Table II and the control chart was that in Fig. 2.

Fig. 2 shows the points are now in control indicating that the variations of the fraction downtime are that which can be normally expected by chance causes alone. After gathering more than the earlier indicated 900 readings* a control

chart was made for the complete information recalculating p and checking all the data, Table III, for control. This chart is shown in Fig. 3 for the complete study data.

After the delay-ratio of 14.3 pct was found the degree of accuracy of the final study was calculated. Accuracy is shown by the formula desired accuracy = $2\sqrt{\frac{p'(1-p')}{N}}$, where the




FIG. 1—Fraction downtime outside the control limits show up in weeks 2, 8 and 9, indicate need for further check.

FIG. 2—Plot within control limits resulted when legitimate delays shown in FIG. I were removed, times replotted.

FIG. 3—Final chart for all readings, recalculated, shows plot of delay time to be well within upper and lower limits.

10 12

Other ratio delay studies were being made simultaneously, and readings were continued on all jobs throughout the period of observation.

11-

1)-

n n

ol

of

II.

nd

11-

la

he

its.

GE

RATIO-DELAY DATA: FIRST NINE WEEKS

Week	No. of Observa- tions N	Downtime Observa- tions c	Fraction Downtime P	$3\frac{\bar{p}(1-\bar{p})}{N}$	Control Limit (LCL)	Control Limit (UCL)
1 2 3	81	15	0.185	0.0408	0.120	0.202
	93	11	0.118	0.0381	0.123	0.199
	101	15	0.149	0.0386	0.124	0.198
23456789	135	35	0.185	0.0316	0.129	0.193
	76	10	0.132	0.0421	0.119	0.203
	65	12	0.185	0.0455	0.116	0.206
	112	19	0.170	0.0347	0.126	0.196
8	133	17	0.128	0.0318	0.129	0.193
	121	24	0.198	0.0334	0.127	0.194
Totals	917	148	$\bar{p} = \frac{148}{913}$	= 0.161		

actual p of 0.143 was substituted and 1428 was substituted for N. This gave an error of less than 1 pct. This implies that, if another study was made, 95 pct of the time the fraction downtime p would not be greater than \pm 1 pct from the present fraction downtime of 0.143.

Ratio-delay technique has been used widely in determining the downtime allowance to be applied to time study.

REFERENCES

- J. S. Petro, Using Ratio-Delay Studies to Set Allowances, Factory Management and Maintenance, Oct., 1948.
- R. L. Morrow, Time Study and Motion Economy, Ronald Press: New York, 1946.
- L. P. Alford and J. R. Bangs, Production Handbook, Ronald Press: New York, 1944.

TABLE II

RATIO-DELAY DATA: FIRST NINE WEEKS*

Week	No. of Observa- tions N	Downtime Observa- tions	Fraction Downtime	$3\frac{\vec{p}(1-\vec{p})}{N}$	Lower Control Limit (LCL)	Upper Control Limit (UCL)
1 2 3 4 5 6 7 8	61 77 76 105 56 61 90 114 109	11 9 12 17 7 10 14 13	0.180 0.117 0.158 0.162 0.125 0.164 0.156 0.114	0.0453 0.0404 0.0406 0.0346 0.0473 0.0453 0.0373 0.0333	0.102 0.107 0.106 0.112 0.100 0.102 0.110 0.114 0.113	0.192 0.187 0.188 0.182 0.194 0.192 0.184 0.180 0.181
Totals	749	110	$\bar{p} = \frac{110}{740}$	= 0.147		

* Corrected.

TABLE III

COMPLETE RATIO-DELAY DATA

Week	No. of Observa- tions N	Downtime Observa- tions €	Fraction Downtime	$3\frac{\tilde{\rho}(1-\tilde{\rho})}{N}$	Lower Control Limit (LCL)	Upper Control Limit (UCL)	
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16	61 77 78 105 56 61 90 114 109 149 145 126 85 56 25	11 9 12 17 7 10 14 13 17 18 20 17 14 8	0.180 0.117 0.158 0.162 0.162 0.164 0.156 0.114 0.156 0.121 0.138 0.135 0.184 0.138	0.0453 0.0404 0.0406 0.0346 0.0473 0.0473 0.0332 0.0332 0.0339 0.0295 0.0316 0.0316 0.0316 0.0316 0.0316 0.0372	0.098 0.103 0.102 0.108 0.096 0.098 0.106 0.110 0.109 0.114 0.114 0.111 0.104 0.096 0.072 0.106	0.188 0.183 0.184 9.178 0.190 0.188 0.180 0.176 0.177 0.177 0.172 0.172 0.182	
Totals	1428	204	$\frac{1}{p} = \frac{20}{141}$	- = 0.143			

NEW BOOKS

- "Die-Casting," by C. O. Herb. In the second edition of a text which has already gained recognition, Mr. Herb brings his data up-to-date and to a new completeness. Discussion of methods, machinery, alloys and die design make up the backbone of the book. The Industrial Press, 148 Lafayette St., New York 13. \$4.50. 310 p.
- "Gmelins Handbuch Der Anorganischen Chemie. System No. 41 Titan (Titanium)." Entire pertinent world literature on titanium is systematically arranged and reviewed. Geology, geochemistry, metallurgy, physics, technology, and alloys are covered. (In German.) Walter J. Johnson, Inc., 125 East 23 St., New York 10. \$27.50. 481 p.
- "Gmelins Handbuch Der Anorganischen Chemie, System No. 3 Sauerstoff (Oxygen), Part 2." (In German.) Covers the distribution of oxygen, physical and chemical properties and behavior. A special section deals with oxygen isotopes. Technology of manufacture is treated in detail. A handbook of the pertinent literature on the subject. Walter J. Johnson, Inc., 125 East 23 St., New York 10. \$15.48. 218 p.
- "Yankee Iron." Some time ago an unusual book came across this desk telling the story of a company—Eastern Malleable Iron Co. Imaginative overall, and lush in spots, it tells the dramatic and moving story of the development and life of a foundry business. Inset in the cover is a sample of the company product, a "Yankee Iron" casting. Eastern Malleable Iron Co., Naugatuck, Conn. 140 p.
- "101 New Uses For Porcelain Enamel." Comprehensive listing of feasible applications of porcelain enamel. Possible products range from hog feeders to ship bulkheads. Porcelain Enamel Institute, 1010 Vermont Ave., N.W., Washington 5, D. C. \$6.00.
- "A Manual On Underground Corrosion." A roundup of latest information on corrosion causes and corrective measures, illustrated with line drawings. Starts with an explanation of the Galvanic cell and is written so the layman can understand the subject. Columbia Gas System Corp., 79 North Third St., Columbus 15, Ohio. 75¢. 37 p.

CARBIDE TIPPED HAMMERS cut pulverizing costs



By W. E. Fawcett Engineer Kennametal, Inc. Latrobe, Pa.

Hammers of pulverizing mills last up to 100 times longer when tipped with tungsten carbide. In one coke crushing installation where special steel hammers milled one carload, carbide tipped hammers milled 80 carloads. Similar results have been obtained in milling foundry sand. Overall hammer length, essential to mill efficiency, is maintained for longer periods. K grades of tungsten carbide have been developed with high impact strength. Costs for replacement of hammers have been reduced while maintenance downtime has been minimized.

hile the advantages of cemented tungsten carbides for metal working operations are well known, a comparatively new field is their use in pulverizer and shredding applications.

Alloy steel hardness runs 10 to 15 Rc points below the wear resistant grades of tungsten carbide. These grades of carbide K1, K6 and K8 have a hardness of Rc 76, 80, and 81 respectively compared to steel with a maximum hardness of about Rc 66. The individual tungsten carbide particles are between sapphire and diamond in the scratch hardness test.

The wear surface is almost entirely made up of these extremely hard particles, providing good resistance to abrasive action. Fig. 1 shows a typical metallurgical structure. Uniformly distributed grains of various sizes up to a few micro inches in length provide strength, and virtually complete freedom from porosity. This excellent structure accounts, in a large measure, for the outstanding wear resistance tungsten carbides display. Comparative life up to 100 times that of steel has been achieved in some cases.

Normally an exceptionally hard material such as tungsten carbide would have a very low impact strength. Continued research has developed grades with surprisingly high impact strength. A comparison of K6 with SAE 4045 steel will help to visualize this high impact strength. A single blow on a ½-in. square specimen of K6 shows an impact strength in the vicinity of 9.5 ft lb. Impact strength of SAE 4045 steel at 174 Bhn may run as low as 5 ft lb. The softer the tungsten carbide grade, the more shock resistant it proves to be.

High impact strength of some grades of cemented carbide is demonstrated by its use in interrupted cutting with single-point tools, and percussive applications such as rock bits, mortars and pestles, and hammer applications for pulverizing.

In making lead pencils, pea-sized graphite particles are first pulverized into a very fine powder. A Raymond 18-in. high speed vertical pulverizing mill is used to reduce the graphite. Hammers revolve in a 17½-in. diam circle at 6000 rpm. The




FIG. 1—Metallurgical structure of tungsten carbide. Hard particles, uniform grain distribution provide strength, freedom from porosity. X1500.




FIG. 2—Hammers of graphite pulverizing mill tipped with K6. Pea-sized particles are ground to fine powder.

mill is powered with a 25 hp motor and graphite fed in by a screw-type conveyer.

Lump graphite drops onto the hammers which spin horizontally around a vertical axis. Forced air at 800 cfm carries the fine graphite up to a classifying device through which material of finished size passes. Oversized particles drop back down into the hammers for further pulverizing. This fine graphite is carried off through a closed system to hoppers where it is bagged.

Present life of K6 carbide tipped hammers is 500 hr at a cost of \$0.011 per hammer per hour of pulverization. This figure far surpasses anything previously tried, including other carbides, Figs. 2 and 3. Carbide tipped hammers have been used in several cases on the Jay Bee Mill for chopping alfalfa and grain. On these mills, a gravity separator removes stones, bolts, and other foreign material.

The mill, Fig. 4, uses 54 hammers per set which swing in a 34-in. diam circle at 3600 rpm. Two tips, each $3/16 \times 6/16 \times 9/16$ in. were applied to the hammer bodies, one tip on each end of the reversible hammers. The hammers are normally

used for chopping alfalfa. During off-seasons, however, corn is run through the mill.

Steel hammers formerly used cost \$1.24 each. Hammer life was estimated at 200 tons per set. This figures out to a 0.337¢ hammer cost per ton, plus labor and down time for changing hammers every 24 hr during operation. Carbide-tipped hammers consisted of 54 hammer bodies at \$1.24 each plus \$5.17 for the carbide and the brazing of two K6 tips on each hammer. After 1800 tons were put through the mill its hammers were only partly used on one end. Operational cost at this point totaled 0.192¢ per ton. An estimated ½ hammer life has been used. This would amount to an estimated cost of 0.064¢ per ton, without the added savings in downtime realized.

Several chocolate manufacturers use the carbide tipped hammers to pulverize cocoa beans. Hammers on their Raymond mills travel in a 22-in, diam circle at 3600 rpm. Original manganese steel hammers, Fig. 5, lasted about 10 days



FIG. 3—Pulled from service before full life was obtained, this graphite mill hammer shows signs of wear.




FIG. 4—Setup of carbide-tipped hammers in Jay Bee mill used for chopping alfalfa and corn.

and crushed about 180,000 lb of cocoa beans. Steel hammers were changed frequently since higher efficiency is achieved when hammers are at full length. Greater overall efficiency has been

h.

11

A

3

.5

4

ıt

1f

n

1e

E

Carbide tipped hammers used in a coke crushing mill boosted yield per set of hammers from one to 80 carloads . . . With extra wearproofing output reached 110 carloads per set . . .



FIG. 5—Cast manganese steel hammer after pulverizing about 180,000 lb of cocoa beans.



industrial definition of the state of the st

FIG. 6—Hammer tipped with K6 tungsten carbide was removed after pulverizing 5 million 1b of cocoa beans.



FIG. 7—Forged steel hammer used for crushing coke. Hammer, left, crushed 33 tons. Hammer, right, is unused.

achieved by carbide hammers due to their longer life at full length.

K6 tipped hammers, Fig. 6, operated for 8 months on a 7-day week at 22,000 lb per day, or 5 million lb of pulverized cocoa bean. An increased life of 28 times over steel hammers was noted. This application showed an estimated savings for 1 yr of \$3007.

A steel company had previously used special steel hammers for crushing coke to ¹/₈-in, for sintering. These hammers, 38 to a set, were removed and built up with special hard welding material after crushing 1 carload of 33 tons. Fig. 7.

To minimize hammer changing and maintain production, a set of steel hammers tipped with K12 carbide was tried. These hammers, Fig. 8, crushed 80 carloads, 2640 tons, before steel supporting the carbide tips was worn too much for further operation. To prevent wearing of steel behind the tips, two rows of carbide tips were used on the next set of hammers, Fig. 9. With this additional wear-proofing 110 carloads, or 36,630 tons of coke were crushed before replacement was necessary.

A third set of hammers was installed with three rows of our tips. Inspection after crushing 75 carloads of coke indicated the hammers would be good for well over 200 carloads.

Many other similar applications are being developed. These embrace pulverizing of porcelain in the reclaiming of scrap; pulverizing of coal for use in solid fuel injection systems; breaking up of foundry sand; pulverizing of the less dense stone; and shredding of grain, peanut shells, wood, and sugar cane. Application of tungsten carbide tips to hammer mill hammers, has generally resulted in longer service life, more reliable performance and lower maintenance costs.



FIG. 8—Eighty carloads of coke were crushed in mill from which this tungsten carbide tipped hammer was taken.




FIG. 9—To prevent wear behind the tips, coke crushing hammers were tipped with tungsten carbide as above.

PRECISION INSPECTION

Checks Engine Components Rapidly, Accurately

By Herbert Chase Consultant Forest Hills, N. Y.



Air gages play an important part in insuring quick and precise measurements of engine components in Ford's Cleveland plant. In one case, 27 dimensions of a crankshaft are checked in 50 seconds. One man can check dimensions on 800 to 900 camshafts per 8 hr shift with a camshaft multicheck. A special scale weighs connecting rod ends and automatically sets milling cutters for proper metal removal. The latest type of dynamic crankshaft balancing equipment is used.

Production of components for six-cylinder engines in Ford Motor Co.'s new Cleveland plant is accomplished rapidly and with a high degree of precision. Checking and inspection of these components requires proper measuring equipment so that corrections can be made before sizes go outside of specified limits.

Of the numerous types of measuring equipment used in the plant, air gages play an important part in insuring rapid and precise measurements. With air gages measurements are closer than those obtained in ordinary gaging but are



FIG. I—Final dimensional check of Ford six-cylinder engine crankshafts is made on this machine. Air gages measure 27 critical dimensions.

THE AUTHOR—Mr. Chase, engineer, former trade magazine editor, and author of engineering texts, has been closely associated with industrial developments since 1910.

A complete job of gaging dimensions that must be closely held... One gage can indicate 27 critical crankshaft dimensions at once.

so much faster that the time savings justify their greater cost.

In many cases, air gages do a complete job of gaging dimensions that must be closely held. They are so arranged that the position of bobs in glass tubes between lines at specified tolerances show at a glance whether dimensions are within limits. One of the most elaborate of these gages, shown in Fig. 1, shows quickly whether 27 critical dimensions of a crankshaft are within limits, as well as the exact dimension at each point.

The crankshaft is placed in a self-aligning cradle or fixture and turned by hand to determine whether bearing surfaces are out of round. Some dimensions are held within limits 0.0008 in. apart. There are 27 gage tubes. If the air supported bobs do not float between limiting lines on the background scales, the part is rejected. About 50 seconds is required to check the 27 dimensions on the shaft, which is faster and more precise than conventional gaging.

Another air gage, a camshaft multicheck, measures only the four main bearings for diameter and runout, on face for runout and the oil pump gear for pitch diameter. These measurements require only ten gage tubes. One man is able to check 800 to 900 camshafts per 8 hr shift and as skill improves can go as high as 1200 to 1400.

A further camshaft check is made on the Cam Probograph shown in Fig. 2. This highly accurate production instrument supports the camshaft between centers to measure and record cam lobe profile deviations, eccentricities, angular alignments, and also automatically computes and records cam lobe profiles corrected for eccentricity. Since this check takes about 2 hr per camshaft, samples are taken from various cam grinding machines during all working shifts, affording complete control of the process.

A pot-like air gage is used to check pistons, each of which has to be placed by hand into a fixture, as seen in Fig. 3. When in place, air gage plugs enter both ends of the hole. Readings are then made on a four-tube multi-column gage that indicates two piston diameters at two locations for tapered OD as well as the ID of the pin hole at each end.

Graded in steps of 0.0001 in.

After readings of the pinhole ID are taken, the pistons are graded for selective fits of pins that differ in steps of only 0.0001 in. Pistons are then fed along tracks in a rack, each track being for pistons having one of three different selected hole diameters. At the end of the rack, pistons are fitted with pins of corresponding sizes.

The weight of each end of connecting rods is determined on a special scale shown at the right in Fig. 4. Weight at each end of the connecting rods must be within 2 grams of specifications. Since the weight of both ends always exceeds the maximum allowable limit, they must be milled to bring them within limits To prevent error and delay, the weighing scale is provided with an electronic device which automatically sets two milling cutters to remove the correct amount of metal at each end.

After the rod is weighed it is placed in the




FIG. 2 — With Cam Probograph measurements are made on cam lobe contour, runout and heel diameter. A graphical record of any deviations from standard is made.

milling fixture and the cutters are started. No hand setting is required. While one rod is being milled, the next one is being weighed and setting for the cutters computed according to the amount of correction needed. No re-weighing after milling is required. About 7000 rods per 8 hr shift are weighed and milled in this setup.

Dimensional checks of connecting rods are made mostly by multi-column air gages. One of these has a "nut cracker" fixture that employs a toggle arrangement to clamp the side faces of the crank end against a base, the rod first being set over a gage pin projecting up from the base.

The ID of the hole is measured at two points as a check on taper, and any lack of soundness is determined by swinging the rod through a 90 deg. angle while in the fixture. At the same time width between end faces is measured and any deviation from the squareness of these faces with the bore is determined. Measurements are indicated by the position of the bobs within the gage tubes.

Checked for parallel

Another air gage checks the relationship of the crank end pin bearing hole to the piston hole. Measurements are made to find out if the axes of the two holes are parallel, which they won't be if the rod is bent or twisted. Center to center distance of the two holes is also measured.

When the diameters of crank end and piston pin holes of rods are measured, the rods are classified as to hole sizes. This is done so that piston pins of correct size can be chosen and so that the crank end will be applied to a crankpin that it fits properly.

Dynamic balancing of the six-cylinder crankshafts is done in the latest type of balancer, one of which appears in Fig. 5. These machines not only determine the amount and location of unbalance but are equipped with instruments that indicate where and in what angular position weight must be removed to bring the shaft into balance. Drill heads, with $^{1}{}_{2}$ in. and I in. drills, are mounted on the machine and remove metal at specified points on the integrally cast counterweight or on the cheeks of the crankshaft.

Due to the length of the shafts, they are balanced one half at a time. On both halves the procedure is the same. The shaft is revolved and unbalance is recorded. The shaft is stopped and the operator sets it at the indicated angle. Drills are fed automatically to the required depth for proper amount of metal removal. When drilling is completed the correct dynamic balance is attained.



FIG. 4—Weights of each end of connecting rod are checked by precise scale, at right, which automatically sets milling cutters to correct depth.



FIG. 3—Pot-type gage in combination with air gages measures piston OD and taper as well as ID of piston hole. Pistons are graded as to pin hole size.



FIG. 5—Instrument readings on balancing machine automatically provide for correct metal removal, using drills mounted on the machine.

AUTOMATIC BAR POINTER IMPROVES SPRING PRODUCTION




FIG. I—Plan view of automatic end pointing setup used at Chrysler in front spring production.



By W. G. Patton Asst. Technical Editor

Addition of a comparatively simple mechanical bar handling and roll feeding device has increased production and cut rejects of pointed steel bars used for front suspension coil springs in Chryslermade cars. In addition to providing relief from a monotonous, fatiguing job, the device has improved quality control on the job. A big gain in output per sq ft of floor space was possible.

Front coil springs for Chrysler-built cars range in size from 0.654 in. to 0.519 in. diam. Bars varying from 127 in. to 154 in. in length are used for the coil springs for each line of cars and body type. Spring design varies according to the weight, length and other features of the vehicle.

In addition to holding the height of the coiled spring within specification limits, load specifications also apply. For example, coil springs must be held within =37 lb at a definite working height.

Close production control is essential, particularly since the point of the spring is an important factor in determining its length. Flatness of the point must also be closely held.

Meeting these exacting requirements, as well as the need for increased production, first drew the attention of Dodge management to the desirability of automatic feeding of an Ajax roll pointer. Details of the machine were worked out


by Dodge engineers cooperating with equipment suppliers.


The previous method used at Dodge for pointing steel bars for springs—and which is being continued until additional new equipment becomes available—involves the usual bar end heating in a slot-type furnace. The end-heated bars are moved manually to standard pointing rolls. The bars are then inserted alternately in the rolls and in the squeeze dies. Three roll-and-squeeze passes are required for each bar.

While highly skilled operators turn out a good product, it was evident when top output was needed that a lot of muscle was going into a job that could not be humanly controlled within desired close limits while maintaining the necessary production rate. This led to the decision to try automation.

Under the new completely automatic bar pointer setup, Fig. 1, production of pointed bars has been increased from 125 to 400 per hr. Output










FIG. 2—Bars are loaded into feeder, then automatically conveyed through fast heating furnace.

FIG. 3—Front view of pointer setup, showing relative position, halfway through the transfer cycle.

FIG. 4—Overall view shows operator at discharge table checking bars delivered from machine.

FIG. 5—Closeup of control box used on pointer setup. Air system plays an important part in operation of the control unit.

"Fatigue and drudgery have been eliminated . . . Negligible wear on the automatic setup . . ."

per sq ft of floor space has been increased proportionately and fewer rejects are reported even though production has been greatly increased. Human fatigue and drudgery have been eliminated from a tiresome, wearying job.

Operating experience during the past year shows there is negligible wear on the automatic setup. Downtime for adjustments and repairs has been held to a minimum. Air valves and other actuating and timing devices are flexible and have proved reliable in service.

Another advantage of the installation is that automatic equipment can be operated three shifts. A long operator training period is not needed.

Only one end of the bar — about 12 in. — is heated in the Surface Combustion slot-type furnace. For most springs, Amola steels (when available) or SAE 5160 centerless ground stock is used.

Steps in operation

Detailed steps in the bar-pointer operation are as follows:

1—Approximately a 1-hr supply, 400 bars, are placed on the loading rack, Fig. 2. Bars feed by gravity against a stop. Cam-operated pins located at three points along the storage rack move up simultaneously, pushing the bar onto a 2-screw conveyer which feeds the slot-type furnace. These pins also prevent movement of a second bar onto the furnace feed until the proper time. There are several stops and guides to control movement of the bars through the furnace.

2—Worm screws feeding the furnace are driven by a Reeves variable speed device. The highspeed gas furnace is equipped with water cooling and other standard features.

Movement of the bars through the furnace is synchronized with the turning of the rolls. The worm drive moves the bars through the heating furnace at a rate dependent on the production rate.

3—At the proper time, the worm drive releases the bar into a gravity-fed V-type holder. The holder is lined with wood at the cold end to minimize shock and eliminate vibration of the dropping bar. Simultaneousily, an air-actuated length gage moves out and pushes the bar into position for feeding the rolls. No end gage stop is used in the rolls.

4—A double arm crank simultaneously picks up the heated bar and places the finished bar on a table. The heated bar is held in back of the hot end by a steel finger-type gripper mounted on a steel arm, Fig. 3.

Timing of the opening and closing of the fingers and forward and backward movement of the arm is cam-controlled by a chain timer synchronized with the turning of the rolls. A pulley mounted on the rear arm, also supports the bar.

Height of the bar above the floor is determined by the amount the arm is moved forward or backward. Each bar moves through 180° during the process of being transferred from the loading station. The bar moves forward a distance of approximately 18 in. at the start of the cycle.

5—In front of the opening between the squeezing dies is a steady rest. This is in top position during each of the first two strokes.

6—The forging cycle consists of three strokes. On each stroke an alternate rolling and squeezing takes place. With each stroke, the bar moves forward for rolling, retracts for squeezing. This cycle is repeated twice. On the third stroke, the steady rest position is lowered about ¾ in. to permit the bar to reach the lowest position in the die. In this position, identifying parts numbers are stamped on the narrow, flat side of the pointed bar.

7—The combined load-pickup device removes the pointed bar and simultaneously loads a freshly heated bar into the machine. Pointed bars are transferred to a discharge table, Fig. 4.

Ability of the automatic machine to keep pointed bars flat and uniformly square was an important consideration in adopting the new forming method. In the Dodge spring pointing operation, width and thicknes of the pointed bar is held within 0.015 in. and 0.005 in. respectively.

Peened with cut wire shot

Following the pointing operation, bars are conveyed through a bar heating furnace, coiled and oil quenched and drawn and, finally, shot peened with cut wire shot.

Since consistently high quality of the finished coil spring is largely dependent on the accuracy and control of the initial pointing operation, the uniform results obtained from this new automatic high production pointing operation are most desirable.

The cam gear box which controls the sequence of operations of the bar pointing machine is shown in Fig. 5. Cam gears are operated directly off a jack shaft by a roller chain connected to the main roll. Shown in the photograph are five Air Saver valves which work directly off the cam.

The air system operates at a pressure of 60 psi. The air system at Dodge operates at approximately 100 psi. A reduction valve is required to reduce the operating pressure to the desired level. A surge tank is included in the system to make certain an adequate volume of air will be available at all times.

Several of the valves in the cam box, Fig. 5, operate more than one valve in the air system. At several points in the system, flow control valves are used to provide the fine adjustment necessary to insure fast and accurate control.

Hot

..available at

CENTRAL STEEL

AND WIRE COMPANY

SEAMLESS STEEL

mechanical in complete size ranges

WELDED STEEL

(Flash-in and Flash-removed) Round, square and rectangular

STAINLESS STEEL

seamless and welded tube and pipe

COPPER AND BRASS

tubing and water pipe in a complete range of tempers

ALUMINUM

tubing and pipe in a wide range of tempers and analyses

Hot Rolled • Cold Finished

Carbon & Alloy • Stainless

Copper • Brass • Aluminum

expanded Metal • Structurals

Central Steel & Wire Company

CHICAGO 80, ILL. P. O. Box 5310-A REpublic 7-3000 DETROIT 12, MICH. 13400 Mt. Elliott Ave. TWinbrook 2-3200 CINCINNATI 14, OHIO Box 148 Annex Sta. AVon 2230 MILWAUKEE 14, WIS. 6623 W. Mitchell St. EVergreen 4-7400

"SERV-RITE"

Insulated Thermocouple Wire **Extension Lead Wire**

FOR

PLATINUM COUPLES CHROMEL ALUMEL IRON CONSTANTAN COPPER CONSTANTAN IRON CUPRONEL

No matter what your wire or insulation requirements may be, you can depend on Gordon "Serv-Rite" insulated wire for pyrometers—recognized as a standard of highest quality for nearly half a century. All "Serv-Rite" wire is now manufactured in the new, completely modern Gordon plant, employing up-to-date equipment and machinery, supervised and operated by skilled techniciansyour guarantee of continued precision quality. In addition to maintaining large stocks of all common types of wire, Gordon will manufacture special insulation, in long or short runs, to suit your individual needs and meet your most rigid specifications.

All Types of Insulation

Felted Asbestos

Asbestos Braid

Weatherproof Braid

Glass Braid

Polyvinyl Plastic

Nylon Braid

Stainless Steel Armored Braid

Silicone Treated

Cotton Braid

Lead Jacket



The home of "SERV-RITE"

Full Particulars on Request

CLAUD S. GORDON CO.

Manufacturers & Distributors

Thermocouple Supplies • Industrial Furnaces & Ovens Pyrometers & Controls • Metallurgical Testing Machines Dept. 16 - 3000 South Wallace St., Chicago 16, III. Dept. 16 - 2035 Hamilton Ave., Cleveland 14, Ohio


Technical Briefs

AUSTENITIC STAINLESS:

Solubility of carbon studied by NBS . . . Lower values reported.

Austenitic stainless steels, with distinctive crystal structure combine superior resistance to corrosion with ease of working. Properties and applications of these steels are considerably affected by the amount and form of carbon they contain.

A study of solubility of carbon in austenitic stainless steel containing 18 pet Cr and 10 pet Ni was recently conducted on AISI types 302 and 304 stainless steels at request of the Navy Bureau of Aeronautics.



SOLUBILITY of carbon in high purity austenitic stainless of 18 pct Cr. 10 pct Ni.

Carbon Content-With a carbon content of 0.007 pct, lowest content studied, solution was substantially complete between 1300° and 1400 F. Solubility appeared to increase approximately linearly from about 1400° to 1975 F, the maximum temperature studied, where carbon solubility was approximately 0.08 pct.

These values of solubility are appreciably lower than previously reported. The solubility curve developed at NBS indicates that type 304 ELC (extra low carbon) stainless steel can be effectively an-

IF YOU WANT MORE DATA

You may secure additional information on any item briefed in this section by using the reply card on page 69. Just indicate the subject heading and the page on which it appears. Be sure to note exactly the information wanted.

nealed at 1700°F, but that ordinary type 304 stainless should be annealed at temperatures in excess of 1900°F if the carbon is to be fully dissolved.

Limitations - The NBS study also points up limitations on the effectiveness of attempts to eliminate intergranular embrittlement of austenitic 18 pct Cr-10 pct Ni steel by reducing carbon content.

Annealing of austenitic stainless steels is often governed by the desire to obtain a completely austenitic structure-that is, a structure in which all carbon is in solution in gamma iron.

Annealing temperatures usually range between 1950° to 2000°F.

Annealing at lower temperatures, however, results in smaller grain size, which is thought to reduce susceptibility to intergranular embrittlement. Since the temperature at which all carbon is in solution increases with carbon content, it seems to follow that low-carbon steels may be annealed at lower temperatures than the higher-carbon varieties.



SPECIMEN of high purity stainless is placed in electric furnace at National Bureau of Standards during study of carbon solubility in stainless. Rods were held in furnace at 800°F for 6 weeks to precipitate carbon. ring

m he he

·s. he

ordild be xcess to be

study n the elimiment et Ni itent. nless e deausstruc-

soluually F. peranaller to reranutemis in arbon that

ealed

n the


placed olubility nace at carbon.

AGE

CRANKSHAFTS:

Fewer fixtures needed, saving in floorspace reported.


Greater precision in machining 7-ton crankshafts for Cooper-Bessemer Co.'s largest, most powerful engines is possible with this new crankpin turning lathe. Since the head of the Wickes crankpin turning lathe turns while the erankshaft remains stationary.



CRANKPIN turning lathe installed at Grove City, Pa., plant of Cooper-Bessemer has helped reduce number of jigs needed for machining big 7-ton crankshaft.

counterweighting the crankshaft is no longer required.

Fewer jigs are needed and less floor space involved in handling the turning operation. A key component for the 5000 hp engine, the crankshaft must be precision assembled to tenths of thousandths accuracy. The big lathe is installed at Cooper-Bessemer's engine building plant located at Grove City, Pa.



LOADED shells are checked for size to assure correct gun chamber fit in this big gaging unit developed by Sheffield Corp. in cooperation with Picatinny Arsenal. Unit is reported to be one of the largest gaging units ever built.


apping machines

lead

Grabler Cuts Costs and 🏽 🦚 📽 Increases Production with

TAPPERS





Famous Grabler Square G Fittings are accurately produced to high standards at high speeds on five batteries of three CLEVE-LAND Fittings Machines. One operator for each battery keeps the magazines full of rough castings... Finished tees and ells are threaded and chamfered and automatically discharged to containers.

High Production . . . Lower Costs . . . Increased Profits. CLEVE-LAND engineers can help you attain these desirable objectives. Standard CLEVELAND Tappers with the famous CLEVELAND Lead Screw Controlled Spindles perform such operations as Tapping, Threading, Chamfering, and Core Drilling...turn semiskilled workers into skilled operators. Write today for Catalog RA16.






Mr. Lead Screw says:

Cleveland Tappers have ALL the features you want, possess such advantages as quickly changed spindle speeds... Heat treated alloy spindles ... Precision depth control... Super sensitive clutch . . . Positive coolant and lubricant supply. Check with Cleveland First.



THE CLEVELAND TAPPING MACHINE CO. A Subsidiary of AUTOMATIC STEEL PRODUCTS, INC. CANTON 6, OHIO





calcined dolomite vs. dead burned dolomite

THE price of calcined dolomite approaches that of dead burned dolomite. But in terms of effectiveness as a hearth refractory, calcined dolomite has most of the shortcomings of raw dolomite. However, it lacks the effectiveness of this low priced material for routine drying of bottom.

Calcined dolomite is often called "single burned", just as dead burned dolomite is referred to as "double burned". This outdated nomenclature originated years ago when raw dolomite was first calcined (fired to a temperature high enough to drive off CO₂) and then refired at higher temperatures to obtain dense, thoroughly shrunk granules containing essentially crystalline magnesia and lime.

Calcined dolomite, with a density of 60 to 80 pounds as opposed to 120 pounds per cubic foot for dead burned dolomite, has a high porosity. It reacts rapidly with atmospheric moisture and carbon dioxide. Thus, slaking in transit and storage causes excessive fines. Fines not only pose a dust problem for furnace personnel, but when

swept through the furnace by combustion gases, result in damage to all refractories, both below and above floor level.

Lacking density and an integral coalescing agent, calcined dolomite is highly vulnerable to attack during the initial stage of the heat. Calcine thus removed increases slag volume. Magnesia from the calcine leads to viscous slags which take manganese and iron oxides into solid solution, rendering them ineffectual in their important role of refining agents.

Today few steel plants use calcined dolomite. Thus, practice proves the reasoning of science—in increasing consumption of dead burned dolomite.

A pioneer in the manufacture of dead burned dolomite, Basic Refractories Incorporated fulfills its responsibility as a supplier of this essential hearth refractory through a continuing program of product research and quality control and by anticipating, through increased and improved production facilities, the ever expanding requirements of the steel industry for Magnefer and Syndolag.



Basic Refractories Incorporated

845 HANNA BUILDING, CLEVELAND 15, OHIO

Exclusive Agents in Canada: REFRACTORIES ENGINEERING AND SUPPLIES, LTD., Hamilton and Montreal

126

THE IRON AGE

q

tl



New Capacity Strengthens Case for Early Decontrol

By end of this year industry's capacity will be about 116 million net tons . . . Total gain this year more than 7,250,000 . . . Could pour 118 million net tons during next year.

Steel companies in the United States are adding more than 7,250,000 net tons of ingot capacity this year, according to a survey just completed by THE IRON AGE. When this is added to their capacity at the beginning of this year (108.6 million tons), year-end capacity will be close to 116 million tons.

Completion of several large additional projects early in 1953 will raise the industry within reaching distance of its 120-million-ton goal established unofficially in early 1951 under the spur of defense requirements, fast tax amortization, and industry confidence in continuing civilian demand for steel.

Electric Gains Fastest—Of the 1952 expansion total, more than 6 million tons is represented by new openhearth capacity. Balance of the new capacity, over 1 million tons, is due to electric furnace expansion.

ult in

level.

, cal-

g the

eases

scous

solid

rtant

Thus,

asing

mite.

bility

ugh a

con-

roved

its of

AGE

When final figures for 1952 are in, openhearth capacity will be over 101 million tons, an increase of 6.3 pct over capacity at start of the year, and 11 pct over capacity at Jan. 1, 1951. Electric furnace capacity will be over 9 million tons, up 13.5 pct from start of the year and 24 pct over capacity at Jan. 1, 1951.

Big Gainers—Major new capacities being brought in this year include 1.2 million tons of openhearth expansion at Indiana Harbor Works of Youngstown Sheet & Tube Co.; approximately 900,000 tons by Jones & Laughlin at Pittsburgh and Cleveland; 600,000 tons by U. S. Steel at Fairless Works; approximately 800,000 tons by Bethlehem; 800,000 tons of openhearth and electric furnace capac-

ity by Republic; 504,000 tons of electric furnace capacity by Northwestern Steel & Wire Corp. at Sterling, III.; 550,000 tons of openhearth by Lone Star Steel Co., Lone Star, Tex., and 750,000 tons of new openhearth capacity by Inland Steel at Indiana Harbor. Youngstown expansion at Indiana Harbor was offset by scheduled elimination of 330,000 tons of bessemer capacity.

Geographically, over 3 million tons of new 1952 capacity is being brought into production in the Midwest, while over 2.5 million tons is scheduled for the East.

Coming Next Year — Included among capacities to be added early next year will be 1.2 million tons at the new Fairless Works of U. S. Steel in addition to the 600,000 tons scheduled to be added before the end of 1952.

Other early 1953 additions include Pittsburgh Steel, 325,000 tons due to openhearth furnace enlargements; Detroit Steel, Portsmouth Plant, New Boston, O., 750,000 tons, 4 new 250-ton openhearths; Tennessee Coal & Iron Div., Fairfield, Ala., 200,000 tons, openhearth enlargements. National Steel Corp., also will bring in new capacity next year.

Cost Is Staggering—The industry's newest expansion program involves an investment of more than \$4.5 billion on the basis of Certificates of Necessity approved by the Defense Production Administration. The certificates cover expansion in steel finishing capacity, coal and coke, ferroalloys and ores, blast furnace capacity, foundries, forges, and lake and river trans-

portation as well as steel melting expansion.

Industry investment in steel works and rolling mills alone will be over \$2.5 billion, of which 61.8 pct will be allowed fast tax amortization. Proposed blast furnace construction will involve spending of \$651 million, while another \$708 million will be spent on iron ore projects. Fast tax write-offs approximate 71.4 pct and 70 pct, respectively.

Decontrol Argument — New capacity, completed and in the offing, is a potent factor in industry arguments for decontrol of steel. A steel industry task force supported its decontrol recommendations with the following market forecast for 1953:

- The industry can produce as much as 118.8 million net tons of ingots—if needed.
- (2) No more than 14 million tons will be required for military and atomic energy uses, as now planned.
- (3) This will leave as much as 104 million tons for all other purposes—one-third more than the estimated 80 million tons which will have been available for non-defense uses during 1952.

An open-end CMP now seems likely in the near future. This would permit mills to sell to customers without tickets after specified lead time had expired. There is a good chance that all controls, except for military and atomic energy priorities, will be lifted by Apr. 1. Directives will probably be kept.


Steelmaking operations this week are scheduled at 106 pct of rated capacity, one point lower than the past several weeks. Unusually high operating rate can be expected for the remainder of the year because expansion has raised actual capacities for above official ratings.


Help


feed these


hungry mouths!

The steel industry NEEDS your scrap to help supply YOUR needs in STEEL









ROOT OUT THE SCRAP TODAY
ROUTE IT ON ITS WAY!

Superior Steel

CORPORATION

CARNEGIE. PENNSYLVANIA

Market Briefs and Bulletins

Expansion—Aluminum Ore Co., Bauxite, Ark., plans to build a new plant to manufacture finished chemical products from alumina processed from bauxite. Cost of building the new facilities is estimated at more than \$5 million. Construction schedule has not yet been determined but production from the first unit built will be ticketed for defense industries.

Auto Market—Automakers believe consumer car demand will be strong early in 1953 but some believe the market may ease considerably thereafter. As a result, they want production as high as possible early in 1953. That's why they're exerting such strong pressure on the steel market now.

Capacity Doubled—Installation of three new heat-treating furnaces has more than doubled the capacity of Kropp Forge Co., Chicago. The new furnaces have a rated capacity of more than 4000 lb per hr as compared with the 2000-lb-per-hr rate of the company's older furnaces. Installation of the units was a part of the company's \$5 million expansion program started 2 years ago.

OIT Quotas—Office of International Trade will license up to 118.875 short tons of production tinplate for export during first quarter 1953. Of this quantity, 97,500 tons must be used for foreign food packaging and 21.375 tons for petroleum and its products. OIT also set fourth quarter export quotas for corrugated aluminum sheet and scrap at a combined total of 3,800,000 lb. In addition, a special quota of 100,000 lb of aluminum scrap has been set aside for small business consumers in the Caribbean area,


Won't Happen Again—Aircraft industry has been assured there will be no sudden stoppage of military aircraft production when the Air Force goal of 143 wings is reached. Maj. Gen. William H. Tunner, deputy commander of Air Materiel Command, told the National Security Industrial Assn. that the Air Force has definite plans to prevent widespread cancellations of contracts such as followed World War II.

Tubing Allotment—Supplemental allotments of casing and tubing totaling 128,569 tons have been granted to 760 oil and gas operators for the first quarter of 1953. Total tonnage distributed in supplemental allotments is about 47,000 tons greater than was expected when primary authorizations were issued last month. Of the total, allotments amounting to 35,550 tons will be made to operators drilling less than 40 wells a month. Larger operators will get 93,019 tons.

Price Rise—Increases of 3e and 4e per lb of contained chromium are available to producers of ferrochrome, chromium metal, ferrochrome silicon, ferrosilicon chrome, and chrome manganese silicon alloys. Ceiling Price Reg. 180, effective Nov. 25, authorizes ceilings higher than those established under the General Ceiling Price Reg. Increases amount to 3e per lb of contained chromium for high-carbon products and 4e per lb for low-carbon items.

Another Contract — Wilputte Coke Oven Div., Allied Chemical & Die Corp. has been awarded a contract for construction of a battery of 76 by-product coke ovens at Youngstown Sheet & Tube Co.'s Campbell Works, Youngstown, Ohio. The new facilities will have a rated capacity of 450,000 tons per year.


STEEL OPERATIONS



District Operating Rates

Week of Week of

District	Nov. 23	Nov. 16
Pittsburgh	107.0	107.0
Chicago -	109.5	113.0
Valley	104.0	104.0
Philadelphia	100.0	100.0
West	106.5	111.0*
Buffalo	106.5	106.5
Cleveland	109.0	107.0
Detroit	106.0	106.0
Wheeling	102.0	102.0
Birmingham		
(South)	107.0	106.5
South Ohio River	93.0	90.0
St. Louis	84.0	86.5
East	95.5	92.5*
Aggregate	106.0	107.0
Beginning Jan. I,	1952, opera	ations are
based on annual 670 net tons.	capacity o	of 108,587



N AGE

Lead Price Follows London Dip

No weakness shown in U. S. market but sagging British market drags lead price down . . . Same is likely for zinc when trading resumes about the first of year—By R. L. Hatschek.

The London market is still leading U. S. lead prices around by a nose ring. About the time trading in England got to the point where foreign metal could be imported here at about "1c below the New York price a custom smelter cut back to 14.25c per lb at New York and was shortly followed by a producer who reduced the St. Louis price to 14.05c.

This was the first dip for lead during the month and it certainly wasn't caused by weakness here. True, buying had tapered off a bit, but the market still had an inherent firmness. At the end of the week London prices were even lower, equivalent to a New York price of about 13.20c. This brought the domestic price down another 1/4¢ peg with a custom smelter moving first, a producer following soon after. Both reductions caused similar drops in lead scrap prices. If this trend continues in London it's certain to continue here.

No Zinc Change—Yet—All of the action in lead has caused a slightly weaker tone to prevail in zinc but there have been no price changes—so far. The market continues quiet with the East St. Louis price at 12.50c per lb. But what will happen when zinc trading is resumed in London?

The British Ministry of Materials has indicated it won't be as

haphazard in disposing of zinc stocks as it was in the case of lead. But it still looks as though London will hook the same nose ring onto zinc prices.

Copper Costs—Office of Price Stabilization has extended current brass mill and copper wire mill ceiling prices to Mar. 1, 1953. Recalculation was made unnecessary by the unchanging nature of the Chilean copper price. The lag is accounted for by the time it takes between purchase and finished product.

In a move applicable principally to manufacturers of copper alloys and copper dust, OPS has authorized producers who use only primary copper in their products to raise prices by 3.84¢ per lb of copper contained. This action covers producers operating under the General Ceiling Price Regulation and excludes producers of copperclad and copper-coated items governed by Supplementary Reg. 100 to the GCPR.

Motor Makers—Although copper wire mill products are forecast by National Production Authority as continuing very tight in early 1953, the agency expects to hand out enough CMP tickets on copper, aluminum and steel to generator and fractional hp motor manufacturers to permit them to fill orders.

Household appliance demand for

small motors is growing. But NPA believes volume will fall off when pipelines and inventories are filled Meanwhile, supplemental allocations of wire mill products are being prepared for motor and generator manufacturers, enough perhaps to bring fourth quarter volume up to that of the third quarter.

Ingot Shipments—October shipments of brass and bronze ingots totaled 25,811 tons, according to the industry's Defense Council. This compares with 22,770 tons in the previous month and brings the 10-month total to 231,312 tons. Projecting this rate through the rest of the year brings the estimated total to about 282,000 tons, a far cry from the 332,378 tons last year.

Tin Up—Trading in prompt tin on the outside market edged \(^1\)se nearer the Reconstruction Finance Corp. price of \(^1\)121\(^1\)2 last week when the quotation rose to \(^1\)121\(^3\)se per lb. This, however, was on the basis of small lots. Meanwhile the London and Singapore markets dipped slightly with the Singapore price finishing the week at a New York equivalent of \(^1\)1.20 for March delivery.

Rockdale Starts — First aluminum pig was produced at Aluminum Co. of America's new Rockdale, Tex., reduction plant on Monday. When completed the plant's four potlines will have a smelting capacity of 85,000 tons of aluminum annually. Second line is scheduled to start up next month, with the last two being scheduled for completion during the spring.

Fo

his

th

of

the

for


Power for the first two lines will be supplied by Texas Power & Light Co. but the others will have to wait for completion of Alcoa's own lignite-burning power plant in the fall. At that time all four lines will go on the lignite diet, the first use of this fuel for powering aluminum reduction plants. The new plant will eventually employ between 1100 and 1200 workers with an annual payroll of \$4.5 million.

NONFERROUS METAL PRICES

	Nov. 19	Nov. 20	Nov. 21	Nov. 22	Nov. 24	Nov. 25
Copper, electro, Conn.	24.50	24.50	24.50	24.50	24.50	24.50
Copper. Lake delivered	24.625	24.625	24,625	24.625	24.625	24.625
Tin, Straits, New York	\$1.211/4	\$1.211/4	\$1.213/8		\$1.213/8	\$1.213/8*
Zinc, East St. Louis	12.50	12.50	12.50	12.50	12.50	12.50
Lead, St. Louis	14.30	14.05	14.05	14.05	13.80	13.80
Note: Quotations are going	ng prices.					
*Tentative.						

HIGH STRENGTH AND PRESSURE TIGHTNESS...

Water boxes produced of nickel cast iron by Kutztown Foundry & Machine Corp., for Foster Wheeler Corp., to obtain greatly improved physical and mechanical properties in these large castings.



IN CASTINGS OF LARGE DIMENSIONS

Here are three water boxes, weighing 21,500 pounds each, for a power-plant condenser system designed by Foster Wheeler Corporation, New York City.

Excessive pressures of the service involved call for high strength, as well as high density of grain structure.

Accordingly, these water boxes, produced by Kutztown Foundry & Machine Corporation, Kutztown, Pa., were cast in 2% nickel cast iron.

Meeting ASTM "Class 50" specification (minimum 50,000 psi tensile strength) and characterized by dense structure with fine dispersion of graphite throughout, this nickel cast iron provides an extraordinary degree of pressure tightness under hydrostatic pressures.

The matrix of nickel alloyed iron closely resembles the pearlitic matrix found in high-carbon steels. In contrast, the matrix of ordinary plain iron resembles that found in low-carbon steels. Throughout industry, nickel cast irons spell economy when you need strength, wear resistance and pressure tightness. Write for our suggestions regarding the best nickel alloyed iron for your specific applications.

At the present time, the bulk of the nickel produced is being diverted to defense. Through application to the appropriate authorities, nickel is obtainable for the production of engineering nickel cast irons for many end uses in defense and defense supporting industries.

	treet, New York 5, N. Y. cooklet entitled, "Guide to the
	ering Cast Irons.
Name	Title
Company	
Address	
City	State

THE INTERNATIONAL NICKEL COMPANY, INC. 67 WALL STREET, N.Y.

November 27, 1952

131

Monant's elting lumie is onth.

NPA when filled lloca-

s are

genpervol-

arter.

shipngots ag to uncil. ns in s the Proe rest nated a far year.

ot tin 1 1sc nance week .213s n the e the rkets

apore New Iarch

lumi-

lumi-

onth.
duled
oring
s will
er &
have
coa's

four t, the

The aploy rkers \$4.5

AGE

MILL PRODUCTS

(Cents per lb, unless otherwise noted)

Aluminum

Aluminum

(Hase 19,000 lb, J.o.b. ship. pt. fit. allowed)

Flat Sheet: 0.188 im., 28, 38, 31.6c; 48, 618-0, 33.6c; 528, 35.8c; 248-0, 248-0AL, 34.6c; 758-0, 758-0AL, 41.9c; 0.081 im., 28, 38, 32.8c; 48, 618-0, 35.2c; 528, 37.4c; 248-0, 248-0AL, 35.8c; 758-0, 758-0AL, 43.9c; 0.032 im., 28, 38, 34.5c; 48, 618-0, 39.0c; 528, 41.8c; 248-0, 248-0AL, 43.8c; 758-0, 758-0AL, 52.8c; 248-0, 248-0AL, 43.8c; 758-0, 758-0AL, 54.8c. Plate ½ in. and Heavier: 28-F, 33.F, 29.7c; 48-OAL, 34.0c; 758-0, 758-0AL, 40.7c. Extruded Solid Shapes: Shape factors 1 to 5, 35.5c to 77.2c; 12 to 14, 36.2c to 35.5c; 24 to 26, 38.7c to 81.2c; 36 to 38, 45.9c to 81.7g. Rod, Rolled: 1.064 to 4.5 in., 28-F, 38-F, 39.4c to 35.2c; cold-finished, 0.375 to 3 in., 28-F, 38-F, 42.5c to 36.8c. Screw Machine Stock: Rounds, 118-Ts, ½ to 11, 32 in., 56.2c to 44.1c; 3 to 1½ in., 43.6c to 41.0c; 1 9/16 to 3 in., 40.4c to 37.8c; 178-Ts, 1.6c per lb lower. Base 5000 lb.

Drawn Wire: Coiled, 6, 651 to 0.874 in., 28, 41.5c to 30.5c; 528, 50.4c to 36.8c; 568, 53.6c to 44.1c; 178-T4, 56.7c to 39.4c, 618-T1, 50.9c to 88.9c.

Extruded Tubing: Rounds, 638-T5, OD in in.: 1/4 to 2, 38.9c to 58.5c.

Extruded Tubing: Rounds, 63S-T5, OD in in.

Extruded Tubing: Rounds, 638-T5, OD in in.: 14 to 2, 38.9¢ to 56.7¢: 2 to 4, 35.2¢ to 47.8¢; 4 to 6, 35.7¢ to 43.6¢; 6 to 9, 36.2¢ to 45.7¢.

Roofing Sheet: Flat, 0.019 in. x 28 in., per sheet, 72 in., \$1.199; 96 in., \$1.595; 120 in., \$1.997; 144 in., \$2.398. 0.24 in. x 28 in., 72 in., \$1.488; 96 in., \$1.20 in., \$2.414; 144 in., \$2.897. Coiled sheet: 0.019 in. x 28 in., 29.6¢ per lb; 0.024 in. x 28 in., 29.6¢

Magnesium

Magnesium
(F.O.B. mill, freight allowed)
Sheet and Plate: FS1-O, ¼ in., 63¢; 3/16 in., 65¢; ¾ in., 67¢; B & S Gage 10, 68¢; 12, 72¢. Specification grade higher. Base: 30,000 lb.
Extruded Round Rod: M, diam in., ¼ to 0.311 in., 74¢; ¾ to ¾ in., 57.5¢; 1¼ to 1.749 in., 53¢; 2½ to 5 in., 48.5¢. Other alloys higher. Base up to ¾ in. diam, 10,000 lb; ¾ to 2 in., 20,000 lb; 2 ia. and larger, 30,000 lb.
Extruded Solid Shapes, Rectangles: M. In weight per ft, for perimeters less than size indicated, 0.10 to 0.11 lb, 3.5 in., 62.3¢; 0.22 to 0.25 lb, 5.9 in., 59.3¢; 0.50 to 0.59 lb, 8.6 in., 56.7¢; 1.8 to 2.59 lb, 19.5 in., 53.8¢; 4 to 6 lb, 28 ln., 49¢. Other alloys higher. Base, in weight per ft of shape: Up to ½ lb, 10,000 lb: ¼ to 1.80 lb, 20,000 lb; 1.80 and heavier, 30,000 lb.
Extruded Round Tubing: M, wall thickness,

30,000 lb.

Extruded Round Tubing: M. wall thickness, outside diam, in., 0.049 to 0.057; ½ in. to 5/16, \$1.40; 5/16 to ¾, \$1.26; ½ to ½, 6, 93¢; 1 to 2 in., 76¢; 0.165 to 0.219, 5% to ¾, 61¢; 1 to 2 in., 57¢; 3 to 4 in., 56¢, 0.04er alloys higher. Base, OD in in.; Up to 1½ in., 10,000 lb; 1½ in. to 3 in., 20,000 lb; 3 in. and larger, 30,000.

Titanium

(100,000 lb base, f.o.b. mill)

Commercially pure and alloy grades. Sheets and strip, HR or CR, \$15; Plate, HR, \$12; Wire, rolled and/or drawn, \$10; Bar, HR or forged, \$6; Forgings, \$6.

Nickel and Monel

(Base prices, f.o.b. mill)

and the second	3	or reserve	
	"A"	Nickel	Monel
Sheets, cold-rolled		77	60 1/4
Strip, cold-rolled .		83	63 1/2
Rods and bars		7.3	5816
Angles, hot-rolled		7.3	5816
Plates		75	5936
Seamless lubes		100	9316
Shot and blocks			531/4

Copper, Brass, Bronze

(Freight prepaid on 200 lb)

		Extruded
Sheet	Rods	Shapes
Copper 45.52		45.12
Copper, her	41.37	
Copper, drawn.	42,62	
Low brass 42.34	12.03	
Yellow brass . 40.17	39.86	
Red brass 43.10	42.79	
Naval brass 44.72	38.78	40.04
Leaded brass		38.02
Com's bronze , 44.39	44.08	00.02
Mang, bronze . 48,44		
Phoe bronze ciro	42.83	43.89
Phos. bronze . 64.72	64.97	
Muntz metal. 42.69	38.25	39.50
Ni silver, 10 pct 51.96	54.18	

PRIMARY METALS

I WINNEY INFINES
(Cents per lb, unless otherwise noted)
Aluminum ingot, 99+%, 10,000 lb, freight allowed 20,00 Aluminum pig 19,00 Antimony, American, Laredo, Tex 34,50 Beryllium copper, 3.75-4.25% Be \$1.56 Beryllium aluminum 5% Be, Dollars
per lb contained Be \$69.50 Bismuth, ton lots \$2.25 Cadmium, del'd \$2.00 Cobalt, 97-99% (per lb) \$2.40 to \$2.47 Copper, electro, Conn. Valley 24.50 Copper, Lake, delivered \$24.625
Indium, 99.8%, dollars per troy oz. \$2.25 Iridium, dollars per troy oz. \$2.20 Iridium, dollars per troy oz. \$2.00
Lead, New York Magnesium, 99.8+%, f.o.b. Freeport, Tex., 10,000 lb. Magnesium, sticks, 100 to 500 lb. 42.00 to 44.00 Magnesium, sticks, 100 to 500 lb. Magnesium, sticks, 100 to
Mercury, dollars per 76-lb. flask, fo.b. New York \$2.90 to 44.00 Nickel electro, f.o.b. N. Y. warehouse 59.58 Nickel oxide sinter, at Copper Creek, Ont., contained nickel . 52.75
Palladium, dollars per troy oz. \$24.00 Platinum, dollars per troy oz. \$90 to \$93 Silver, New York, cents per oz. 83.25 Tin, New York \$1.21% Titanium, sponge \$5.00 Zinc, East St. Louis 12.50 Zinc, New York 13.83 Zirconium copper, 50 pct \$6.20

REMELTED METALS

Brass Ingot

	Cents	per	16		de	:14	27	er	•	d	C	a	9"	70	00	70	18)
85.5	-5-5 in	Test																
No	0. 115																	27.25
1.	o. 120												*				4	26.75
	o. 123					٠												26.25
	0-10 in																	
N.	0. 305				0					0		0						33.00
No	0. 315																	30.50
	0-2 ing																	
No	0. 210								٠							0		41.50
No	o. 215																	40.00
N	0. 245											0						34.50
Yello	ow ingo	30																
No	0. 405			. ,					0								0	23.25
Man	ganese	bro	TIZE	6														
1	0. 421		4.4							k		×	+			+		30.50
		Ali	umi	in	u	m		i	10	30	+							
(Cents	per	lb.	1	00	3,0	00	0	1	b	(71	2.6	ì	(21	ne	r)
95.5	alumi	7.11.177	- 41	Fo	0	F3	0	11	0	201	2							

1130	nis	per 1		00.0				22.6	1	0	221	er)
5-5 al												
0.30	cop	per, 1	max						0			. 2
0.60	cop	per, 1	nax									. 2
iston	allo	VS (]	No.	122	tvi)e)	١.					. 2
io. 12	alu	m. (1	No.	2 gr	ade	(:						. 1
08 al												
95 al	lox											. 2
13 all	OY	(0.60	COL	per	ma	X.)					. 2
	7.0											- 9

	grandialed	U	31101				
Grade	1-95-973675						18.80
Grade	2-92-95%						18.60
Grade	3-90-92%						18.40
Grade	4-85-90%			*	6		18.20

ELECTROPLATING SUPPLIES

Anodes

(Cents per lb, freight allowed, 500 lb	lots)
Copper Cast, oval, 15 in. or longer Electrodeposited Flat rolled Forged ball anodes Brass, 80-20	37.34 33% 38.34 43
Cast, oval. 15 in. or longer Zinc, oval Ball, anodes Nickel, 99 pct plus	$\begin{array}{c} 343, \\ 2616, \\ 2516, \end{array}$
Cast Rolled, depolarized Cadmium Silver 599 fine, rolled, 100 oz lots, per troy oz, f.o.b Bridgeport,	76.00 77.00 \$2.15
Conn.	14.1 4.00
Chemicals	
(Cents per 1b, f.o.b. shipping poin	(18)
Copper cyanide, 100 lb drum Copper sulfate, 99.5 crystals, bbl Nickel salts, single or double, 4-100	12.85
lb bags, frt. allowed	2716
Nickel chloride, 375 lb drum Silver cyanide, 100 oz lots, per oz Sodium cyanide, 96 pct domestic	27 1/4 67 1/4
Zinc cyanide, 100 lb drum	$\substack{19.25\\47.7}$

SCRAP METALS

Brass Mill Scrap cents per pound, add '4e per lb for shipments of 20,000 to 40,000 lb; add 1c for more than 40,000 lb)

	4 6 1 00												
]	He	av		Tur	
Copper						٠			21	1/2		20	
Yellow	bra	201								1/8		17	
Red br	ass								20	14		19	%
Comm.	bron	nze							20	1/2		19	3/4
Mang.	bron	ze					0		18	3 1/2		17	3/4
Brass :	rod e	nds	٠	0	0	0	0		18	5 7/8			
		ston											
Cents	per							oac		ots	, d	eliv	er

Ingot Makers' Scrap Cents per pound, carload lots, delivered

to refinery	
No. 1 copper wire	19.25
No. 2 copper wire	17.75
Light copper	16.50
No. 1 composition	18.50
No. 1 comp. turnings	18.36
Rolled brass	15.50
Brass pipe	16.50
Radiators	14.75
Aluminun	
Mixed old cast	9 - 9 %
Mixed new clips	10 —11
Mixed turnings, dry	9 - 91/2
Dota and name	814 9

Dealers' Scrap Dealers' buying price, f.o.b. New York in cents per pound)

Copper and Brass

	18% 19 1/4
No. 2 heavy copper and wire.	17 -171/2
Light copper	15 1/2 16
New type shell cuttings	15 1/2 16
Auto radiators (unsweated)	14
	1732-18
	17 -17 1/2
	16 1 -17
	15 -15 1/2
	111/2-12
Old rolled brass	14 14 15
	151/2-16
	16 -16%
Brass rod ends	$15\frac{1}{2}$ -16 15 $-15\frac{1}{2}$
No. 1 brass rod turnings	10 -10 72
Aluminum	

Alum pistons and struts
Aluminum crankcasee
2S aluminum elippings
Old sheet and utensils
Borings and turnings
Misc. cast aluminum
Dural clips (24S) 7 1/2 10 1/2 7 1/4 - 6 Zinc New zinc clippings 7
Old zinc 5
Zinc routings 3
Old die cast scrap 4

6 1/9 ---

Nickel and Monel

Nickel anodes
Clean nickel turnings ... 35
Clean nickel turnings ... 35
Nickel anodes ... 35
Nickel rod ends ... 35
New Monel clippings ... 28
Clean Monel turnings ... 28
Nickel silver clippings, mixed ... 13
Nickel silver turnings, mixed ... 12

Magnesium

Miscellaneous Block tin
No. 1 pewter
No. 1 auto babbitt
Mixed common babbitt
Solder joints
Sinbor ters 55 13 1/2 — 14 17 60

Solder joints
Siphon tops
Small foundry type
Monetype
Lino, and stereotype
Electrotype
Hand picked type shells
Lino, and stereo, dross
Electro dross



Here's a Challenging Opportunity for Every Man Responsible for Tooling and Production

Your tools and dies represent an immediate opportunity to bring unit costs down to a reasonable level. A quick re-check of this vital cost zone can result in definite savings. Sometimes these savings show up in less die finishing or adjusting. Or in longer runs with less downtime for regrinding. Many times they come about through a drastic reduction in the number of tools and dies you make each year,

Actual job records in plant after plant *prove* these cost economies can be realized. A good example is the job shown above. A re-check of these dies, used to blank and form .008" thick bronze thermostat diaphragms, showed that a different steel with better wearing qualities was needed to reduce excessive downtime for regrinding. This steel, Carpenter Hampden (Oil-Wear), eliminated 11 hours of machine downtime each week and produced over a half-million *extra* diaphragms per grind!

Certainly, if other plants are finding new output and production savings by re-checking their tools and dies, you can too. First step is to use The Carpenter Matched Set Method to select the one steel best suited for your job. By so doing, you back your selection with really dependable Carpenter Matched Tool and Die Steels. Then a call to your nearest Carpenter Mill-Branch Warehouse or Distributor brings fast delivery from stock. THE CARPENTER STEEL COMPANY, 121 W. BERN ST., READING, PA.

Are You Missing These Opportunities In Your Cost Relief Zone?

- Less die finishing and adjusting
- Greater output between grinds
- · Fewer heat treating failures
- Less machine downtime

On Job After Job Carpenter Matched Tool and Die Steels Have Made Them Possible!



952

livered

Carpenter

Matched Tool and Die Steels

Export Department: The Carpenter Steel Co., Port Washington, N. Y.—"CARSTEELCO" Mill-Branch Warehouses and Distributors in Principal Cities Throughout the U. S. A. and Canada

How Much Scrap Will be Bought in '52?

It's estimated that 30 million gross tons of scrap will be bought this year. Sales loss for trade estimated at about 4.5 million tons . . . No room for inconsistent buying.

Consumers of scrap iron and steel will use an estimated 62,900,000 gross tons of home and purchased scrap this year. The scrap industry will contribute over 30 million tons of this tonnage, on the basis of the traditional ratio of 50 pct home scrap to 50 pct purchased. Last year 68,518,000 tons of purchased and home scrap was consumed.

What accounts for the downtrend is the steelmaking loss of 19 million net tons incurred during the 54-day strike. Another million tons may have been lost because the strike caused some delay in steel expansion. Converted to gross tons this loss is about 17,800,000 tons, of which the scrap industry would have supplied about 4.5 million gross tons.

From very low levels the scrap industry has helped bring mill scrap stockpiles to more than respectable proportions. To meet the steel industry's growing appetite for metallics, the scrap industry has over the past few years invested many millions of dollars in new equipment and expansion. It has spent itself into a position where demand for scrap must remain fairly constant. The scrap industry's machinery cannot be endangered.

Scrap men believe the time is at hand for consumers to regard scrap with the same respect accorded their most precious raw materials. That means purchasing policies must remain consistent. In other words scrap should not be regarded as something that's just there anytime.

In Chicago talk was circulating that steelmaking grades might slip below ceiling prices. But at presstime this had not been confirmed.

Pittsburgh—The market has settled into a year-end lull. Approaching winter appears to be worrying no one. Consumers are satisfied to maintain current ample inventories. At the same time no one is interested in forcing prices down. Despite general mill optimism nothing will be done that might tend to dry up scrap sources.

Chicago - Market here continues slow. Some worry was expressed last week over the probable future of steelmaking grades. At press time this had not been confirmed in sales at below ceiling prices. An offer of \$39.50 on No. 1 bundles and No. 1 heavy melting was reported, but was turned down. Freight absorption is now reported on nearly all grades with the exception of openhearth. Brokers indicate that their prices on cast grades are largely nominal, sales in this grade are so few. Sales reported indicated that this market was continuing to sink.

Philadelphia — Openhearth, blast furnace and low phos grades are sailing along at ceiling prices and no complaints are heard—unless the quality doesn't come up to snuff. But cast is different. A major consumer is now buying cupola cast at \$47 a gross ton, \$1 lower than previously. Offers were made to buy at \$45 and \$46 but no sales at those figures were reported. Dealers say their buying prices have not yet been reduced.

New York—Some brokers and dealers see competition tightening and perhaps cutting down the profit margin. The scrap industry is geared to handle a huge volume of scrap and seems disappointed when shipments ease. The market here can be described as fair. Scrap at the dealer level is tight and car procurement is still a nuisance. Mixed yard cast was pegged at \$42 a ton following a purchase.

St. Louis—Movement of scrap iron to this district showed some improvement the latter part of the week. But still there is only token buying by the mills—giving an order if a dealer needs one to move material. One of the mills has two furnaces down for re-

pairs, and is asking shippers to string out the dispatch of cars. The demand for cast iron grades continues slow, and consumers will buy only in truck loads, declining carloads at any price. On the other hand, there has been some demand for rail ends by the foundries.

Birmingham—Scrap market here is very dull. A little blast furnace material and openhearth scrap is moving north but no sales are reported in this district. The cast market is also very sluggish but no price changes have occurred.

Detroit — Blast furnace grades gained some strength here as mills both in the district and Pittsburgh stepped up purchases. Openhearth and electric grades are in strong demand, the latter unusually so. After struggling along on scanty inventories, mills here are beginning to gain on consumption.

Cleveland—Dealers here hope to lay down more yard scrap as mills continue to live off storage and intransit supplies. Top grades are moving but shipments generally are restricted. Good grades still command ceiling prices. Market is expected to remain quiet until well after the first of the year.

Cincinnati—Buying in this area is generally limited to basing point as consumers remain stingy on spring-board limits. Most mills are slowly depleting their inventories and aiming at year end balance. There is some indication that cast scrap and turnings might soften in the near future. Mills are willing to pay good spring-boards on scarce electric furnace and railroad scrap. Yard receipts within a 70-mile radius are slow.

Boston—The scrap trade in the New England area reports practically no change in the market for this week. The single price move occurred when a few buyers went to \$38 for mixed cupola cast, making the current quotation a range of \$37 to \$38. Steel grades are still moving freely with consumers demanding the quality they pay for.

West Coast — Market continued weak in openhearth grades up and down the coast as mills continued to work on large inventories. The cast market also continued weak.

for the purchase or sale of SCrap CONSULT OUR NEAREST OFFICE FOR THE PURCHASE AND SALE OF SCRAP LURIA BROTHERS AND COMPANY, INC. MAIN OFFICE OFFICES BIRMINGHAM, ALA. CLEVELAND, OHIO LOS ANGELES, CAL. READING, PENNA. LEBANGN, PENNA LINCOLN-LIBERTY BLDG. READING, PENNA. BOSTON, MASS. GETROIT, MICH. NEW YORK, N. Y. ST. LOUIS, MO. DETROIT (ECORSE). BUFFALO, N. Y. HOUSTON, TEXAS PITTSBURGH, PA. SAN FRANCISCO, CAL. MODENA, PENNA. PITTSBURGH, PENNA. ERIE. PERNA CHICAGO, ILLINOIS LEBANON, PENNA. PUEBLO, COLORAGO SEATTLE, WASH. LEADERS IN IRON AND STEEL SCRAP SINCE 1889

November 27, 1952

ring and low, ruck

rice. been the

manovd in also

ades mills urgh arth deafter veng to

conansit but cted. illing main f the

ea is t as ringowly ning some urnture. ringand ithin

New y no

veek. vhen

ixed quo-

Steel

with

they

nued

and ed to

cast

AGE

135

Iron and Steel SCRAP PRICE

(Maximum basing point prices, per gross ton, as set by OPS in CPR 5 and amendments.)

Switching Charge Dollars per gross ton	\$0.99 .75 .65 .75 .75	25552	26.93	28.00.015		\$6	95	.50	.78	51.	.33	.57	66 652 66 66 66
Easing Points GRADES OPS No.	Pittsburgh Johnstown Brackenridge Butler Midland Monessen Sharon	Youngstown Canton Steubenville Warren	Cleveland. Buffalo Cincinnati Middletown	Chicago Claymont Coateeville Conshohocken. Harrisburg Phoenixville.	Sparrows Pt. Bethlehem Ashland, Ky. Kokomo, Ind. Pertsmeuth, O	St. Louis	Detroit	Dufuth	Kansas City	Birmingham Alabama City Atlanta	Minnequa	Houston	Los Angeles Pittsburg, Cal. Portland, Ore San Francisco
No. 1 bundles	\$44.00 44.00 43.00 43.00 43.00 34.00 38.00 38.00 38.00 41.00	\$44.00 44.00 43.00 43.00 34.00 38.00 38.00 38.00 41.00	\$43.90 43.00 42.00 42.90 42.90 33.00 37.00 37.00 40.00	\$42.50 42.50 41.50 41.50 32.50 36.50 36.50 36.50 39.50	\$42.00 42.00 41.00 41.00 32.00 36.00 36.00 36.00 39.00	\$41.00 41.00 40.60 40.00 40.00 31.00 35.08 35.00 35.00 38.00	\$41.15 41.15 40.15 40.15 31.15 35.15 35.15 35.15 38.15	\$40.00 40.00 39.00 39.00 39.00 30.00 34.00 34.00 34.00 37.00	\$39.50 39.50 38.50 38.50 38.50 39.50 33.50 33.50 33.50 36.50	\$39.00 39.00 38.00 38.00 38.00 38.00 33.00 33.00 36.00	\$38.00 38.00 37.00 37.00 37.00 32.00 32.00 32.00 32.00 35.00	\$37.00 37.00 36.00 36.00 36.00 37.00 31.00 31.00 31.00 34.00	\$35.00 35.00 34.00 34.00 34.00 25.00 29.00 29.00 32.00
Forge crops	51.50 49.08 46.50 46.00 47.00 49.08 50.00 44.00 46.00 43.00	51.50 49.80 46.50 46.00 47.00 49.00 50.00 44.00 46.00 43.00	50,50 48.00 45,50 45,00 46,00 48,00 49,00 43,00 45,00 42,00	50.00 47.58 45.00 44.50 45.50 47.50 48.50 42.80 44.50 41.50	49.50 47.00 44.50 44.00 45.00 47.00 48.00 42.00 44.00 41.00	48.50 45.00 43.50 43.00 44.00 46.00 47.00 41.00 43.00 40.00	48.65 46.15 43.65 43.15 44.15 46.15 47.15 41.15 43.15 40.15	47.50 45.00 42.50 42.00 43.00 45.00 48.00 40.00 42.00 39.00	47.00 44.50 42.00 41.50 42.58 44.50 45.50 49.50 41.60 38.50	48.50 44.90 41.50 41.00 42.00 44.00 45.00 39.06 41.00 38.00	45.50 43.00 40.50 40.00 41.00 43.00 44.00 38.09 40.00 37.00	44.50 42.00 39.50 39.00 40.00 42.00 43.00 37.90 39.00 38.00	42.50 40.00 37.50 37.00 38.90 40.90 41.00 35.00 37.00 34.00
No. 1 RR heavy melting	48.00 48.90 51.00 52.90 54.00 53.00 48.00 51.00 51.00 58.00 51.00 40.08	46.00 48.00 51.00 52.00 54.00 53.00 48.00 51.00 51.00 56.00 51.00	45.86 47.00 50.00 51.00 56.00 47.00 50.00 48.00 50.00 39.00	44.50 46.50 49.50 50.50 51.50 48.50 49.50 47.50 56.50 38.50	44.00 48.00 49.00 50.00 51.00 46.00 49.90 47.00 49.00 56.00 38.00	43.00 45.00 48.00 49.09 51.00 50.00 45.80 48.00 48.00 48.00 48.00 37.09	43.15 45.15 48.15 49.18 51.15 50.15 45.15 48.15 48.15 48.15 55.15 48.15	42.00 44.00 47.00 48.00 50.00 49.00 44.00 47.00 45.00 47.00 54.00 47.00 38.00	41.50 43.50 46.50 47.50 49.50 48.50 48.50 46.50 53.50 46.50 35.50	41.00 43.00 46.00 47.00 49.00 48.00 48.00 46.00 46.00 53.00 46.09	40.00 42.00 45.00 46.00 48.00 47.00 42.00 45.00 45.00 52.00 34.00	39.00 41.00 44.00 45.00 47.00 48.00 41.00 42.00 44.00 51.00 44.00 33.00	37.00 39.00 42.00 43.00 45.00 44.00 39.00 42.00 42.00 42.00 42.00 31.00

Cast Scrap Ceilings

Prices set by CPR 5, OPS (F.o.b. all shipping points)

Grades			OPS	No.
Cupola cast			1	\$49.00
Charging box cast	,		. 13	47.00
Heavy breakable cast			. 3	45.00
Cast iron brake shoes .		-	. 5	41.00
Stove plate			. 6	46.00
Clean auto cast			. 1	52.00
Unstripped motor blocks				
Cast iron carwheels				
Malleable				
Drop broken mach'y cast			. 11	52.00

Celling price of clean cast iron foundry runout or prepared cupola drops is 75 pct of corresponding grade.

Under Ceiling Scrap Prices

Pittsburgh

Machine shop turnings		\$32.00
No. I machinery cast		52.00
Heavy breakable cast .		45.00
Malleable		55.00

Chicago

Low phos. forge crops	50.00	to	\$51.00
Cut struc., plate, 3 ft & less	44.50	to	45.50
Cut struc., plate, 2 ft & less	46.50	to	47.50
Cut struc., plate, 1 ft & less	47.50	to	48.50
Machine sliop turnings	30.00	to	31.50
Mixed borings, turnings	34.00	to	35.50
Shoveling turnings	34.00	to	35.50
	34.00	to	35.50
Cupola cast	43.00	to	44.00
Heavy breakable cast	10.00		41.00
Malleable	48.00	to	49.00
Stove plate	41.00	to	42.00
Clean auto cast	17.00		48.00
Charging box cast	41.00	to	43.00
Drop broken mach'y	47.00	to	48.00
Unstripped motor blocks.	35.00	to	37,00
Cast iron brake shoes	40.00	to	41.00

Philadelphia Area

Clean cast chem. borings.			
Cupola cast	46.00	to	47.00
Unstripped motor blocks.	34.00	to	36.00
Charging box cast	45.00	to	46.00

Cleveland

Cast iron	bor	ing	S				\$34.00	to	\$34.50
Stove pla	te						45.00	to	46.00
Malleable							54.00	to	55.00

Youngstown

Cast in	on bori	ngs		\$35.00	to \$35.a
---------	---------	-----	--	---------	-----------

Buffalo

No.	1	machin	nery	cast				
No.	1	cupola	cast			46.00	to	47.00

Birmingham

Shoveling turnings .				\$30.00	to	\$32.00
Cast Iron borings				30.00	to	32.00
No. 1 Cupola cast				46.00	to	47.00
Stove plate						
Charging box cast .						
Heavy breakable						
Unstripped motor bl	OC	k	9	39.00	to	40.00

New York

Brokers' Buying prices per gross to	n, on cars:
Clean cast chem. borings.\$30.00	to \$30.50
No. 1 machinery cast 47.00	
Mixed yard cast	42.00
Charging box cast 44.00	
Heavy breakable cast 44.00	
Unstripped motor blocks 34.00	to 35.00

Boston

Brokers	' Buying	prices	per	gross	ton.	on	cars
Mixed	cupola o	cast		. \$37.	00 to	\$38	8.00
	breakab						
	plate						
Unstri	pped mo	tor bl	ocks	30	00 to	3 (1.25

Detroit

Brokers'							
No. 1 co	upola c	ast .				34	8.00
Heavy b	reakab	le cas	t .	.\$43.	00 to	4	4.00
Stove p	late			. 43.	.00 to	4	4.00
Cast iro	n brak	e shoe	8	. 39.	.00 to	4	0.00

Cincinnati

NO. 1	cupota	CSTRE		0	0	0	0	0	0	0	0			¢ 10.00
Stove	plate		9			0	٥	,						46.06
Drop	broken	cast	9	0					\$5	1	. (10	to	52.00

St. Louis

Charging	box	cast				\$43.00	to	\$44.00
No. 1 cu	pola	cast				48.00	to	49.00
Heavy bi	reaka	ble o	ast			41.00	to	42.00
Unstrippe	ed m	otor	blo	ck	S.			38.00

San Francisco

No. 2 heavy	melting					e	\$31.00
No. 2 bundles					0		29,00
Machine shop							14.00
No. 1 cupola	cast	0 .	٠	0	0		44.00

Los Angeles

No. 2 heavy melting	\$21.00
No. 2 bundles	39.00
Machine shop turnings	14.00
Shoveling turnings	20.00
No. 1 cupola cast	46.00
Seattle	

No. 2 bundles No. 1 cupola cast Heavy breakable Hamilton, Ont.

No. 1 hvy. melting	 	0	\$35.50
No. 1 bundles			35,50
No. 2 bundles			
Mechanical bundles			
Mixed steel scrap			31.50
Mixed borings, turnings			32.50
Rails, remelting			35.50
Rails, rerolling			44.80
Bushelings			30.50
Bush, new fact, prep'd .			33.50
Bush, new fact, unprep'd			
Short steel turnings			
Cast scrap			50.00
.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,			

You'll enjoy smoother sailing

COLD ROLLED STEEL

99

San Fra

6.00 4.00 0.00

9.00 5.00 2.00

1.00

 $\frac{4.00}{4.00}$

1.00 9.00 4.00 0.00 6.00

9.00 3.00 5.50

5.50 5.50 5.00 3.50 1.50

2.50 5.50 4.80 0.50 2.50 2.50 0.00 under 24 inches wide and especially 12 inches and narrower.



DEPENDABLE DAN

*Please do not confuse STRIP with
"SH-RIP" which is sheet steel cut into
strip widths, in coils or otherwise.

Any Reliance "Dan" will gladly
tell you more about DSC
STRIP.

with STRIP*

Do you make stampings, tubing or formed shapes?

Then you know that smoother sailing in production depends a lot on the UNIFORMITY of the steel you feed your presses, welders and rolling machines.

When you hit rough going due to troublesome variations in thickness, temper or surface quality, use Steel Strip. It will help make your work flow more steadily from set-up to finished product.

For greater UNIFORMITY is in the nature of Steel Strip. Its making follows stricter standard practices. You benefit from more restricted tolerances.

Take thickness. In strip the leeway averages only about half of what's allowed, say, for Sheet Steel.

Temper, too, is more closely controlled. Strip rolling and heat treating combine to give you temper ranges graduated from soft to full hard—to fit your job best.

In surface quality, you normally have your choice—either bright or "satin"—and consistently so.

FOR HELPFUL ACTION CALL OUR NEAREST PLANT OR OFFICE

DETROIT STEEL

PRODUCERS OF

Coke and Coal Chemicals - Pig Iron - Ingots
Slabs - Sheet Bars - Billets - Wire Rods
Manufacturers' Wire - Merchant Wire Products
Welded Fabric - Cold Rolled Steel Strip

GENERAL OFFICES
DETROIT 9, MICHIGAN

RELIANCE STEEL DIVISION

Processors and Distributors JOB-FITTED Sheet and Strip Steel

GENERAL OFFICES — BOX 4308 — PORTER STATION, DETROIT 9, MICHIGAN PLANTS

CLEVELAND PLANT, 3344 E. 80th St., VUIcan 3-3600, Cleveland 27, O. DETROIT PLANT, 13770 Joy Road, WEbster 3-5866, Detroit 28, Mich. EASTERN PLANT, 2061 State Street, STate 7-5781, Hamden (New Haven 7), Conn. MIDWEST PLANT, 1601 South Wolcott Ave., CAnal 6-2442, Chicago 8, III.

OFFICES

COLUMBUS 12, OH10, 1373 Grandview Avo., Kingswood 9502 DAYTON, OH10, 120 W. Second Street, Michigan 0581 DETROIT 28, MICH., 13770 Joy Road, WEbster 3-5866 GRAND RAPIDS 2, MICH., 326 Keeler Bidg., Glendale 6-9569 INDIANAPOLIS 4, IND., 1509 Fletcher Trust Bidg., FRankin 2333 JACKSON 18, MICHIGAN, 801 Reynolds Bidg., Jackson 4-6189 MILWAUKEE 19, WIS., 4822 W. Center St., HI Iliop 2-1040 NEW YORK 19, N. Y., 250 West 57th St., Columbus 5-4870 ROCHESTER 4, N. Y., 5 St. Paul St., Baker 1061 ST., LOUIS 8, MO., 4378 Lindell Bivd., LUcas 4550 "TOLEDO 4, ONIO, 2114 Ohio Bidg., GArifeld 8384 WORCESTER 8, MASS., 339 Main St., Worcester 5-0686

RELIANCE Job-Fitted PRODUCTS COLD ROLLED STEEL STRIP and FLAT WIRE

Coils . . . Cut Lengths . . . All Tempers

SHEETS

COLD ROLLED...HOT ROLLED...H. R. PICKLED...LONG TERNE...GALVANIZED Standard and Production Sizes or Cut to Actual Working Dimensions

COPYRIGHT 1952 D. S. C.

Comparison of Prices

Steel prices on this page are the average of major producing areas: Pittsburgh, Youngstown.		
---	--	--

Price	advances	over	previous	week	аге	printed	in	Heavy	Type ;
	appear in								

declines appear in Italics.				
accinica appear in stavios.	Nev. 25 1952	Nov. 18 1952	Oct. 28 1952	Nov. 27 1951
Flat-Rolled Steel: (per pound)	1002		2002	
Hot-rolled sheets	3.775€	3.775€	3.775€	3.60€
Cold-rolled sheets		4.575	4.575	4.35
Galvanized sheets (10 ga)	5.075	5.075	5.075	4.80
Hot-rolled strip	8.725	3.725	3.725	3.50
Cold-rolled strip	5.20	5.20	5.20	4.75
Cold-rolled strip	3.90	3.90	3.90	3.70
Plate				7.85
Plates wrought iron		9.00	9.00	
Strains C-R strip (No. 302)	36.75†	36.75†	86.75†	36.75
Tin and Terneplate: (per base be				
Tinplate (1.50 lb.) cokes		\$8.95	\$8.95	\$8.70
Tinplate, electro (0.50 lb.)		7.65	7.65	7.40
Special coated mfg. ternes	7.75	7.75	7.75	7.50
Bars and shapes: (per pound)				
Merchant bars	3.95€	3.95€	3.95¢	8.70€
Cold finished bars	4.925	4.925	4.925	4.55
Alloy bars	4.675	4.675	4.675	4.30
Structural shapes	8.85	3.85	3.85	8.65
Stainless bars (No. 302)	31.50†	21.50†	31.50†	31.50
Wrought iron bars		10.05	10.05	9.50
Wire: (per pound)				
Bright wire	5.225€	5.225€	5.225¢	4.85€
Rails: (per 100 lb)				
Heavy rails	. \$3.775	\$3.775	\$3,775	\$3.60
Light rails	4.25	4.25	4.25	4.00
Semifinished Steel: (per net ton	Y			
Rerolling billets	. \$59.00	\$59.00	\$59.00	\$56.00
Slabs, rerolling	. 59.00	59.00	59.00	56.00
Forging billets	. 70.50	79.50	70.50	66.00
Alloy blooms, billets, slabs	. 76.00	76.00	76.00	70.00
Wire Rod and Skelp: (per poun	di			
Wire rods	4.325€	4.325€	4.325€	4.10€
Skelp	. 3.55	3.55	3.55	
		3.90	3.99	3.35
† Add 4.7 pct. to base and ex	tras.			
Composite: (per pound)				
Finished steel base price	. 4.376∉	4.376¢	4.376€	4.1316

	iov. 25	Nev. 18	Oct. 28	Nov. 27
	1952	1952	1952	1951
Pig Iron: (per gross ton) Foundry, del'd Phila. Foundry, Valley Foundry, Southern, Cin'ti Foundry, Birmingham Foundry, Chicago† Basic del'd Philadelphia Basic, Valley furnace Malleable, Chicago† Malleable, Valley Ferromanganese	55.00 58.93 51.38 55.00 59.77 54.50 55.00	\$60.69 55.00 58.93 51.38 55.00 59.77 54.50 55.00 226.25	\$60.69 55.00 58.93 51.38 55.00 59.77 54.50 55.00 55.00 226.25	\$57.97 52.50 55.58 48.88 52.50 57.09 52.00 52.50 186.25

†The switching charges for delivery to foundries in the Chicago district is \$1 per ton.

‡Average of U. S. prices quoted on Ferroalloy pages.

Composite: (per gross ton) Pig iron	\$55.26	\$55.26	\$55.26	\$62.72
Scrap: (per gross ton) No. 1 steel, Pittsburgh No. 1 steel, Phila. area No. 1 steel, Chicago No. 1 bundles, Detroit Low phos., Youngstown No. 1 cast, Pittsburgh No. 1 cast, Philadelphia No. 1 cast, Chicago	41.50° 41.50° 41.15°	\$43.00* 41.50* 41.50* 41.15* 46.50* 49.00† 47.50 43.50	\$43.00* 41.50* 41.50* 41.16* 46.50* 49.00† 47.50 44.50	\$43.00° 41.50° 41.60° 41.15° 46.50° 49.00† 49.00†

* Basing pt., less broker's fee. † Shipping pt., less broker's fee.

Composite: (per gross ton) No. 1 heavy melting scrap \$42.00	\$42.00	\$42.00	\$42.00
Coke, Connellaville: (per net ton at ov Furnace coke, prompt \$14.75 Foundry coke, prompt 17.75	\$14.75	\$14.75 17.75	\$14.75 17.75
Nonferrous Metals: (cents per pound to	large buyer	ra)	
Copper, electrolytic, Conn 24.50 Copper, Lake, Conn 24.625		24.50 24.625	24.50 24.625
Tin, Straits, New York \$1.215 Zinc, East St. Louis 12.50		\$1.211/8	\$1.03 19.50
Lead, St. Louis	14.30	13.30	18.80 19.00
Aluminum virgin ingot 20.00 Nickel, electrolytic 59.58	20.00 59.58	$\frac{20.00}{59.58}$	59.58
Magnesium, ingot 24.50	24.50	24.50	24.50

† Tentative.

Composite Price Notes

Finished Steel Composite

Weighted index based on steel bars, shapes, plates, wire, rails, black pipe, hot and cold-rolled sheets and strips, representing major portion of finished steel shipment. Index recapitulated in Aug. 28, 1941, issue and in May 12, 1949.

Starting with the issue of May 12, 1949, the weighted finished steel composite was revised for the years 1941 to date. The weights used are based on the average product shipments for the 7 years 1937 to 1949 inclusive and 1946 to 1948 inclusive. The use of quarterly figures has been eliminated because it was too sensitive. (See p. 139 of May 12, 1949, issue.)

Pig Iron Composite

Based on averages for basic iron at Valley furnaces and foundry iron at Chicago, Philadelphia, Buffalo, Valley and Birmingham.

Scrap Steel Composite

Average of No. 1 heavy melting steel scrap delivered to consumers at Pittsburgh, Philadelphia and Chicago.

Warehouse Price Notes

Base Quantities (Standard unless otherwise keyed): Cold finished bars; 2000 lb or over Alloy bars; 1000 to 1999 lb. All others; 2000 to 3999 lb. All HR products may be combined for quantity. All galvanized sheets may be combined for quantity. CR sheets may not be combined with each other or with galvanized sheets, for quantity.

Exceptions: (1)500 to 1499 lb, (9)1500 to 8499 lb, (9)6000 lb or ever, (4)450 to 1499 lb.

WARE-	_									Base	price, f.e	.b., doll	ars per 1	00 Њ.
HOUSES		Sheets			Strip		Plates	Shapes	Bars		Alloy Bars			
Cities City Delivery	Het-Relled		Cold-Rolled (15 gage)	Galvanized (10 gage)	Het-Relled	Celd-Relied		Standard	Hot-Relied	Cold- Finished	Het-Relied A 4615 As relied	Het-Relied A 4140 Annealed	Celd-Drawn A 4615 As relied	Celd-Drawn A 4140
Baltimore\$.2	0 5.8	manage of the	7.17	8.42-	6.42		6.30-	6.47	6.41	7.18-				*****
Birmingham	5 5.1	01	6.65	8.57 7.701	5.80		6.47	5.95- 6.71	6.71 5.80	7.43 8.25- 8.40				
Boston			7.35-	8.59-	6.55	8.503	6.75-	6.56-	6.38-	7.63	10.78	11.15-		13.18
Buffalo	5.1	76-	7.52 6.60- 6.65 6.65	8.63 8.40- 8.41 8.00	6.16- 6.21 5.83-	6.19	6.80 6.26- 6.37 5.95-	6.75 5.96- 6.08 5.95-	6.54 5.76- 5.90 5.83	6.00- 6.95 6.56-	10.70	11.18 11.00- 11.07 10.65	12.70	12.51 14.42 12.65
Cincago	5.1	80-		5.00	5.84		6.00	6.98		6.92				
Cineinnati	15 6.	13	6.72	8.47	6.14		6.47	6.42	6.13	7.16		11.07		13.07
Cleveland	20 5.	80- 81	6.65	8.14	6.00- 6.01		6.12-		5.89	6.66- 6.90		10.79		12.79
Denver	7.	17			7.43-7.69	8.90	7.37	7.50-	7.61-7.71	8.24				
Detreit		00- 07	6.81- 6.92	8.64	6.13	7.99	6.45			6.975- 7.21	10.72	10.92	12.72	13.02
Heusten	20 6.	74- 79	7.78-7.79	8.68	6.61-6.75	9.80	6.63		6.82-	9.00-	11.90	11.90		13.90
Indianapolis. del											.,,,,,,			
Kansas City	20 6.	47	7.31	8.50- 8.72	6.51	8.07	6.62	6.62	6.58	7.57	11.15-	11.45-	13.13-	13.43
Los Angeles	20 6.	60	8.45-	9.65	6.75-	9.15	6.66	6.60-	6.60-	8.36-		12.05		14.60
Memphis	10 6.	56			6.60		6.71	6.71	6.57-	7.98-				
Milwaukee		97-	6.82	8.17	6.00-		6.12	6.12	6.00	6.83-		10.82		12.82
New Orleans		98 28	7.12		6.32			6.43	6.31	7.85				
New York		26-	7.27-7.60	8.31 ² 8.42	6.56-	9.53	6.60	6.39-	6.59	7.53-7.73	10.74-	11.04-	12.74-	13.0
Nerfolk		10	7.00	0.76	6.81		6.64		6.44	8.45	10.30			
Philadelphia		11-	7.13-	8.30-	6.45		6.24			7.45-	10.57-	10.79	12.74	12.7
Pittsburgh	20 5.	38	7.92	8.79	7.45 5.94		6.86		6.68 5.83	6.66	10.74	10.65		12.6
Portland	20 7.	60-	9.07-	8.45	7.60		7.30	7.30	7.35	6.90 9.45				35333
Salt Lake City		85	9.45	10.904	7.65 8.45		7.85	8.00	8.40					
San Francisco	15 6.	90	8.20	10.00-	6.90	9.25			6.70	8.40	-	12.05		14.6
Seattle		.16-	8.23-	9.80-	7.39		. 7.04	6.75			-	11.70		13.7
St. Louis	20 6	. 10-	8.83		7.69 6.14	9.73		6.35	6.13		10.65	10.95	12.65	12.9
St. Paul		. 30	7.83	8.39	6.50	1	6.6		6.33	7.32	1			1

HIGH SIGN FOR STEEL PIPE


The increasing amount of standard steel pipe being used to support TV antennae is another sign of the ever-growing demand for steel in the West.

Much of the pipe used for these supports is Kaiser Steel continuous weld pipe which assures great safety and strength. It's one of a diversified line of steel products produced by Kaiser Steel to provide a nearby, dependable source to help meet the West's many needs.

It's good business to do business with



built to serve the West



PROMPT, DEPENDABLE DELIVERY AT COMPETITIVE PRICES • plates • continuous weld pipe • electric weld pipe • tin plate • hot rolled strip • hot rolled sheet alloy bars • carbon bars • structural shapes • cold rolled strip • special bar sections • semi-finished steels • pig iron • coke oven by-products For details and specifications, write: KAISER STEEL CORPORATION, LOS ANGELES, OAKLAND, SEATTLE, PORTLAND, HOUSTON, TULSA, NEW YORK

November 27, 1952

18

. 82

.04-

,	RON AGE		Plante 13	entify produc	ers nated in	key at end of	tarde_ tares	,						
	JEETE	ING	OTS	BILLE	SLABS	DOMS,	PIPE SKELP	PIL- ING	SHA		STRIP			
•	IIICES	Carbon Forgong Net Ton	Alloy Net Ton	Carbon Rerolling Net Ton	Carbon Forging Net Ton	Alloy Net Ton		Sheet Steel	Carbon	Hi Str Low Alloy	Hot rolled	Cold- rulled	Hi Str. H.R. Line Alloy	Hi Str. CR Lov Allay
	Bethiehem, Pa					\$76.00 B3			3.90 B3	5 80 B3				
	Buffalo, N. Y.			59.00 R3	\$70.50 b3 R3	\$76.00 B3.		1.675 B3	3.90 B3	5.80 B	3 725 B3. R3	5.10 B3	5.70 B3	7 90 B3
	Claymont, Del.													
	Coatesville, Pa.													
	Conshohocken, Pa.				\$77.50 42	\$83.00 .42					4.125 .42		5.90 42	
	Harrisburg, Pa.													
	Hartford, Conn.													
10	Johnstown, Pa.			\$59.00 B3	\$70.50 B3	\$76.00 B3			3.90 B3	5.80 B3	3.725 B			
EASI	Newark, N. J.													
_	New Haven, Conn.											5.60 A5 5.85 D1		
	Phoenixville, Pa.								6.10 P2					
	Putnam, Conn.					-								
	Sparrows Pt., Md.								-		3.725 B3	5.10 B3	5.70 B3	7.90 B3
	Worcester, Mass.													
	Trenton, N. J.											6.45 R4		
	Alton, III.										4.20 <i>L.</i> /			
	Ashland, Ky.										3.725 A7			
	Canton-Massilen, Ohio				\$70.50 R3	\$76.00 R3 \$78.60 T5								
	Chicage, Sterling, III.			\$59.00 U1	\$70.50 U1, R3,W8	\$76.00 U1. R3,W8		4.675 U1	3.85 UI, W8	5.80 U1	3.725 A1, W8 4.725 N4	5.35 A1		
	Cleveland, Ohio				\$70.50 R3							5.10 A5,J3		7.45 /3
	Detroit, Mich.	\$56.00 R5	\$57.00 R5		\$73.50 R5	\$79.00 R5					4.025 G3 4.40 M2	5.30 G3 5.45 M2 5.60 D7 6.05 D2	6.30 G3	8.15 G3
	Duluth, Minn.						-					0.00 278		
WEST	Gary, Ind. Harbor Indiana			\$59.00 (//	\$70.50 U1	\$76.00 U1.		4.675 13	3.85 <i>I</i> 3	5.80 /3, U/ 6.30 Y/	3.725 <i>[3,</i> <i>Ul, Yl</i>	5.35 /3	5.65 <i>I</i> 3, <i>UI</i> 6.15 <i>YI</i>	
· A	Granite City, III.								-	0.50 7 7			0.10 11	
DDLE	Kokomo, Ind.	_						-	-					
ME	Middletown, Ohio						-		-			5.10 .47		-
	Niles, Ohio										4.225 S/	5.70 T4	5.65 5/	7.30 SI
	Sharen, Pa.											5.80 SI		
	Pittsburgh, Pa. Midland, Pa.	\$54.00 (//	\$57.00 U1, C11	\$59.00 U1,	\$70.50 U1.	\$76.00 U1, C11	3.55 U/ 3.65 J3	4.675 UI	3.85 U1,J3	5.80 U1.J3	3.725 J 3, 47 3.975 A 3 4.225 S7, S9	5.10 J 3, A7 5.45 A 3 5.80 B 4, S7		
	Portsmouth, Ohio													
	Weirton Wheelling. Follansbee, W. Va.								4 10 W3		3.825 W3	5.10 W3	6.10 W3	7.95 11/3
	Youngstown, Ohio					\$76.00 Y1, C10	3.55 U/ R3			6.30 Y1	3.725 UI. YI,R3	5.10 R3, Y/ 5.70 C5 5.80 B4	5.65 R3, UI 6.15 YI	7.30 R3 7.80 Y/
- politica	Fentana, Cal.	\$81.00 K7	\$83,00 K7	\$78.00 K1	\$89.50 K1	\$95.00 K/			4.45 K1	6 40 K/	4.975 K/	6.75 K!	6 55 K1	
	Geneva, Utah			-	\$70.59 C7				3.85 C7	5.80 C7			-	
	Kansas City Mo.			1					4.45 S2		4.325 S2			
WEST	Los Angeles Torrance, Cal.				\$89.50 B2	\$96.00 B2			4.45 C7,B2	6.35 B2	4.475 C7.B2	6.85 C1	6.40 B2	
	Minnequa, Colo.								4.30 C6		4,775 C6			
	San Francisco Niles, Pittsburg, Cal				\$89.50 B2				4.40 <i>B2</i> 4.56 <i>P</i> 9	6.30 B2	4.475 C7,B2		6 40 B2	
_	Seattle, Wash.				\$89.50 B2				4.50 B2	6.40 B2	4.725 B2		6.65 B2	
H	Atlanta, Ga			-							4 275 A8			
SOUTH	Birmingham Ala. Alabama City, Ala. Houston, Texas			\$59.00 72					3.85 T2,R	5.80 72	3.725 T2.R			

SHEETS WIRE ROD TINPLATE PLATE													STEEL
Flot-rolled 18 ga. & hvyr.	Cold- rolled	Galvanized 10 ga.	Enameling 12 ga.	Long Terne 10 ga.	Hi Str. Low Alloy H.R.	Hi Str. Low Alloy C.R.	Hi Str. Low Allay Galv,	Hot- rolled 19 ga.		Cokes* 1.25 lb. base box	Electro* 0.25 lb. base box	Hollowere Frameling 29 ga.	
													Be hiehem, Pa.
3.775 B3	4.575 B3				5.675 B3	6.925 B3							Buffalo, N. Y.
	-	-			-					† Special o			Claymont, Del.
										1.25-lh coke	base box		Costesville, Pa
4.175 .42					5.925 A2					blackplate :			Conshohocken, Pa.
										deduct \$2.20 from 1.25-lb coke base box * COKES: 1.50-lb			Harrisburg, Pa
										add 25e.	1: 0:50-lb add		Hartford, Conn.
									4.325 B3	25e; 0.75-16			Johnstown, Pa
													Newark, N. J.
													New Haven, Conn.
													Phoeniaville, Pa
							-		-				Putnam, Conn
3.775 B3	4.575 B3	5.075 B3	_		5.675 B3	6.925 B3	7.775 B3		4.425 B3	\$3.80 R3	\$7.50 B3		Sparrows Pt., Md.
	-								4.625 45				Worcester, Mass.
									4.425 R#				Alton, III.
3.775 A7		5.075 A7	1 025 47						4.70 L1				Ashland, Ky.
3.113.74	-	5.075 R3	4.525 AZ		-	-							Canton-Massillon
3.775 W8					5 675 UI				4.325 A5.				Chicago,
									N4,R3				Sterling, III
3.775 <i>R3</i> , <i>J</i> 3	4.575 R3, J3		4.925 R3		5.675 R3. J3	6.925 R3, J3			4.325 Ai				Cleveland, Ohio
3.975 G3	4.775 G3				6.225 G3	7.475 G3							Detroit, Mich.
					-			-					Duluth, Minn.
3.775 <i>B</i> , <i>UI</i> , <i>YI</i>	4.575 <i>13</i> , <i>UI</i> , <i>YI</i>	\$.075 <i>13</i> , <i>UI</i>	4.925 U/	5.475 UI	5.675 13, UI 6.175 YI	6.925 13, U/ 7.425 Y/			4.325 Y/	\$8.70 U/. 13, Y/	\$7.40 U1. 13	6.10 UI, YI	Gary, Ind. Harbor, Indiana
4.30 G2	5.275 G2	5.50 G2	5.625 G2								\$7.60 C.2	6.30 G2	Granite City, III.
		5.475 C9											Kokomo, Ind
	4.575 A7		4.925 .47	5.475 A7									Middletown, Ohio
4.175 S/					5.675 <i>S1</i>						\$7.40 R3		Niles, Ohio Sharon, Pa.
3.77 5 U1, J3,A7 3.925 A3	4.575 U1, J3,A7	5.075 UI	4.925 UT		5.675 U1. J3	6.925 U1. J3	7.625 UI		4.325 A5 4.525 P6	\$8.70 UI.	\$7.40 U1, J3	6.10 U/	Pittsburgh, Pa. Midland, Pa.
									4.525 P7				Portsmouth, Ohio
3.775 W'3, W5	4.575 W3, W5	5.075 W3, W5		5.475 W3, W5	6.625 W3	7.275 W3				\$8.70 W s.	\$7.40 16 5	6.35 H/5	Weirton, Wheeling, Follansbee, W. Va
3.775 UI, R3, YI	4.575 R3, Y1	5.775 R/	4.925 Y/	6.05 E2	5.675 R3, UI 6.175 YI	6.925 R3 7.425 Y1		5.65 <i>E2</i> 5.825 <i>R1</i>	4 325 Y/	\$8.70 R3			Youngstown, Ohio
4.725 K1	5.525 K1			-		7.875 K/			5.125 K!				Fontana, Cal.
3.875 C7													Geneva, Utah
													Kansas City, Mo.
4.475 C7		5.825 C7						5.575 C7	5.125 C7.B2	?			Los Angeles, Torrance, Cal.
	-								4.575 C6				Minnequa, Colo.
1.475 C7	5.525 C7	5.825 C7							4.975 C7	\$9.45 C7	\$8:15 C7		San Francisco, Nile Pittsburg, Cal.
													Seattle, Wash.
													Atlanta, Ga.
.575 T2. R3	4.575 T2	5.075 T2. R3			5.675 T2			4.925 Ri	4.325 T2 R3	\$3.80 72	\$7.50 72		Birmingham, Ala Alabama City Ala
	-								4.725 52				Houston, Tex

B3

B3

*f*3

SI

113

				producers listed								
	STEEL PRICES			BA	RS				PLA	TES		WIRE
•		Carbon Steel	Reinforcing	Cold Finished	Alloy Hot- rolled	Alloy Cold Drawn	Hi Str. H.R. Low Alloy	Carbon Steel	Floor Plate	Alloy	Hi Str. Low Alloy	Mfgr's. Bright
	Bethlehem, Pa.				4.675 B3	6.00 B3	5 925 B3					
	Buffalo, N. Y.	3.95 B3,R3	3.95 B3,R3	4.975 B5	4.675 B3,R3	6.00 83,85	5.925 B3	3.90 B3			5.95 B3	-
	Claymont, Del.							4.35 C4		5.35 C4		
	Coatesville, Pa.							4.35 L4	-	5.75 L4		
	Conshocken, Pa.							4.35 A2	4.95 .42		6.20 42	-
	Harrisburg, Pa.	-						6.50 C3	6.50 C3			
	Hartford, Conn.			5.475 R3		6.45 R3						
AST	Johnstown, Pa.	3.95 B3	3.95 B3		4.675 B3		5 925 B3	3.90 B3	1	5.25 B3	5.95 B3	5.225 B3
ML.	Newark, N. J.			5.375 W10		6.35 W10					-	
	New Haven, Conn.											
	Phoenizville, Pa.			-								
	Putnam, Conn.			5.475 W/0								
	Sparrows Pt. Md.		3.95 B3					3.90 B3		5.25 B3	5.95 B3	5.325 B3
	Worcester, Mass.					6.35 ,45						5.525 A5
	Trenton, N. J.											
	Alton, III.	4.50 L/										5.45 L1
	Ashland, Ky.							3.90 A7				
	Canton-Massillon	3.95 R3		4.925 R2,R3	4.675 R3 4.72 T5	5.99 T5 6.00 R2, R3						
	Chicage, Sterling, III,	3.95 U.W8, R3 4.55 N4	3.95 R3 4.70 N4	4. 925 A5, B5, W8, W10	4.675 R3, U1, W8	6.00 B5,L2, R3,W8,W10 6.05 A5		3.90 UI,W8	4.95 UT	5.25 UI	5.95 U1	5.225 A3, N4, R3 5.325 K2 5.475W7
	Cleveland, Ohio	3.95 R3	3.95 R3	4.925 A5,C13		6.00 C13 6.05 A5	5.925 R3	3.90 R3,J3	4.95 /3		5.95 R3, J3	5.225 A5, C13.R3
	Detroit, Mich.	4.10 <i>R5</i> 4.30 <i>G3</i>		5.075 <i>R5,P8</i> 5.175 <i>P3</i>	4.825 <i>R5</i> 5.025 <i>G3</i>	6.15 R5,P8 6.20 P3	6.675 G3	4.45 G3			6.90 G3	
les.	Duluth, Minn.											5.252 .45
VES		205 12 111	205 12 111		4 675 12 111	C 00 12 145	c noc 12 111	200 12 111	405 12	F 25 111	E 0.5 12 111	5.325 M+
W	Gary, Ind. Harbor, Indiana	3.95 <i>13, U1,</i> <i>Y1</i>	3.95 /3. U1, Y1	4.925 L2, M5, R3	4.675 13, U1, Y1	6.90 LZ.M), R3,R5	5.925 <i>13. U1.</i> 6.425 <i>Y1</i>	3.90 /3, U/, Y/	4.95 /3	5.25 U/	5.95 <i>13, U1</i> 6.45 <i>Y1</i>	5.325 144
IDI	Granite City, III.							4.60 G2		-		
-	Kokomo, Ind.		-				-					5.325 C9
w	Middletown, Ohio											
	Niles, Ohio Sharon, Pa							4.15 S/		5.70 St	5.95 SI	
	Pittsburgh, Pa. Midland, Pa.	3.95 U1,J3	3.95 U1, J3	4.925 A5.J3, W10,R3,C8	4.675 U1, J3, C11	6.00 C8,C11, W10, 6.05 A5	5.925 U1,J3,	3.90 U1, J3	4.95 U1, J3	5.25 U1.J3	5.95 U1, J3	5.225 45. J3 5.475 P6
	Portsmouth, Ohio											5.623 P7
	Weirton, Wheeling,	4.10 W3						3.90 W5				
	Follansbee, W. Va. Youngstown, Ohio	3.95 U1, Y1,	3.95 U1, Y1,	4.925 Y/		6.00 C10, Y1	5.925 UI	4.20 W3 3.90 U1, Y1,			5.95 R3	5.225 Y/
		R3	R3		YI		6.425 Y/	R3			6.45 Y/	
	Fontana, Cal.	4.65 K1	4.65 K/		5.725 K1		6.975 K1	4.50 K1		6.20 K/	6.55 K1	
	Geneva, Utah							3.90 C7			5.95 C7	
	Kansas City, Mo.	4.55 52	1.55 52		5.275 52							5.825 51
WEST	Los Angeles, Torrance, Cal.	4.65 C7,B2	4.65 C7,B2	6.375 R3	5.725 <i>B2</i>		6.625 B2					6.175 C7,B
	Minnequa, Colo.	4.40 C6	4.75 C6					4.70 C6				5.475 C6
	San Francisco, Niles, Pittsburg, Cal	4.65 C7,P9 4.70 B2	4.65 C7.P9 4.70 B2				6.675 B2					6.175 C6,C
	Seattle, Wash.	4.70 B2	4.70 B2				6.675 B2	4.80 B2			6.85 B2	
-	Atlanta, Ga.	4.50 .48	4.50 .48									5.475 A8
HIDO	Birmingham, Ala. Alabama City, Ala.	3.95 T2.R3	3.95 T2,R3				5.925 T2	3.90 T2,R3			5.95 T2	5.225 T2, R3
1	Houston, Texas	4.35 S2	4.35 52		5.075 S2			4.30 S2			-	5.625 52

IN VAPOR DEGREASING

IRE

B3

B3

LI

45

M4

6 (9

5.45.

5 P6

5 P7

5 Y/

5 51

5 C6

5 C6,C7

75 .48

25 TZ.

25 52

952

5 C7.B

WHEN SO MUCH



DEPENDS ON A QUALITY SOLVENT

IT PAYS TO SPECIFY

SPEEDY, DEPENDABLE...



"TRICLENE" D Trichlorethylene is the result of over 20 years of research and practical experience in the degreasing field. Made under carefully controlled conditions by the pioneer manufacturer of degreasing solvents in the U. S., each shipment of "Triclene" D is carefully pretested for stability and purity... must meet test standards higher than those established by military and federal specifications (MIL-7003 and O-T-634). Yet "Triclene" D costs no more than other leading brands of degreasing solvents.

"Triclene" D is available nationally in 55 gallon drums and tank cars of various sizes. Distribution points in over 100 principal cities are ready to serve you with prompt deliveries. And trained Du Pont technical representatives with broad experience in the field will be happy to work closely with you in keeping your degreasing installations operating at peak efficiency.

E. I. du Pont de Nemours & Co. (Inc.), Electrochemicals Dept., Wilmington 98, Delaware.

Send for your copy of "Vapor Degreasing with Du Pont Non-Flammable Solvents." It shows you how and where "Triclene" D can be used to save time and cut costs in metal cleaning.





150% Anniversary

BETTER THINGS FOR BETTER LIVING . . . THROUGH CHEMISTRY

E. I. du Pont de Nemours & Co. (Inc.)

Electrochemicals Dept., Wilmington 98, Delaware

Please send me detailed information on Vapor Degreasing: applications, advantages, equipment used . . . and more facts on Du Pont "Triclene" D. We are interested in cleaning ____products.

Name ______Position _____

Firm _____

Street & No. ______

November 27, 1952

143



In instances where more than one draw is required to produce the part, a stack of two or three blanks can often be preformed at one time.



In some applications the Hydroform can be tooled to pierce and trim materials during the forming operation. Blanking intricate shapes from very thin materials is possible.



Edging, or sharpening the radius between the flange and the wall of the part, is easily done on the Hydroform. Hydroform edging produces the same effect as restriking in a conventional die.

Cover of 0.064" 2SO Aluminum. Hydroformed in 2 operations.





Strainer of 20 gage perforated cold rolled steel. Hydroformed in 1 operation.





Cap of 3/8" cold rolled steel. Hydroformed in 1 operation.

Here's what you can do by Hore's what you ca



HOLD CLOSE TOLERANCE

Close tolerances can be held by Hydroforming. The part at left is a diaphragm, shown before and after trimming. The two parts, of 0.010" stainless steel, were produced to mate with an air-tight fit. Part height can be held within ±0.005" tolerance.



CAMBIMIST

Parts consisting of two or three different materials can be drawn simply by placing blanks together. Cut-away view shows a part formed by placing a blank of aluminum between two blanks of cold rolled steel. Angle assembly of 0.075" Aluminum. Hydroformed in 1 operation.



Aircraft detail of 0.040" Aluminum. Hydroformed in 1 operation.



Cover of 0.032" Aluminum. Hydroformed in 1 operation.



Vessel of ¼" cold rolled steel Hydroformed in 1 operation.

PRODUCE DEEP DRAWN PARTS WITH VERY FEW LIMITATIONS AS TO SHAPE

Hydroforming has revolutionized deep drawing. The parts and forming operations illustrated on the opposite page show the extreme versatility of this process. Note the wide variations in part shape. Note, too, that Hydroforming is *not* confined simply to the production of round or symmetrical parts.

WORK WITH A WIDE RANGE OF MATERIALS

Parts can be Hydroformed of steel, aluminum, magnesium, copper, aluminized steel, brass, plastics, insulating materials and precious metals. High-strength alloys successfully Hydroformed include titanium, Inconel, Nimonic 75, L-605, stainless steels, stainless-clad copper.


Blank thickness can range from foils to $\frac{3}{8}$ " mild steel. Blanks ranging up to 32" maximum diameter can be drawn in standard machines. Larger equipment available on application.

There are several basic shapes that cannot be practically Hydroformed. It is not practical to form sharp, pointed conical shapes (Fig. A). Straightwalled cup shapes having a depth to diameter ratio of $2\frac{1}{2}$ or more to 1 are not practical to form (Fig. B). Parts similar to shell casings which have a relatively thin wall as compared to a thicker closed end cannot be Hydroformed (Fig. C). Bulged parts having a small opening are impractical to form. Parts of this type with a large opening can be made using a segmented punch for removal after forming (Fig. D).



With the few exceptions noted above, practically any shape can be Hydroformed. In addition, Hydroforming brings to industry many other benefits affecting the time and cost of producing deep drawn parts. Only simple, low-cost tooling is required. Most parts are produced in a single draw. Part quality is materially improved. Surface finish is unimpaired.

Investigate Hydroforming now. It will change your thinking on deep drawing and forming. Let a Cincinnati Milling Machine Co. field engineer give you detailed information on how Hydroforming can be profitably applied to your production.






Write for your copy of Hydroform Bulletin M-1759



THE CINCINNATI MILLING MACHINE CO.



Key to Steel Producers

With Principal Offices

- Acme Steel Co., Chicago
- Alan Wood Steel Co., Conshohocken, Pa.
- 43 Allegheny Ludlum Steel Corp., Pittsburgh
- American Cladmetals Co., Carnegie, Pa.
- American Steel & Wire Div., Cleveland
- 46 Angell Nail & Chaplet Co., Cleveland
- Armco Steel Corp., Middletown, O. Atlantic Steel Co., Atlanta, Ga. 47
- Babcock & Wilcox Tube Co., Beaver Falls, Pa.
- Bethlehem Pacific Coast Steel Corp., San Francisco
- R3 Bethlehem Steel Co., Bethlehem, Pa.
- FL# Blair Strip Steel Co., New Castle, Pa.
- Bliss & Laughlin Inc., Harvey, Ill.
- Calstrip Steel Corp., Los Angeles Carpenter Steel Co., Reading, Pa.
- Ci Central Iron & Steel Co., Harrisburg, Pa
- Claymont Products Dept., Claymont, Del. Cold Metal Products Co., Youngstown
- Colorado Fuel & Iron Corp., Denver
- C7
- Columbia-Geneva Steel Div., San Francisco Columbia Steel & Shafting Co., Pittsburgh
- C9 Continental Steel Corp., Kokomo, Ind.
- C10 Copperweld Steel Co., Glassport, Pa.
- Crucible Steel Co. of America, New York
- C12 Cumberland Steel Co., Cumberland, Md.
- C13 Cuyahoga Steel & Wire Co., Cleveland
- Detroit Steel Corp., Detroit
- D2 Detroit Tube & Steel Div., Detroit
- Driver Harris Co., Harrison, N. J. D3
- Eastern Stainless Steel Corp., Baltimore
- Empire Steel Co., Mansfield, O.
- Firth Sterling Inc., McKeesport, Pa.
- Fitzsimmons Steel Corp., Youngstown
- Follansbee Steel Corp., Follansbee, W. Va. F3
- Globe Iron Co., Jackson, O.
- Granite City Steel Co., Granite City, Ill. 6.2
- G3 Great Lakes Steel Corp., Detroit
- HI Hanna Furnace Corp., Detroit
- Ingersoll Steel Div., Chicago
- Inland Steel Co., Chicago
- 14 Interlake Iron Corp., Cleveland
- Jackson Iron & Steel Co., Jackson, O.
- 12
- Jessop Steel Corp., Washington, Pa. Jones & Laughlin Steel Corp., Pittsburgh
- Joslyn Mfg. & Supply Co., Chicago
- Kaiser Steel Corp., Fontana, Cal.
- Keystone Steel & Wire Co., Peoria K3 Koppers Co., Granire City, Iil.
- Laclede Steel Co., St. Louis
- 1.2 La Salle Steel Co., Chicag
- 1.3 Lone Star Steel Co., Dallas Lukens Steel Co., Coatesville, Pa.
- Mahoning Valley Steel Co., Niles, O. McLouth Steel Corp., Detroit
- Mercer Tube & Mfg. Co., Sharon, Pa. M3
- Mid-States Steel & Wire Co., Crawfordsville, Ind. Monarch Steel Co., Inc., Hammond, Ind. 14
- M6 Mystic Iron Works, Everett, Mass.
- National Supply Co., Pittsburgh
- N2 National Tube Co., Pittsburgh N3 Niles Rolling Mills Co., Niles, O.

AGE

- N4 Northwestern Steel & Wire Co., Sterling, III
- Oliver Iron & Steel Co., Pittsburgh
- Page Steel & Wire Div., Monessen, Pa.
- Phoenix Iron & Steel Co., Phoenixville, Pa.
- Pilgrim Drawn Steel Div., Plymouth, Mich.
- Pittsburgh Coke & Chemical Co., Pittsburgh
 - Pittsburgh Screw & Bolt Co., Pittsburgh

- P6 Pittsburgh Steel Co., Pittsburgh
- P7 Portsmouth Div., Detroit Steel Corp. Detroit P8 Plymouth Steel Co., Detroit
- P9 Pacific States Steel Co., Niles, Cal.
- RI Reeves Steel & Mfg. Co., Dove, O.
- R2 Reliance Div. Eaton Mfg. Co., Massillon, O. R3 Republic Steel Corp., Cleveland
- Roebling Sons Co. (John A.), Trenton, N.
- R5 Rotary Electric Steel Co., Detroit
- Sharon Steel Corp., Sharon, Pa.
- 52 Sheffield Steel Corp., Kansas City
- Shenango Furnace Co., Pittsburgh
- Simonds Saw & Steel Co., Fitchburg, Mass.
- S5 Sloss Sheffield Steel & Iron Co., Birmingham
- Standard Forging Corp., Chicago
- Stanley Works, New Britain, Conn. 58 Superior Drawn Steel Co., Monaca, Pa.
- S9 Superior Steel Corp., Carnegie, Pa S10 Sweat's Steel Co., Williamsport, Pa.
- S11 Seidelhuber Steel Rolling Mills, Seattle
- Tonawanda Iron Div., N. Tonawanda, N. Y.
- Tennessees Coal & Iron Div., Birmingha
- Tennessee Products & Chem. Corp., Nashville
- Thomas Strip Div., Warren, O.
- Timken Steel & Tube Div., Canton, O.
- 76 Tremont Nail Co., Wareham, Mass.
- Ul United States Steel Co., Pittsburgh
- U2 Universal-Cyclops Steel Corp., Bridgeville, Pa.
- WI Wallingford Steel Co., Wallingford, Co.
- W2 Washington Steel Corp., Washington, Pa.
- W3 Weirton Steel Co., Weirton, W. Va.
- W4 Wheatland Tube Co., Wheatland, Pa.
- W5 Wheeling Steel Corp., Wheeling, W. Va.
- W6 Wickwire Spencer Steel Div., Buffalo W7 Wilson Steel & Wire Co., Chicago
- W8 Wisconsin Steel Co., S. Chicago, Ill. W9 Woodward Iron Co., Woodward, Ala.
- W10 Wyckoff Steel Co., Pittsburgh
- YI Youngstown Sheet & Tube Co., Youngstown

MERCHANT WIRE PRODUCTS

	Standard & Coated Nails	Woven Wire Fence 9-151'2 ga.	Fence Posts	Single Leep Bale Ties	Twisted Barbless Wire	Gal. Barbed Wire	Merch. Wire Ann'ld	Merch, Wire Gal.
F.o.b. Mill	Col	Col	Col	Col	Col	Col	¢/lb.	$g/lb_{\rm o}$
Alabama City R3*† Aliquippa, Pa. J3 Atlanta A8 Bartonville K2	118 127 130 127	135 141 140 139	140	132 135 132		148 149	6.075 6.075 6.325 6.075	6.525
Buffalo W6 Chicago N4° Cleveland A6 Cleveland A5	118	137		132	146	146	6.075	6.40
Crawfrdsvi M4 Donora, Pa. A5* Duluth A5 Fairfield, Ala. T2*	130 118 118	140 133 133		134 132 132 132		142	6.175 6.075 6.075	
Johnstn, Ps. B3 Jaliet, Ill. A5*	135 127 118	147	148	132	149	156	6, 475	6.925 6.575 6.225
Kokome, Ind. C9 Les Angeles B2 Kansas City S2 Minnequa C6*	139	146		144		160	7.025	7.125
Meline III. R3 Pittsburg, Cal. C7°. Menessen P6	137	156	136	156	162	162		7,125
Portsmouth P7. Rankin, Pa. A5°. So. Chicago R3°†. S. San Fran. C6.	132 118 118	133	140			144	6.075	6.225 6.325 7.40
Sparrows Pt. B3 Struthers, O. Y11 Torrance, Cal. C7°. Wercester A5°	129			134	151		6.075	6.675
Williamsport, Pa. S10	1							111124

Cut Nails, carloads base \$7.80 per 100 lb. (less 20¢ to jobbers) at Conshehocken Pa. (A2) Wheeling, W. Va. (W5) \$7.80.

* Add 45¢ per 100 lb. on Std. & Coated Nails.

1 Galv. Merch. Wire based on 15¢ Zinc.

† Zinc extra if not included on Galv. Merch. Wire.

STAINLESS STEELS

Base price, cents per lb., f.o.b. mill. Add 4.7 pct to base and extras.

Product	301	302	303	304	316	321	347	410	416	430
Ingots, rerolling	14.25	15.25	16.75	16.25	24.75	28.00	21.75	12.75	14.75	13.00)
Slabs, billets, rerolling	18.50	20.00	22.00	21.00	32.25	26.25	28.50	16.50	20.00	16.75
Forg. discs, die blocks, rings	34.00	34.25	36.75	35.75	53.00	40.25	44.75	28.00	28.50	28.50
Billets, forging	26.25	26.50	28,50	27.75	41.50	31.25	35.00	21.50	22.00	22.00
Bars, wires, structurals	31.25	31.50	34.00	33.00	49.25	37.00	41.50	25.75	26.25	26,25
Plates	33.00	33.25	35.25	35.25	52.00	40.75	45.25	27.00	27.50	27.50
Sheets	41.00	41.25	43.25	43.25	57.00	49.25	53.75	36.56	37.00	39.00
Strip, hot-rolled	26.50	28.25	32.50	30.25	48.75	37.00	41.25	23.50	30.25	24.00
Strip, cold-rolled	34.00	36.75	40.25	38.75	59.00	48.25	52,25	30.50	37.00	31.00

STAINLESS STEEL PRODUCING POINTS—Sheets: Midland, Pa., CII; Brackenridge, Pa., A3; Butler, Pa., A7; McKeesport, Pa., U1; Washington, Pa., W2; (type 316 add 4.5¢) J2; Baltimore, E1; Middletown, O., A7; Massillon, O., R3; Gary, U1; Bridgeville, Pa., U2; New Castle, Ind., I2; Ft. Wayne, J4; Lockport, N. Y., R4.

Strip: Midland, Pa., Cll; Cleveland, A5; Carnegie, Pa., 59; McKeesport, Pa., Fl; Reading, Pa., C2; Washington, Pa., W2 (type 316 add 4.5¢); W. Leechburg, Pa., A3; Bridgeville, Pa., U2; Detroit, M2; Canton-Massillon, O., R3; Middletown, O., A7; Harrison, N. J., D3; Youngstown, C., Lockport, N. Y., S4; Sharon, Pa., S1 (type 301 add 1/4¢); Butler, Pa., A7; Wallingford, Conn., W1.

Bars: Baltimore, A7; Duquesne, Pa., U1; Munhall, Pa., U1; Reading, Pa., C2; Titusville, Pa., U2; Washington, Pa., J2; McKeesport, Pa., U1; I; Bridgeville, Pa., U2; Dunkirk, N. Y., A3; Massillon, O., R3; Chicago, U1; Syracuse, N. Y., C11; Watervliet, N. Y., A3; Waukegan, A5; Lockport, N. Y., S4; Canton, O., T5; Ft. Wayne, J4.

Wires: Waukegan, A5: Massillon, O., R3; McKeesport, Pa., F1; Ft. Wayne, J4; Harrison, N. J., D3; Baltimore, A7; Dunkirk, A3; Monessen, P1; Syraouse, C11; Bridgeville, U2.

Structurals: Baltimore, A7; Massillon, O., R3; Chicago, Ill., J4; Watervliet, N. Y., A3; Syracuse, C11.

Plates: Brackenridge, Pa., A3 (type 416 add 1/4); Butler, Pa., A7; Chicago, Ul; Munhall, Pa., Ul; Midland, Pa., C11; New Castle, Ind., I2; Lockport, N. Y., S4; Middletown, A7; Washington, Pa., J2; Cleveland, Massillon, R3. Forged discs, die blocks, rings: Pittsburgh, C11; Syracuse, C11; Ferndale, Mich., A3; Washington, Pa., J2.

Forging billets: Midland, Pa., C11; Baltimore, A7; Washington, Pa., J2; McKeesport, F1; Massillon, Canton, O., R3; Watervliet, A3; Pittsburgh, Chicago, U1; Syracuse, C11. ALLEGHENY LUDLUM-Slightly higher on Type 301; slightly lower on others in 300 series.

WASHINGTON STEEL-Slightly lower on 300 series except where noted.

PIPE AND TUBING

Base discounts (.o.b. mills. Base price about \$200 per net ton.

	BUTTWELD									SEAN	ILESS									
	1,2	In.	3/4	ln.	1	în.	11/4	In.	112	la	2	In.	21/2-	3 In.	2	In.	21/2-	3 In.	31/2	-4 In.
STANDARD T. & C.	Bik.	Gel.	Blk.	Gal.	Blk.	Gal.	Blk.	Gal.	Blk.	Gal. 17.25	Blk. 37.5	Gal. 17.75	B1k.	Gal. 18.25	Blk.	Gal.	Blk.	Gal.	Bik.	Gal.
Spacrows Pt. B3 Toungstown R3	30.5	8.25 10.25	33.5 35.5	12.25	35.5	15.75 17.75 6.25	36.5 38.5 27.0	16.25 18.25 6.75	39.0 27.5	19.25	39.5 28.0	19.75	40.0	20.25						
Fentana K1. Pittaburgh 13 Alten, Ill. L1	21.0 32.5 31.5	1.25 10.25 9.25	24.0 35.5 34.5	2.75 13.25 13.25	26.5 38.0 37.0	15.75	38.5 37.5	16.75	39.0 38.0	17.25	39.5 38.5	17.75 18.75	40.0 39.0	18.75 19.25	24.0	2.25	27.0	5.75	29.0	7.75
Sharen M3. Pittsburgh N1	32.5 32.5	9.25 10.25	35.5 35.5	13.25 14.25	38.0 38.0	16,25 17.75	38.5 38.5	16.75	39.0 39.0	17.25 19.25 19.25	39.5 39.5 39.5	17.75 19.75 19.75	40.0 40.0 40.0	18.25 20.25 20.25	24.0		27.0		29 0	*****
Wheeling W5 Wheatland W4 Teungstown Y1	32.5 32.5 32.5	10,25 10,25 10,25	35.5 35.5 35.5	14.25 13.25 14.25	38.0 38.0 38.0	17.75 15.75 17.75	38.5 38.5 38.5	18.25 16.75 18.25	39.0 39.0 39.0	17.25	39.5 39.5	17.75	40.0	18.75	24.0	3.75	27.0	6.75	29.0	8.75
Indiana Harbor Y/ Lerain N2	31.5 32.5	9.25 15.25	34.5 35.5	13.25 14.25	37 0 38.0	16.75 17.75	37.5 38.5	17.25 18.25	38.0 39.0	18.25	38.5 39.5	18.75	39.0 40.0	19.25 20.25	24.0	3.75	27.0	6.75	29.0	8.75
EXTRA STRONG PLAIN ENDS																				
Sparrows Pt. B3 Youngstewn R3	30.25	9.5	34.25	13.5	36.25	17.0	36.75	17.5	37.25	18.5	37.75 39.75	19.0 21.0	38.25 40.25	19.5						
Fentana K1 Pittsburgh J3	20.75 32.25 29.25	10.0	24.75 36.25 33.25	14.0	26.75 38.25 35.25	16.0	27.25 38.75 35.75	17.0	27.75 39.25 36.25	17.5	28.25 39.75 36.75	18.0	28.75 40.25 37.25	19.0	23.75	2.0	27.75	6.5	31.25	10.0
Alten, Ill. L1. Sharen M3. Pittsburgh N1.	32.25 32.25	10.5	36.25 36.25	14.5 15.5	38.25 38.25	17.5 19.0	38.75 38.75	18.0 19.5	39.25 39.25	18.5 20.5	39.75 39.75	19.0	40.25	19.5	23.75		27.75		31.25	
Wheeling W5	32.25	11.5	36.25 36.25	15.5	38.25	19.0 16.0 19.0	38.75 38.75 38.75	19.5 17.0 19.5	39.25 39.25 39.25	20.5 17.5 20.5	39.75 39.75 39.75	21.0 18.0 21.0	40.25 40.25 40.25	21.5 19.0 22.5	23.75	4.5	27.75	8.5	31.25	12.0
Toungstewn YI Indiana Harber YI Lerain N2	32.25 31.25 32.25	11.5 10.5 11.5	36.25 35.25 36.25	15.5 14.5 15.5	37.75 37.25 38.25	17.5 19.0	37.75 38.75	18.5	38.25 39.25	19.5	38.75	20.0	39.25 40.25	20.5	23.75	4.5	27.75	8.5	31.25	12.0

Galvanized discounts based on zinc, at 17¢ per lb, East St. Louis. For each 1¢ change in zinc, discounts vary as follows: \(\frac{1}{2} \) in., \(\frac{3}{4} \) in., and \(1 \) in., \(1 \frac{1}{4} \) in., \(1 \frac{1}{2} \) in., \(2 \) in., \(3 \) in., \(\frac{1}{2} \) pt. Calculate discounts on even cents per lb of zinc, i.e., if zinc is 16.51¢ to 17.50¢ per lb, use 17¢. Jones & Laughin discounts apply only when zinc price changes 1¢;

Threads only buttweld and seamless, \(1 \) pt. higher discount. Plain ends, buttweld and seamless, \(3 \) in. and under, \(3^3 \) a pts. higher discount. Buttweld jobbers' discount, \(5 \) pct. St. Louis zinc price now 12.5¢.

COVE

COKE	
Furnace, beehive (f.o.b. oven) Net-	Cor
Connellsville, Pa \$14.50 to \$15 Foundry, beehive (f.o.b. oven)	1, 01
Connellsville, Pa \$17.50 to \$18	0.0
Foundry, oven coke Buffalo, del'd \$24	53
Chicago, f.o.b	0.00
New England, del'd 24	. 84
Seaboard, N. J., f.o.b. 22 Philadelphia, f.o.b. 22	.7
Swedeland, Pa., f.o.b. 22 Palnesville, Ohio, f.o.b. 21	6
Erle, Pa., Lob	
Cleveland, del'd 25	1.1.
Cincinnati, del'd 25 St. Paul, f.o.b. 22	1.01
St. Paul, f.o.b. 22 St. Louis 25	4
Birmingham, del'd	111
Lone Star, Tex., f.o.b. 18	.50

ELECTRICAL SHEETS

22 Ga. H-R cut length F.o.b. Mill Centa Per Lb.	Armalure	Elec.	Meter	Dyname	Transf. 72	Transf. 65	Transf. 58
Beech Battom W5.		7.85	9.10	9.90	10.45	11.00	11.70
Brackenridge A3	7.35	7.85	9.10	9.90	10.45	11.00	11.70
Granite City G2		8.55	9.80				
Ind. Harbor 13	7.35	7.85	9.10				
Manafield E2	7.35	7.85	9.10	9.90			
Niles, O. N3	7.35	7.85					
Vandergrift U1							
Warren, O. R3.	7.35	7.85	9,10				
Zanesville A7	7.35	7.85	9.10	9.90	10.45	11.00	11.70

PIG IRON

Dollars per	gress ten.	f.o.b.,	subject to	switching	charges.

Producing Point	Basic	Foundry	Malleable	Bessemer	Low Phos.	Bl. Furnace Silvery
Bethlehem B3	56.50	57.00	57,50	58.00	1	
Birmingham R3	50.88	51.38	1			
Birmingham W9	50.88	51.38				
Birmingham S5	50.88	51.38				
Buffalo R3	54.50	55.00	55.50			
Buffalo H1	54.50	55.00	55.50			66.75
Buffale W6	54.50	55.00	55.50			
Chicago 14	54.50	55.00	55.00	55.50		
Cleveland 45	54.50	55.00	55.00	55.50	59,50	
Cleveland R3	54.50	55.00	55.00			
Daingerfield, Tex. L3	50.50	51.00	51.00			
Dolath 14	54.50	55.00	55.00	55,50		
Frie 14	54.50	55.00	55.00	55.50		
Erie 14 Everett, Mass. M6		59.25	59.75			
Fantana K I	60.50	61.00			11111	
Fentana K/ Gemeva, Utah C7	54.50	55.00				
Granite City, III. K3	56.40	56.90	57.40			
United Office VI	54.50	55.00	55.00			
Hubbard, Ohie YI	54.50	22.00	33.00			65.50
Jackson, Ohio JI,GI	FR FA	60.60	57 50			
Minnequa C6	56.50	57.50	57.50			
Menessen P6	56.50	0.000	2011	FF F6		
Neville Island P4	54.50	55.00	55,00	55.50		
Mtsburgh UI	54.50		20000	55.50		
Sharpaville S3	54.50	55.00	55.00	55.50	40.00	
Steelten B3	56.50	57.00	57.50	58.00	62.50	
wedeland A2	58.50	59.00	59.50	60.00		
Tolodo 14	54.50	55.00	55.00	\$5.50	11111	
rov. N. Y. R3	56.50	57.00	57.50	26121	62.50	
Youngstown Y/	54.50	\$5.00	55.00	\$5.50		
N. Tenawanda, N. T. 7/		55.00	55.50			

DIFFERENTIALS: Add 50e per ton for each 0.25 pct silicon over base, (1.75 to 2.25 pct, except low phos., 1.75 to 2.00 pct), 50e per ton for each 0.50 pct manganese over 1 pct, \$2 par ton for 0.5 to 0.75 pct nickel, \$1 for each additional 0.25 pct nickel. Subtract 38e per ton for phespherus, content 0.70 pct and over. Silvery Iron: Add \$1.50 per ton net for each 0.50 pct add over. Silvery Iron: Add \$1.50 per ton net for each 0.50 pct add over. Silvery Iron: Add \$1.50 per ton net for each 0.50 pct for each 0.50 pct add over. Silvery Iron: Add \$1.50 per ton net for each 0.50 pct or more phespherus, manganese as above. Bessemer formsilicon prices are \$1 over comparable silvery iron.

CAST IRON WATER PIPE

Per Net Ton

6 to 24-in., del'd Chicago \$105.30 to \$108.80 to 24-in., del'd N.Y... 108.50 to 109.50 to 24-in., Birmingham 91.50 to 96.00 folia and larger, f.o.b. cars, San Francisco, Los Angeles, for all rall shipments; rail and water shipments less\$123.00 to \$130.00 Class "A" and gas pipe, \$5 extra; 4-in pipe is \$5 a ton above 6-in.


BOILER TUBES

\$ per 100 ft. carlead	Si	IN.	Sean	nless	Elec.	Weld
lots, cut 10 to 24 ft. F.o.b. Mill	OD- In.	B.W.	H.R.	C.D.	H.R.	C.D.
Babcock & Wilcox	2 21/2 3 31/2 4	13 12 12 11 10	32.17 35.78 44.72	28.14 37.83 42.11 52.65 65.31	31.19 34.69 43.36	36.67 40.82 51.05
National Tube	2 21/2 3 31/2 4	13 12 12 11 10	31.28 35.87 42.56	27.94 38.31 43.93 52.12 66.16	30.51	
Pittsburgh Steel	2 2 ¹ / ₂ 3 3 ¹ / ₂	13 12 12 11 10	36.87	28.58 39.19 44.93 53.32 67.68		

C-R SPRING STEEL

	CARBON CONTENT								
Cents Per Lb. F.e.b. Mill	0.26-	0.41-	0.61	0.81- 1.05	1.06-				
Bridgeport, Conn. S7	5.80	7.65	8.25	10.20	12.50				
Carnegie, Pa. S9		7.65	8.25	10.20	12.50				
Cleveland A5	5.10	7.30	8.25	10.20	12.50				
Detroit D1	6.45	7.50	8.10						
New Castle, Pa. B4.	5.80	7.65	8.25	10.20					
New Haven, Conn. D!	6.70	7.60	8.20						
Sharon, Pa. S1	5.80	7.65	8.25	10.20	12.50				
Trenten, N. J. R4		7.95	8.55	10.50	12.80				
Warren, Ohio T4	6.20	7.65	8.25	10.20	12.50				
Weirton, W. Va. W3.	5.80	7.65	8.25	10.20	12.50				
Worcester, Mass, 45	5.40	7.60	8.55	10.50	12.80				
Youngstown C5		7.65	8.25	10.20	12.50				

*Sold on Pittsburgh base



Consistent
Hardenability obtained
in Boron Steels
made with
GRAINAL ALLOYS

The most common test for boron steels is measurement of hardenability by the end quench or Jominy hardenability test. Today's steel substitutions are made on the basis of similar hardenability since a reasonable prediction can thus be made of the hardness and strength of a given part.

The curves above show the relationship between the hardenability of a series of seven heats of 81B40 steel and the hardenability band for 4140H steel, which it often replaces. The 81B40 heats were made in one electric furnace shop, and the remarkably consistent hardenability shown by the curves was obtained by the use of Grainal alloy as the means of adding the boron.

Consistent hardenability means consistent strength and hardness after heat treatment, which is the aim of every fabricator. The best proof that the Grainal alloys insure this objective is found in the successful use of three million tons of Grainal-treated steels.

VANADIUM CORPORATION OF AMERICA

*** LEXINGTON AVENUE, NEW YORK 17, N. Y. - DETROIT - CHICAGO - CLEVELAND - PITTSBURGH



November 27, 1952

7.75

8.75

8.75

10.0

12.0

08.80 09.50 96.00

Weld C.D.

27.28 36.67 40.82 51.05 63.32

12.50 12.80 12.50 12.50 12.50 12.80 12.50

952

RAILS, TRACK SUPPLIES

F.a.b. Mill Cents Per I.b	No 1 Srd Rails	Light Rails	Joint Bars	Track Spikes	Screw Spikes	Tie Plates	Track Bolts Treated
Bessemer U/	3,775	4.25	4.925				
Chicago R3		1100		6.65			
Cleveland R3							
Cleveland R3 Ensley T2	3.775	4.25					
Enirhald 77		4 25		6 65		4 775	
Gary UI	3.775	4.25				4.775	
Gary UI Ind. Harbor 13.	3.775		4.925	6.65		4.775	
Johnstown B3		4.25					
Joliet UI		4.25	4.925	1000			
Kansas City S2							
Kansas City S2. Lackawanna B3	3.775	4.25	4.925			4.775	
Lebanon B3				6.65			
Minnequa C6	3.775	4.75	4.925	6.65		4.775	9.8
Pittsburgh R3							
Pittsburgh 0/							
Pitt'g, Cal. C7						4.925	
Seattle BZ				7.15		4.925	
Steelton B3	13.775		4.925			4.775	
Struthers Y1.				6.65			
Torrance C7						4.925	
Youngstown R3				6 65			

TOOL STEEL

 $F.o.b. \ \textit{mill}$ Add 4.7 pct to base and extras.

VV	Cr	1.	Mo	Co	Base
18	6	7	240.07		\$1.505
18	6	1		5	\$2.13
	4	A		63	
18	4	2	1011000	-	\$1.65
1.5	4	1.5	8	-	81.0 €
6	4	2	6	-	96.56
High-	carbon	chromiu	m .		63.56
Oll ha	rdened	mangar	10se		. 354
Specia	I carbo	n			. 32.56
War	rehouse	prices	on an	d east	of Mis-
	of are 3 sippi, 5.			gher. V	Vest of

CLAD STEEL

Add 4.7 pct to base and extras.

Stainless-carbon No. 304, 20 pct.	Plate	Sheet
Coatesville, Pa. L4 Washington, Pa. J Claymont, Del. C.	*29.5	
Conshohocken, Pa		*27.50 *26.24
Nickel-carbon 10 pct Contesville, Pa. L Inconel-carbon	32.5	
10 pct Coatesville, Pa. L4	40.5	
10 pct Coatesville, Pa. L4 No. 302 Stainless-copper stainless, Carnegie,		
Pa. A4 Aluminized steel sheets, hot dip, Butler, Pa.		77,00
A7. Includes annealing and pickling, or a		7.75

ELECTRODES

Cents per lb, f.o.b., plant threaded electrodes with nipples, unboxed

010001000	or with triblines,	
Diam. in in.	Length in in.	Cents Per Ib.
	GRAPHITE	
17, 18, 20	60, 72	17.85
8 to 16	48, 60, 72	17.85
7	48, 60	19.57
8 to 16 7 6 4, 5 3 21/2	48, 60	20.95
4, 5	40	21.50
3	40	22.61
2 1/2	24, 30	23.15
2	24, 30	25.36
	CARBON	
4.0	100, 110	8.45
3.5	65, 110	8.45
3-0	65, 84, 1	8.45
24	72 to 10+	8.45
20	84, 90	8.45
24 20 17 14	60, 72	8.45
14	60, 72	9.02
10, 12	60	9.30
9	60	9.58

FLUORSPAR

Washed	gravel,	fot:	Rosiciaire,	III.
10% or m	юге		F, content	3.00

BOLTS, NUTS, RIVETS, SCREWS

Consumer Prices

(Base, discount, f.o.b. mill, Pittsburgh, Cleveland, Birmingham or Chicago)

Nuts, Hot Pressed, Cold Punched-Sq.

Pc	Less Keg.	K	Less Keg.	K.
1/4 in. & smaller. 9/16 in. & 1/4 in. 3/4 in. to 11/4 in.	15 12	28 1/2 25	15 6 12	28 1/2 21
inclusive 1% in. & larger.	9	9 7	1	16 1/2

Nuts, Hot Pressed-Hexagon

½ in. & smaller.	26	31	22	34
9/16 in. & 5 in.	16 1/2	29 12	47.3/92	21
% in. to 1 ½ in.	19	25	9	174
1% in. & larger.	81/6	27	9	173

Nuts, Cold Punched-Hexagon

½ in. & smaller 9/16 in. & % in.		37	22	34
% in. to 11/2 in.				
inclusive	191/2	31 12	12	25

Nuts, Semi-Finished-Hexagon

	R	eg.		His	Y.
½ in. & smaller. 9/16 in. & % in.		4 % 3 å	28	16 16	29 14
% in. to 1% in. inclusive	24	36 26	15		28 4 23
7/16 in. & small-		Light			
er in. thru % in. % in. to 1% in.	28 1/4	45 39 1 ₂			
inclusive	26	37			

Stove Bolts Pet Off List

Packaged, steel, plain finished 48—10
Packaged, plain finish 31—10
Bulk, plain finish 31—10
Bulk, plain finish 62°
*Discounts apply to bulk shipments in not less than 15,000 pieces of a size and kind where length is 3-in and shorter; 5000 pieces for lengths longer than 3-in. For lesser quantities, packaged price applies.

plies.
• Zinc, Parkerized, cadmium or nickel plated finishes add 6¢ per ib net. For black oil finish, add 2¢ per ib net

Riv	ets				Base	per	100	11
3/8	in.	de	larger				37	8

Cap and Set Screws

(In bulk)	Pet Off	Lis
Hexagon head cap screws, co	aree or	
fine thread, ¼ in. thru %		
in., SAE 1020, bright		5
14 in. thru 1 in. up to & includ	ing 6 in.	4.5
14 in. thru % in. x 6 in. &	shorter	
high C double heat treat		41
% in. thru 1 in. up to & includ	ing 6 in.	41
Milled studs		31
Flat head cap screws, listed s	izes	1
Fillister head cap, listed sizes		3
Set screws, sq head, cup poir		
diam, and smaller x 6 in. &	shorter	6

Machine and Carriage Bolts

	Less	U Lite
	Case	C.
% in. & smaller x 6 in & shorter	1.5	28 1/2
shorter	1834	30 1/2
in. & larger x 6 in. & shorter All diam. longer than 6 in	173/2	29 ¼ 27 ¼
Lag, all diam. x 6 in. & shorter	23	35
Lag, all diam. longer than 6 in. Plow bolts	21 34	32

REFRACTORIES

Fire Clay Brick	Carloads, per 1000
First quality, Ill., Ky., (except Saima, Pa.,	Md., Mo., Ohio, Pa.
No. 1 Ohio	
No. 2 Ohio	79.20
Ground fire clay, net t cept Salina, Pa., add	\$1.50) 13.75

Silica Brick

Mt. Union, Pa., Ensley, Ala \$94.60
Childs, Pa 99.00
Hays, Pa
Chicago District
Western Utah and Calif111.10
Super Duty, Hays, Pa., Athens,
Tex., Chicago
Silica cement, net ton, bulk, East-
ern (except Hays, Pa.) 16.50
Silica cement, net ton, bulk, Hays,
Pa
Silica cement, net ton, bulk, Ensley,
Ala 17.60
Silica cement, net ton, bulk, Chi-
cago District 17.60
Silica cement, net ton, bulk, Utah
and Calif 24.70

Chrome Brick Per Net Ton Standard chemically bonded balt, Chester \$82.00

Mannosite Reick

Maduezuc	DITTOR			
Standard.		e	. 1	93.00

Grain Magnesite St. %-in grains

Domestic, in bulk	fines re	moved					\$62.70
Domestic, in bulk	fo.b.	Chewala	h,	W	8.8	h.,	
in bulk						. 0	36.30
in sack	15						41.80

Dond Rurned Dolomite

Dead	burnen b	Olomite	
F.o.b.	producing	points in Pennsyl-	
van	ia. West	Virginia and Ohio	
per	net ton,	bulk Midwest, add	
104	. Milononni	Valley add 20# \$13.75	

LAKE SUPERIOR ORES

51.50% Fe;	natural content, delivered
lower Lake	ports. Prices effective July

	20.	302						
						GT	088	Ton
Old range, be	ssemer							\$9.46
Old range, no	nbessen	ner						9.30
Mesabi, besse	mer							9.20
Mesabi, nonbe	essemer					0 .		9.05
High phospho	rus				0 6			9.05
After adjus	stments	for	8.	na	ly:	ıla,	P	rices
will be increa	sed or d	lecre	as	ed	a	8 t	he	CASE
may be for i	ncrease	s or	d	ec	rei	186	86	after
Dec. 1, 1950.	in Lake	e ve	886	1	187	tes	, U	pper
Lake rail frei	ghts, do	ock !	ha	nd	lin	g	chi	arges
and taxes the	reon.							

METAL POWDERS

MEIAL LOMDERS
Per pound, f.o.b. shipping point, in ton lots, for minus 100 mesh.
Swedish sponge from c.l.f. New York, ocean bags 19.96
Canadian sponge iron, del'd. in East
Fe, carload lots 15.5¢ to 17.0¢
Electrolytic iron, annealed, 99.5+% Fe
Electrolytic iron, unannealed, minus 325 mesh, 99+% Fe 60.0¢
Hydrogen reduced iron, minus 300 mesh, 98+% Fe. 63.0¢ to 89.0¢
Carbonyl iron, size 5 to 10 micron, 98%, 99.8+% Fe.83.0¢ to \$1.48
Aluminum 31.5¢ Brass, 10 ton lots 30.00¢ to 33.25¢
Copper, electrolytic 10.75¢ plus metal value Copper reduced10.00¢ plus metal value
Cadmium, 100-199 lb 95¢ plus metal value Chromium, electrolytic, 99%
min., and quantity, del'd \$3.50 Lead7.5¢ to 12.0¢ plus metal value
Manganese
Molybdenum, 99% \$2.75 Nickel, unannealed \$8.0¢
Nickel, annealed 95.0¢ Nickel, spherical, unannealed 92.0¢
Solder powder . 7.0¢ to 9 0¢ plus met. value
Stainless steel, 302 83.00¢ Stainless steel, 316 \$1.10
Tin14.00¢ plus metal value Tungsten, 99% (65 mesh) \$6.00
Zinc, 10 ton lots



1000

13.75

11.10 16.50 18.70 17.60 17.60 14.70 Ton 82.00

93.00

82.70 36.30 41.80

13.75

July

70n 9.46 9.30 9.20 9.05 9.05 rices case after pper

ton

10.9€

12.0¢

44.0¢ 60.0¢ 80.0¢

\$1.48 \$1.5¢ 3.25¢ value value value

\$3.50

7alue 57.0¢ \$2.75 88.0¢ 95.0¢ 92.0¢ 88.5¢ 7alue 3.00¢ \$1.10

alue 6.00 30.5¢

952

This intricate maze of metal is the valve section of a popular automatic transmission, cast in Gray Iron.



6 Reasons why the final choice was

GRAY IRON!

1. Greater rigidity, strength and dimensional stability

2. Greater accuracy—can be held to closer tolerances

3. Greater wear resistance

 Does not permit dirt to imbed, as do the softer nonferrous materials

5. Desirable thermal expansion characteristics

6. Economy

Intricate components such as the section shown here are economically practical only as integral castings. The final question then becomes—in what material shall they be cast?

This valve section was first experimentally cast in a nonferrous material. However, the final choice was Gray Iron, for the practical reasons listed at the left. These same basic advantages of Gray Iron could well apply to one of *your* current design problems.

Write for technical information on the many advantages of the Gray Iron casting process.



Make it Better with Gray Iron Second largest industry in the metal-working field

GRAY IRON FOUNDERS' SOCIETY, INC.

NATIONAL CITY-E. 6th BLDG., CLEVELAND 14, OHIO


Ferroalloy Prices-		9
errochrome	Spiegeleisen	Alsifer, 20% Al, 40% Si, 40% Fe.
Contract prices, cents per pound, con-	Contract prices gross ton; lump, f.o.b.	contract basis, f.o.b. Suspension Bridge, N. Y.
lined Cr, lump size, bulk in carloads elivered. (65-72% Cr, 2% max. Si.)	16-19% Mn 19-21% Mn	Carloads
06% C 30.50	Palmerton, Pa. 38 4.00 \$85.00	Calcium molybdate, 46.3-46.6% f.o.b. Langeloth, Pa., per
10% C 30.00 0.50% C 29.25 15% C 29.75 1.00% C 29.00 00% C 28.75 5-69% Cr, 4-9% C 22.00	Pgh. or Chicago 84.00 85.00	f.o.b. Langeloth, Pa., per pound contained Mo
5-69% Cr, 4-9% C	Manganese Metal	Ferrocolumbium, 50-60% 2 in.
M. Ferrochrome	Contract basis, 2 in. x down, cents per	x D, contract basis, delivered per pound contained Cb.
Contract price, cents per pound, chro-	96% min. Mn, 0.2% max. C, 1% max.	Ton lots
ium contained, lump size, delivered. High carbon type: 60-65% Cr, 4-6%	Si, 2.5% max. Fe. Carload, packed	Ferro-Tantalum-Columbium, 20%
, 4-6% Mn, 4-6% C. arloads	Ton lots	Ta, 40% Cb, 0.30 C. Contract basis, delivered, ton lots, 2 in.
on lots	Electrolytic Manageore	x D, per lb of contained Cb plus Ta
Low carbon type: 62-66% Cr, 4-6% St,	Electrolytic Manganese	Ferromolybdenum, 55-75%, f.o.b.
6% Mn, 1.25% Max. C.	F.o.b. Knoxville, Tenn., freight allowed east of Mississippi, cents per pound.	Langeloth, Pa., per pound con- tained Mo
n lots	Carloads 30.00 Ton lots 32.00 Less ton lots 34.00 to 37.00	Ferrophosphorus, electrolytic, 23- 26%, car lots, f.o.b. Siglo, Mt.
gh-Nitrogen Ferrochrome	Less ton lots 34.00 to 37.00	Pleasant, Tenn., \$3 unitage, per
Low-carbon type: 67-72% Cr. 0.75% N. Id 5¢ per lb to regular low carbon fer-	Low-Carbon Ferromanganese	gross ton \$ 10 tons to less carload \$
chrome price schedule. Add 5¢ for each	Contract price, cents per pound Mn con-	Ferrotitanium, 40% regular
ditional 0.25% N. romium Metal	tained, lump size, del'd Mn 85-90%.	Ferrotitanium. 40% regular grade, 0.10% C max., f.o.b. Ni- agara Falls, N. Y., and Bridge-
Contract prices, per lb chromium con-	0.07% max. C, 0.06%	ville, Pa., freight allowed, ton lots, per lb contained Ti
ined, packed, delivered, ton lots, 97% in. Cr, 1% max. Fe.	P, 90% Mn 28.45 30.30 31.50 0.07% max. C 27.95 29.80 31.00	Ferrotitanium, 25%, low carbon,
10% max. C \$1.14	0.15% max. C 27.45 29.30 30.50	0.10% C max., f.o.b. Niagara Falls, N. Y., and Bridgeville,
0% max. C	0.50% max. C 26.45 28.30 29.50	Pa., freight allowed, ton lots, per lb contained Ti
w Carbon Ferrochrome Silicon	P, 90% Mn	Less ton lots
(Cr 34-41%, Si 42-49%, C 0.05% max.) entract price, carloads, f.o.b. Niagara		Perrotitanium, 15 to 18%, high carbon, f.o.b. Niagara Falls, N. Y., freight allowed, car-
ils, freight allowed; lump 4-in. x down,	Medium Carbon Ferromanganese	N. Y., freight allowed, car- load per net ton
lk 2-in. x down, 21.75c per ib of con- ined Cr plus 12.40¢ per lb of contained	Mn 80% to 85%, C 1.25 to 1.50. Contract price, carloads, lump, bulk, delivered, per	Ferrotungsten, standard, lump
Bulk 1-in. x down, 21.90¢ per lb con-	lb of contained Mn 21.35¢	or 4 x down, packed, per pound contained W5, ton lots,
ned Cr plus 12.60¢ per lb contained Si.	Silicomanganese	delivered
Contract price per lb of allow dump	Contract basis, lump size, cents per	per 1b contained Mo, f.o.b.
Contract price per lb of alloy, dump livered.	pound of metal, delivered, 65-68% Mn.	Langeloth, Pa bags, f.o.b. Washington, Pa.,
-33% Ca, 60-65% Si, 3.00% max. Fe.	18-20% SI, 1.5% max. C. For 2% max C, deduct 0.2¢.	Langeloth, Pa
on lots	Carload bulk	Simanal, 20% Si, 20% Mn, 20% Al, contract basis, f.o.b. Philo,
alcium-Manganese—Silicon	Briquet, contract basis carlots, bulk	Ohio, freight allowed, per pound
Contract prices, cents per lb of alloy	delivered, per lb of briquet 12.65 Ton lots, packed	Carload, bulk lump 1
mp, delivered. -20% Ca, 14-18% Mn, 53-59% Si.		Ton lots, bulk lump l Less ton lots, lump
rloads 20,00 on lots 23,30	Silvery Iron (electric furnace)	Vanadium Pentoxide, 86 - 89% V ₂ O ₅ contract basis, per pound
ess ton lots 23.30	Si 14.01 to 14.50 pct, f.o.b. Keokuk, Iowa, or Wenatchee, Wash., \$95.50 gross	contained V2O5
MSZ	ton, freight allowed to normal trade area.	Zirconium, 35-40%, contract ba- sis, f.o.b. plant, freight nl-
Contract price, cents per lb of alloy,	Si 15.01 to 15.50 pct, f.o.b. Niagara Falls, N. Y., \$93.00. Add \$1.055 per ton for each	lowed, per pound of alloy,
Alloy 4: 45-49% Cr. 4-6% Mn. 18-21%	additional 0.50% Si up to and including 17%. Add \$1.00 for each 0.50% Mn over	Zirconium, 12-15%, contract ba-
, 1.25-1.75% Zr, 3.00-4.5% C. Alloy 5: 50.56% Cr, 4-6% Mn, 13.50-	1%.	sis, lump, delivered, per lb of
.00% Si, 0.75 to 1.25% Zr, 3.50-5.00% C. on lots 20.76	Silican Metal	Carload, bulk
ess ton lots 22.00	Silicon Metal	B AA-
MZ	Contract price, cents per pound con- tained SI, lump size, delivered, for ton lots	Boron Agents
Contract price, cents per pound of alloy, elivered, 60-65% Si, 5-7% Mn, 5-7% Zr,	packed. 96% SI, 2% Fe	Borosil, contract prices per lb of alloy del. f.o.b. Philo, Ohio, freight allowed, B. 3-4%. Sl.
% Fe, ½ in. x 12 mesh.	97% Si, 1% Fe	40 4500 now the contained 12
ess ton lots	Silicon Briquets	Bortam, f.o.b. Niagara Falls Ton lots, per pound Less ton lots, per pound Corbortam, Tl, 15-21%, B. 1-2%, Sl, 2-4%, Al. 1-2% C. 4.5-7.5%,
Foundry Alloy		Less ton lots, per pound
Cents per pound of alloy, f.o.b. Suspenon Bridge, N. Y., freight allowed, max. Louis. V-5: 38-42% Cr, 17-19% St.	Contract price, cents per pound of briquet bulk, delivered, 40% Si, 2 lb Si	Corbortam, Tl, 15-21%, B. 1-2%, Si. 2-4%, Al. 1-2% C. 4.5-7.5%,
Louis. V-5: 38-42% Cr, 17-19% St, 11% Mn.	Carloads, bulk 6.95	1.0.b. Suspension Bridge, N. L.
on lots 16.50	Ton lots 8.55	freight allowed. Ton lots, per pound
ess ton lots	Electric Ferrosilicon	Ferroboron, 17.50% min. B. 1.50% max. Si, 0.50% max. Al. 0.50%
raphidox No. 4 Cents per pound of alloy, f.o.b. Sus-		max. C. I in. x D. Ton lots
ension Bridge, N. Y., freight allowed, ax. St. Louis. Si 48 to 52%, Ti 9 to 11%,	Contract price, cents per pound contained Si, lump, bulk, carloads, delivered.	F.o.b. Wash., Pa.; 100 lb up 10 to 14% B
a 5 to 7%.	25% Si 20.00 75% Si 14.30 50% Si 12.40 85% Si 15.55 90-95% Si 17.00	14 to 19% B
arload packed 18.00 on lots to carload packed 19.00	90-95% Si 17.00	Grainal, f.o.b. Bridgeville, Pa., freight allowed, 100 lb and over.
ess ton lots 20.50	Calaina Matal	No. 1
78-82% Mn, maximum contract base	Calcium Metal	No. 1 No. 6 No. 79
ice, gross ton, lump size.	Eastern zone contract prices, cents per pound of metal, delivered.	Manganese - Boron, 75.00% Mn. 15-20% B, 5% max. Fe, 150% max. Sl, 3.00% max. C, 2 in. x
Ashtabula, O	Ton lots \$2.05 \$2.95 \$3.75	max. Si, 3.00% max. C. 2 in. x
Ashtabula, O. \$225 O.b. Johnstown, Pa. \$227 O.b. Sheridan, Pa. \$227	Less ton lots 2.40 3.30 4.55	D. del'd
F.o.b. Sheridan, Pa. \$225 F.o.b. Etna. Clairton, Pa. \$228		Ton lots
Add \$2.80 for each 1% above 82% Mn. subtract \$2.80 for each 1% below 78%	Ferrovanadium	Nickel-Boron, 15-18% B, 1.00% max, Al, 1.50% max, Si, 0.50%
	35-55% contract basis, delivered,	max. C, 3.00% max. Fe, balance
Mn.	ner nound contained T'	NI. delivered
Mn. Briquets—Cents per pound of briquet, lellvered, 66% contained Mn. 2 arload, bulk 12.45	per pound, contained V. Openhearth	NI. delivered Less ton lots Sileaz. contract basis, delivered.

PRODUCTION with POWER!

MUELLER MODEL PF PRODUCTION LATHE

Built with rigidity . . . ribbed at points of stress . . . designed to eliminate vibration . . . this rigid production lathe is built for heavy duty!

The motor can be supplied with constant or multi-speed change . . . controlled through push buttons and contractors . . . or electronically controlled giving infinitely variable speed ranges! These lathes give constant cutting speed on any diameter by pre-set controls as extra equipment.



PARTIAL SPECIFICATIONS PF300

AVAILABLE

9.90

\$1.15

\$4.90 4.95

\$8.75

\$1.32

65.00 75.00

\$1.85

77.00

\$5.00

\$1.14 \$1.13

\$1.28

1.00€

7.00€

\$5.25

0.06€

\$1.20

\$1.00 68¢ 59¢

\$1.30 15.00€

952

Write for complete details! 6-20 HP 6-20 HP


PF350

for machine tools!

MOREY MACHINERY CO. INC.

410 BROOME ST. - NEW YORK 13, N. Y.

TELEPHONE: CANAL 6-7400
CABLE ADDRESS WOODWORK, N. Y.





You can choose from a complete line of alternating current industrial-type motors -standard or special-single or polyphasefor every job. Get fast delivery, no red tape. Call your local Howell representative or contact us direct.

ELECTRIC MOTORS CO.


HOWELL, MICHIGAN



M.D. Hubbard Spring Company

302 Central Avenue . Pontiac 12, Mich.





LAND - BIG NAME DRILLING MACHINES 3013

LELAND-GIFFORD COMPANY, WORCESTER, MASSACHUSETTS



Use this Electric Motor Clam Shell for rehandling bulk ma terials in Industrial Plants THE HAYWARD CO. 40-50 Charch St. M. F.



DON'T SCRAP IT!

Ever have a tap or drill break in an expensive part? . . . so that even careful drilling couldn't save it? Today, parts costing as little as 50c can be economically salvaged by an Elox Electron Drill.* They're real money savers! No plant can afford to be without one. Write for particulars.

Elox Corporation of Michigan

726 N. Rochester Rd.

GOSS and DE LEEUW

CHUCKING MACHINES
Four, Five, Six, Eight Spindles • Wark and Tool Ratating Type GOSS & DE LEEUW MACHINE CO., KENSINGTON, CONN.

READ


The Advertising Pages of The Iron Age for New Production Ideas

- MACHINE TOOLS & TOOLING
- COMPONENT PARTS
- MATERIALS HANDLING
- PLANT SERVICE EQUIPMENT
- FASTENING & JOINING PRODUCTS

ITS

N AGE





resistance welding became more efficient and more versatile ... When Sciaky combined imagination with electronics to effectively harness three phase current, resistance welding took a huge step forward. For the first time it was possible to draw a balanced current from all three phases of the supply line. Power factor jumped to near unity. KVA demand slumped as much as 50% or more of previous requirements. But most important, resistance welding became more versatile. By simple adjustments one machine could weld many different metals in a wide range of thicknesses.

This is the type of engineering that keeps Sciaky out in front . . . makes the Sciaky name the symbol of the best in resistance welding.



4915 West 67th Street, Chicago 38
Plants at: CHICAGO • LONDON • PARIS

"The Fox and The Stork"

points a moral to Cutting Fluid users

. . . with apologies to Aesop

The Fox was playing host to the Stork at dinner. Being a great prankster, he served nothing but soup in shallow dishes. The poor Stork got nothing to eat because he could get only the tip of his long bill into the soup.

The Stork reciprocated by having the Fox to a dinner at which he served delicious rice in long thin-necked jars. This time the Fox went without food because he couldn't even get his nose into the jar!

THE MORAL.

Like the Fox and the Stork in Aesop's fable, each cutting fluid has its own capabilities. When put on an application for which it is not suited the cutting fluid fails to give you the production, tool life or finish possible.

Stuart offers you a vast background of experience in the selection and application of cutting fluids, both water-mixed and straight oil types and has the cutting fluids to best meet your requirements. Ask to have a Stuart Representative demonstrate how proper selection and application of cutting fluids saves time, money and materials. Be sure to ask him for the booklet "More Than a Coolant Is Needed."

More Than a "Coolant" is Needed

D. A. Stuart Oil CO.

TIME-TESTED CUTTING FLUIDS AND LUBRICANTS 2727-37 S. Troy St., Chicago 23, Ill.

Free! Dilut-o-graph

Circular slide rule makes dilution of cutting fluids quick, easy! For tanks of 1 to 100 gallons. Fill in coupon, clip to your company letterhead and mail to:

D. A. STUART OIL CO. 2727-37 S. Troy St., Chicago 23, III.

2727-37 S. Troy St., Chicago 23, III.



WEBB

STEELWORKER

The Newest Combination Punch & Shear Designed For Diversified or Production Work

5 Complete Tools in ONE

TWO WEEKS' DELIVERY



- 1 Punch for plate, bars or structurals.
- 2 Cuts angles and tees with straight or miter cut.
- 3 Cuts off round and square
- 4 Shears plates and bars.
- 5 Coping or notching attachment.

For diversified shop work or high production output, this all-purpose machine is always in complete readiness to do any of above operations.

Write for Illustrated Literature and Prices Today.

Mfrs. of PLATE BENDING ROLLS and INDUSTRIAL WEIGHING EQUIPMENT

THE WEBB CORP.

WEBB CITY, MO., U. S. A. Since 1881

MAYLINE -



PLAN FILES AND DRAWER UNITS

Files and units are sturdily constructed of selected oak. Drawers operate smoothly on wood drawer runs. Attractive oak finish. Flush or sanitary base.

Available in units of: 2 tool drawers and 1 shallow drawer, 2 tool drawers and 3 shallow drawers, or 5 shallow drawers —for table top widths of 36" or 42". One tool drawer is equipped with an individual lock.

Prompt delivery on any unit or combination. See your local dealer or write directly to factory.

ENGINEERING MANUFACTURING CO.



637 No. Commerce St.

Sheboygan, Wis. MAYLINE

- MAYLINE -

MUNDT

PERFORATED METALS

The few perforations illustrated are indicative of the wide variety of our line—we can perforate almost any size perforation in any kind of metal or material required. Send us your specifications.

Sixty-seven years of manufacturing perforated metals for every conceivable purpose assure satisfaction.

Write for New Catalog of Patterns



TIN. STEEL. COPPER. ALUMINUM. BRONZE, BRASS, ZINC. ANY METAL, ANY PURPOSE

CHARLES MUNDT & SONS

INDUSTRIAL RADIOGRAPHY

the LOW COST Way
... with Radioactive
Cobalt-60

FREE booklet covers sources, container, handler, survey and personnel protection instruments. Write TODAY for your copy.

• Tracerlab Cobalt-60 Radiography sources with their versatility, low cost and practicality, offer foundrymen, welders and fabricators the ideal means for the non-destructive inspection of metal objects. • For years such inspection has been carried out by X-ray machines or radium, but the cost has been prohibitive, particularly to the occasional user. NOW . . . with Cobalt-60 sources . . . even the smallest firm can radiograph their work to PROVE its quality.

BERKELEY - CHICAGO NEW YORK - WASHINGTON



CONSIDER GOOD USED **EQUIPMENT FIRST**

BELT GRINDING UNIT

Hill Clutch & Machine & Fdry. Co. Open Side Abrasive Belt Grinding Unit, Designed to accommodate slabs up to 3/6" thick x 30" wide x 30' long.

BRAKE-LEAF TYPE

'x 14" Dreis & Krump Leaf Type Bending Brake Motor Driven with 40 H.P. A.C. Motor.

CHARGING MACHINE

6000 lb. Brosius Floor Type Gasoline Driven Charging Machine. Equipped with Peel, Gas-oline Engine, Rubber Tires.

CRANE-GANTRY

ton Whiting Iwo Leg Gantry Crane 52 Ft. Span Cab Control. Three Motors 220 v. 3 ph.

CRANE-LADLE

75 ton Morgan Ladle Crane 49'6" Span 4-Gir-der, With 25 Ton Auxiliary, Complete with 230 Volt D.C. Motors.

FLANGING MACHINE

"McCabe Pneumatic Flanging Machine, Pneumatic Holddowns, Circle Flanging At-

FORGING MACHINE

" Ajax Forging Machine or Upsetter, Motor driven. Equipped with Air Clutch.

FURNACES-MELTING

400 lb. Moore Type "UT" Melting Furnace Top Charge. Complete with Transformer. New

0 lb. Moore type "U1" Metting Furnace top Charge. Complete with Transformer. New 1943—Little Used.

ton Heroult Model V-12 Electric Melting Furnace Top Charge hydraulically operated. Complete with Transformer Equipment.

ton Moore Size "NT" Melting Furnace, with 7500 KVA Transformer 13,200 vo. 3 ph. 60 cy.

HAMMER-COUNTER BLOW TYPE

35 ton Counter Blow Drop Forge Hammer Steam or Air Operated.

LEVELER-ROLLER

0" Aetna-Standard Roller Leveler, Motor Driven. 17 Rolls 4%" dia.

PRESS-BRIQUETTING

Model BL-350 Milwaukee Hydraullc Briquetting Press, Complete with Pumps. Capacity Grey Iron Briquettes 3½ tons per hr.

PRESS-KNUCKLE JOINT

1000 ton Bliss #27 Knuckle Joint, Embossing & Colning Press, 21/2" stroke, 18" Shut Height.

PRESSES-TRIMMING

1500 ton Hydraulic Bending & Trimming Press, Distance between columns 86" x 86", 2500 ton Hydraulic Bending & Trimming Press, Distance between columns 90" x 108",

ROLLING MILLS

OLLING MILLS
"x 10" Schmitz Single Stand I wo High With
Friction Drive Rewinder.
2/2" x 16" Philadelphia Two High Cold Rolling Mill. Complete with Pinion Stand, 75 H.P.
Motor 440/3/60. Starter and Controls, Incl.

Coiler

Coiler.

1" x 24" Waterbury Farrel Iwo Stand Iwo High Rolling Mill. Complete with Elec. Equip 1" x 60" Three High Roughing Mill. Complete with biller heating furnace and accessory equipment including electrical equipment. 7" x 56" United Iwo High Skin Pass Mill.

SAW

No. 749 Espen Lucas Heavy Duty Cold Saw Capacity up to and including cakes or slabs 48" x 7", Stroke 72", Motor Driven.

STRAIGHTENERS

o. O Medart Straightener—NEW 1952. Capacity 1/4" to 11/2" Bars, 2" Tubing.
o. 3 Medart 3-Roll Straightening Machine
Capacity 1" to 31/2" Bars or 41/2" O. D. Pipe Tubing, Machine

No. 3 Mean Capacity I' " to 31/2" I NEW 1950 Tubing.

or lubing. NEW 1750.

o. 18 Sutton Round Straightener, Motor Drive,
Capacity 3/16" to 34" O.D. Friction Drive
complete with 1/3 H.P. A.C. Motor,

TESTING MACHINE

20,000 lb. Southwark-Emery Universal Hydraulic Testing Machine. 300,000 lb. SOUTHWARK-EMERY Universal Hy-draulic Testing Machine.

UNIVERSAL IRONWORKER

No. 28U-30 Buffalo Armor Plate Universal Ironworker — Combination Punch, Shear & Bar Cutter. Motor Driven Capacities — Shear 3" Round, 2\%" Square, 5x1\%" Flat, 5x5x\%" Angles 12"—31\/2\pmu Beams, etc., Punch 1\/2" thru 1\/4".

RITTERBUSH & COMPANY, INC. 50 Church Street, New York 8, N. Y. The Clearing House

NEWS OF USED, REBUILT AND SURPLUS MACHINERY

Machinery Packaging - Faulty packaging is an old but still costly problem. The difficulties of packing machinery were discussed at a recent meeting of the American Assn. of Machinery Importers in New York, and the experiences of these traffic pros can be a useful guide to used machinery deal-

John Nevins, Jr., manager of terminal operations for the U.S. Lines, told the AAMI members that failure to mark crates correctly is one of the major causes of damage during cargo handling. He said modern materials handling units make it possible to move heavy industrial equipment without sliding it along floors or dropping the crates. But the advantages of these advanced handling techniques are lost if crates aren't properly marked. One result of incorrect crate marking is that wrong size winches are sometimes used, increasing the chances of damage to merchandise.

Sling Marks - In instances where machinery walks out of its case, it usually means the equipment was not properly secured. Mr. Nevins stated. He also stressed the importance of indicating the center of gravity on closed crates so handlers can tell where to place slings. An even better method is to mark the exact sling locations on the crates.

(

C

C

CI

DI

DI

G

G

Liq

Milton Thalberg, AAMI president, and sales manager, International Machinery Div., British Industries, Inc., said his firm sent a packaging check-list to its machinery manufacturers along with the original order. The check-list, which covers basic points needed to assure safe shipment, is filled out by the manufacturer when the machine is ready for delivery.

Included in the information requested on the form is the name of crater and the rust-proofing method used to protect the machine. The results have been excellent, he said.

By marking crates correctly, used machinery dealers can reduce considerably the cost, paperwork and time loss that result when equipment is damaged in transit. And dealers sidelining in imports of foreign machinery can eliminate many of their problems by sending their manufacturers detailed packaging instructions



APPROVAL SEAL: Milton Thalberg (left), president, American Assn. of Machinery Importers, and Fred Weil. AAMI director (center), show the association's new seal to Laurence Divine, U. S. Lines. Seal will be attached to all new machinery purchased in friendly European countries if importer can guarantee supply of parts in U. S.

CONSIDER GOOD USED EQUIPMENT

AIR COMPRESSORS

Y

es

9.9

is

ns

si-

a-

n-

nt

a-

th

st, ed

ed he

re-

of

ng

12-

ex-

lv.

ork ien

sit.

rts

mi-

by

de-

d in

AGE

14" x 12" Pennsylvania Air Compressor, 1003 Pressure, Complete with 75 H.P. Syn. Motor 18" & 11" x 14" Sullivan WJ-8 Air Compressor 885 CFM, Driven by 150 H.P. Westinghouse Syn. Motor 440/3/60

BAR TURNING MACHINE

Medart HF-2 Bar Turning Machine, Capacity 1" to 24". Complete with Accessories

BENDING ROLLS

ENDING ROLLS
9' x %" Ryeron Pyramid Type Bending Reli
16'x1%" Hilles & Jones Pyramid Type Bending Reli
30' x 1" Southwark Pyramid Type Bending Reli
30' x 1" Southwark Pyramid Type, Motor Driven
BRAKES—LEAF TYPE
3' x %" Drels & Krump Leaf Type Bending Brake
Motor Driven with 5 H.P. A.C. Motor
13" x 3/16" Chiese \$726 Steel Apron Brake, M.D.
16' x %" Drels & Krump Leaf Type Bending Brake, Motor Dr. with 40 H.P. A.C. Motor
Motor Dr. with 40 H.P. A.C. Motor
BRAKES—BRESS YUGA
BRAKES—BRESS YUGA
BRAKES—BRESS YUGA
BRAKES—BRESS YUGA RRAKES.

RAKES—PRESS TYPE
14' All Steel Hydraulic Press Brake 500 Ton Capacity,
10' 13'18' Dreis & Koure a 3/16" Dreis & Krump Press Brake, Complete ith Electrical Equipment

CHARGING MACHINE

CHARGING MACHINE

4000 lb. Broslus Floor Type Gasoline Driven Charging
Machine, Equipped with Peel, Buda Gasoline Engine, Rubber Tires

CRANES—GANTRY

5 ton Whiting Two Lag Gantry Crane 52' Span Cab
Control Motors 220 v. 3 ph. 60 cy.

15 ton PAH Two Leg Gantry Crane 45' Span With
12' Overhand one send 10' other end 5 ton Auxillary.
Two Trolleys and 8 Motors 440 volt 3 phase 60 cycle

CRANE—LADLE

75 ton Morgan Ladle Crane 49'6" Span 4-Girder
Construction, with 25 Ton Auxillary, Complete with
Motors for 230 Volt D.C.

CRANES—OVERHEAD ELECTRIC TRANELING.

Motors for 230 Voit D.C.

CRANES—OVERHEAD ELECTRIC TRAVELING
5 ton Robbins Myers 33'6" Span 230'8'68
10 ton Strict Strict

With 5 ton Auxiliary

DIEING MACHINES
75 ton Heary & Wright High Speed Dieing Machine
Double Roll Feed. Serap Cutter. 3" Stroke
100 ton Henry & Wright Dieing Machine, 4" Stroke
100 ton Henry & Wright Dieing Machine, 4" Stroke
13" Shut Height. Complete Elecl. Equip.

DIE CASTING MACHINE

Model HA-12 KUX Die Casting Machine, Air operated. Plunger Gooseneck Type for sine, lead and
tial. Die space between bars 124" "124" Die
Separates 8" NEW 1949, never used

DRAW BENCH DRAW BENCH

90 lb. Draw Bench, Motor Driven with 50 H.P. otor. Maximum Draw 40 ft.

FLANGING MACHINE
%" McCabe Pneumatic Flanging Machine, Pneumatic
Holddowns. Circle Flanging Attachment

Holddowns, Circle Flanging, FORGING MACHINES

FURNACE—ANNEALING
Furnace Engr. Co. Bell Type Annealing Furnace Gas
Fired. Operating Space 40"x40" Bound, 500 CFM
Capacity.
FURNACE—HEATING

FURNACE—HEATING

60 KW Leeds & Northrup Homo Furnace 29478-UB28, With controls. Work space 33" dis. x 33" deep

FURNACES—MELTING
400 lb. Moore Type "UT" Melting Furnace. Tep
Charge. Complete with Transformer. New 1948—
Little Used
6000 lb. E.I.S. Nose Tilting Furnace. Complete with
Transformer Equipment
15 ton Heroult Model V-12 Top Charge Hydraulically
Operated. Complete with Transformer Equip.

GFAR BEDUICERS

Operated. Complete with Transformer Equip.

GEAR REDUCERS
500 H.P. United Combination Reduction Gear & Pinion
Stand. Gear Ratio 8.581:1
600 H.P. Farrel Birmingham, Size 18 Reduction Gear,
Ratio 720 to 244 RPM
700 H.P. Falk Single Reduction Gear, Ratie 875 to
200 RPM
1800 H.P. Mesta Gear Reduction Unit, Ratie 19:1
GDININE

GRINDER

No. 4 Cincinnati Centeriess Grinder, Motor Driven.
Capacity standard work rest 3" to 6" dia., optional
work rest 1," to 3". Special fixtures will allow
work to be handled up to 9" dia.
GRINDER—CYLINDRICAL
14 x 55" Norton Type C. Complets with Elect. Equip.

HAMMERS-BOARD DROP

HAMMER—COUNTER BLOW TYPE

\$5 ton Counter Blow Drop Forge Hammer. Steam or Air Operated
HAMMER—STEAM DROF

| MAMMER | SIEAM PORGING | 1500 lb. Erie | MAMMERS | STEAM FORGING | 1200 lb. Massillon Single Frame | 1500, 1800, 2000, 3000, 4000, 6000 lb. Chambersburg | 1500, 1800, 2000, 2000, 2500, 2500, 4000 Erie | 1500, 2000, 2000, 2500, 2500, 4000 Erie | 1500, 2000, 2500, 2500, 4000 Erie | 1500, 2000, 2500, 4000 Erie | 1500, 4000,

HAMMERS-MISCELLANEOUS

No. 6N Nazel Hammer, Geared Motor Drive 200 lb. Bradley Compact Hammer, Arr. for Motor Drive with 10 H.P. A.C. Motor 2000 lb. Chambersburg Pneumatie Hammer Complete with Elect. Equip. New 1951 15"x12" Chambersburg Cecostamp Hammer, 18" stroke

LATHE—TURRET

Model 2L Glabolt Geared Head Turret Lathe, Spindle
Bore 4-1/16". Elect. Equipment and numerous
accessories incl. NEW 1951

LEVELER—ROLLER
69" Astan Standard 17-Roll Leveler, 4%", Dia. Rolls
Arr. Motor Drive

KOTOR\$
1350 H.P. Westinghouse Induction Motor 6600 voit
3 phase 60 cycle 593 R.P.M.
2000 H.P. General Elec. Induction Motor 8600 voit
3 phase 60 cycle 600 R.P.M.
2500 H.P. General Elec. Direct Current Motor 6600
voit 175/350 R.P.M.

MOTOR GENERATOR SET

0 H.P. General Electric Syn. Motor 4400 volt A.C. with two generators 750 KVA 230 volt D.C., Complete with Panel Roard atc.

Nall MAKING MACHINES

Na. 1 1/4 National—Sizes 10D, 12D, 16D, 20D, 30D

No. 3 National—Size 6D, 7D, 8D, 9D

Angell—Sizes 10D, 12D, 16D, roofing

PRESSES-EXTRUSION

RESSES—EXTRUSION
700 tom Horizontal Extrusion Press, 3-Column Type
Ram 26" Diameter, Container suitable for billets
5" x 20"
1200 ton Horizontal Extrusion Press, 3-Column Type
Ram 34" Diameter, Suitable for billets 6" dia. x
22" long

WE OFFER A COMPLETE LIQUIDATION SERVICE ON ANY BASIS WHICH CIRCUMSTANCES INDICATE WOULD BE MOST BENEFICIAL, WHETHER BY AUCTION, PRIVATE LIQUIDATION OR OUTRIGHT SALE

CONSULTANTS IN MANUFACTURING PROBLEMS FOR OVER A QUARTER OF A CENTURY

THERE IS NO SUBSTITUTE FOR EXPERIENCE

CONTACT US IN CONFIDENCE WITHOUT COST OR OBLIGATION

PRESSES-HYDRAULIC

RESSES—HYDRAULIC

Model BL-350 Milwaukee Hydraulic Briquetting Press
Complete with Pump. Capacity Grey Trom Briquettes
3½ tons per hr.
75 ton Williams White Straightening Press 27"
Stroke, Bed 8' x 16". 6½ " Dis. Ram
200 ton Bliss Hydrodynamic 48" Stroke Bed Area
24" x 24", Hyd. Pump Incl.
500 ton Southwark Hydraulic 24" Stroke, 78" Daylight Platen 64" R to L x 32" F to B
500 ton Southwark Hydraulic 24" Stroke, 78" Daylight Platen 58" x 56"
Nitroke Platen 58" x 56"
700 ton Elmes Forming Press, 27" Stroke, 30" Dia.
Ram, Platen 40" x 88" with overlang 40" x 123".
Complete with Pump and Motor

RESS—HYDRAULIC WHEEL

Complete with Pump and Motor

PRESS.—HYDRAULIC WHEEL

100 ton Elmes Inclined Hydr. Wheel Press 72" Between Parallel Bars. Complete with Pump & Motor

PRESS.—KNUCKLE JOINT

\$27 Bliss Knuckle Joint Embossing & Coining Press

1000 ton Capacity, 2%" Stroke, 18" Shut Height

1000 ton Capacity, 2% Stroke, 18 Shut Height PRESSES—STRAIGHT SIDE
No. 305 Bliss 9" Stroke 14" Shut Height Equipped with Marquette Air Cushion
No. 59 Toledo Double Gerred Tie Bod Press 255 ton
Friction Clutch 18" Stroke 36% x 85" Bed Ares
No. 3 Ferracute Super Speed Funch Press 30 ton
Capacity, NEW 1946—never used
No. 620 Bliss High Production Press, 1% Stroke
S1-40 Verson 300 ton Orress, 30" Stroke Bed Ares
40" x 44"
No. 12 Zeb & Hahnemann Patent Percussion Press
150 ton 12" Stroke, 17" x 17" Bed Ares
No. 1037-% Hamilton 360 Ton 18" Stroke Bed Ares
48" x 104"
PRESS—TOGGLE DRAWING.

48" x 184"

PRESS.—TOGGLE DRAWING

No. 410A Bilas 656 Ton Double Crank Strokes 25"
& 17" Bed Ares 80" x 84"

PRESSES.—TRIMMING
Bilas 8.8. Trimming Press with Side Shear, 256 Tun
Capacity, 8" Stroke 52" x 30" Bed Ares

No. 3 Erie Flywhen Drive Trimming Press, 3%"
Stroke 12" Retween Guidee
1500 ton Hydraulic Bending & Trimming Press.
Lince between columns 86" x 86"
2500 ton Hydraulic Bending & Trimming Press.
Distance between columns 90" x 108"

PUNCH—BEAM

Long & Allstatter Double End Heam Punch, Capacity
Beam Punch End—Punch flanges and web 24" I-

PUNCH & SHEAR COMBINATIONS

No. 28 U-30 Buffalo Armor Plate Universal Ironworker. Capacity Punch 1%; then 1%; Bhear 3;

Tound 3%; Square. 3 x 1%; Flat. 5 x 5%; Angles
Style EF Cleveland Single End Punch & Shear, M.D.
Capacity Funch if the 1%;

RIVETER
125 ton Hanna Bull Riveter, Air Driven, 24" Gap, 75"
Reach, Capacity 1" rivets cold and 11/4" rivets how

ROLL—PLATE STRAIGHTENING
7 Roll Bertsch Plate Straightening Machine, Capacity
10' x % Complete Elect. Equip.

ROLLING MILLS

1½" Stockel Four High Rolling Mill, Max. Steel

1½" Stockel Four High Rolling Mill, Max. Steel

Width 6" Work Holis 2½" x 7½", Complete with
electrical equipment

8"10" Schmits Single Stand Two High

12"116" Single Stand Two High, Comp. with Elect.

12":16" Single Stand Two High, Comp. with Elect.
Equip.
12":12" Waterbury Farrel Two High
15":12" Mossberg Single Stand Two High
18":24" Waterbury Farrel Two Stand Two High
18":24" Waterbury Farrel Two Stand Two High
20":356" Poole Two Stand Two High
22":410" Single Stand Two High
22":410" Single Stand Two High
22":410" Single Stand Two High
18":16" United Two High Skin-pass Mill
18":16" Three High Roughing Mill, Complete with
billet heating furnace and accessory equipment inel.
elect. equip.

SAWS

No. 749 Espen-Lucas Heavy Duty Cold Saw. Capacity
up to and incl. cakes or slabs 48" x 7", Stroke 72",
Motor Driven

Notation Saw 54" Blade Hydraulte

Motor Driven
No. 3 Ryerson Friction Saw, 54" Blade Hydraulis
Feed, Complete with Eleel. Equip.
52" Ryerson Friction Saw, 45 H.P. Moter, Capacity
Approx 9" Round, 20" 1-beam, 12" H-beam

SHEAR-ALLIGATOR

SMEAR—ALLIGATOR
No. 7 Thomas Carlin Alligator Shear, 16" Blade
30 H.P., D.C. Motor
SHEARS—ANGLE
Hilles & Jones No. 2 Double Angle Shear, M.D.
Capacity 6" x 6" x %",
Long & Allistatter Double Angle Shear, Model B
Capacity 53574", Complete with Elect. Equip.

SHEAR—BAR
No. LH Lewis Open End Bar Shear, Moter Drive
Capacity 11/3" Round

Capacity 1%" Round
SHEARS—ROTARY
No. 60 Quickwork Rotary Shear, %" Capacity
No. 100 King Rotary Shear, 1" Capacity
No. 30 Quickwork Itotary Shear 5/16" Capacity
Quickwork Heary Duty Circle Shear %" Capacity
Complete with Circle Cutting Attachment
No. 25 A Quickwork Whiting Rotary Shear 14" Capacity,
with Circle Cutting Attachment, Motor
Driven

SHEARS—SQUARING

12'x3/16" Stameo Steel Squaring Shear, Motor Dr.
8'x '4" Drabert Model THZ 8/2500
6'x '4" Long & Allstatter, Belted Motor Driva

LITTERS

24" Torrington Heavy Duty Slitter, Capacity 5 cuts

36" mild steel

31" Yoder Sheet Slitter No. 530, Capacity 8 cuts .194"

to 8 Cuts .156", Motor Dr.

73" Yoder Gang Slitter, Capacity 5 Cuts 30 Gs.

73" Yoder Gang Slitter, Capacity 5 Cuts 30 Ga.

STRAIGHTENERS

No. 0 Medart Bound Straightener. Capacity %"—1%"
bars, 2" tubing. NEW 1852

No. 3 Medart 3-Roll Straightening Machine Capacity 1" to 3%" bars or 4%" O.D. Pipe or Tubing. NEW 1850

No. 1%B Sutton Round Straightener, Moter Dr. Capacity Tubing 5/10" to 3%"—modified to handle up to 3%" O.D. Lubing.

No. 18 Sutton Round Straightener, Moter Drive Capacity 3%" O.D. Lubing.

No. 18 Sutton Round Straightener, Moter Drive Capacity 3%" O.D. Friction Drive complete with 1/3 H P A.C. Motor With 1/3 H P A.C. Motor Palides 8-Roll Strip Straightener & Cutting Machine. Capacity 14" wide 11 Ga. Sheet Steel

STRETCHER

STRETCHER

cKay Hydraulic Bar Stretcher. Capacity up to 1%" dia. in length 12' to 27'

SWAGING MACHINES
No. E4 Langeller, Capacity 1%" Tubing
No. 408 Etna Swager, Capacity 4" Tubing

TESTING MACHINES

300,000 S Bauthwark Emery Universal Hydraulic 20,000 lb. Southwark Emery Universal Hydraulic THREAD ROLLER

odel "C" Watson Flagg Precision Thread Roller Capacity up to 3", Incl. Accessories & Electrical Equipment

WELDERS

FELDER'S

230 KVA Progressive Model A-6 Flash Welder 446
voli 60 cycle. Mechanical Contactor Hi-Pressure
Clamp Assembly-NEW 1949

40,0003 Ransome Welding Positioner. Rectangular
Table 84" x 84" x 15",
McKay Tube or Pipe Welding Unit, Capacity 4%"
to 7¼" 0.D. Complets with all accessory equipment and motors

wire Drawing MACHINE
No. 0 Waterbury Farrel 7-Die Wire Drawing Machine.
Capacity % " red to #10 copper

· Manufacturing

RITTERBUSH & COMPANY, INC. 50 CHURCH ST. NEW YORK CITY 8

Consulting Engineering Service Surplus Mfg. Equipment Inventories Purchases

MILES' QUALITY AIR COMPRESSOR, 21"x13"x16" Worthington

AIN COMPRESSUR, 217x137x167 Worthington
AUTOMATIC, 207x257 Fay (1942)
AUTOMATIC, 87 Bullard Multi-Au-Matic, 6-spindle
AUTOMATIC, 6-spindle Baird chucker
AUTOMATIC, 31/4 & 33/4 Cleveland "A"
BORING MILL, 47 Detrick & Harvey, horizontal, BORING MILL, 4" Detrick & Harvey, horizont floor type
BROACH, No. 1 Foote Burt duplex surface
BROACH, No. 2 No Oligear horizontal hydraulic
BROACH, No. 3XA Oligear horizontal hydraulic
BROACH, No. 32A Oligear horizontal hydraulic
BROACH, V42 American hydraulic, 18 ton
BULLDOZER, No. 22 Williams & White
DRILL, No. 36 HO Baker hydraulic
DRILL, No. 36 HO Baker hydraulic
DRILL, 12-spindle No. 12 Natco
DRILL, 12-spindle No. 10 Defiance rail type
DRILL, No. B 250 H Natco multiple
DRILL, 36-spindle Baush, adjustable spindle DRILL, No. B 250 H Natco multiple
DRILL, 36-spindle Baush, adjustable spindle
DRILL, RADIAL, 3/2*, 8" American sensitive
GEAR HOBBER, No. 124 G&E
GEAR HOBBER, No. 130 Cleveland Rigidhobber
GEAR HOBBERS, No. 3 Adams Farwell
GEAR HOBBERS, No. 12 & Type A Barber Colman
GEAR HOBBERS, No. 12 & Type A Barber Colman
GEAR HOBBERS, No. 1 and 25 5A Lees Bradner
GEAR SHAVER, 8"-12" Red Ring
GRINDERS CENTERLESS, Two No. 2 Cincinnati,
GRINDERS, 10" x 18" & 10" x 36" Norton SemiAuto Auto

Auto
GRINDER, DISC. 30", No. 8 Badger
GRINDER, DISC. No. 228 Hancshett opposed
GRINDER, DISC. No. 84A Gardner opposed
GRINDER, GEAR, 10" Pratt & Whitney
GRINDER, Internal. Bryant Nos. 5, 16A, 16-28 & GRINDERS, INTERNAL, Nos. 72A3 and 72A5

GRINDERS, INTERNAL, Nos. 72A3 and 72A5 Heald
GRINDERS, SURFACE, 12" and 16" No. 22 Healds
GRINDER, SURFACE, No. 78 Wilmarth & Morman
HAMMER, Nos. 5N & 6B Nazel pneumatic
HAMMER, Nos. 5N & 6B Nazel pneumatic
HAMMER, 40 lb. Bradley helve
HONE, Nos. 172 & 2610 Barnes hydraulic
LATHE, ENGINE, 24"x14" American
LATHE, TURRET, No. 5 Acme universal
LATHE, TURRET, No. 5 Gisholt universal, 1943
LATHE, TURRET, No. 5 Gisholt universal, 1943
LATHE, TURRET, No. 2 Gincinnati plain
MILLER, Tow No. 2 Cincinnati plain
MILLER, 18" Cincinnati automatic
MILLER, 18" Cincinnati automatic
MILLER, 18" Cincinnati automatic
MILLER, 1904 45 Product-0-Matic
MILLER, 30%" x 21" x 12" Ingersoll 4-spindla
planer type
MILLER, 48" x 20" x 20' Ingersoll planer type,
3 vertical heads
MILLER, 84" 1ngersoll 6-spindle rotary continuous
MILLER, 84" Ingersoll 6-spindle rotary continuous

AUI, Fall MILLER, 84" Ingersoll 6-spindle rotary continuous MILLER, PLAIN, No. 3B Milwaukee MILLER, THREAD, Type C Hall planetary MILLER, THREAD, Nos. 4, 6 and CT 36 Lees

MILLER, THREAD, Nos. 4, 6 and CT 36 Lees
Bradner
MIBBLER, No. 3 Savage rotary
PLANER, 36"x36"x12" Niles Bement Pond
PRESSES, Nos. POJ. Pl. P2, P3, PA4, P5 and
CA4 Ferracute
PRESS, No. 61 Cleveland OBI
PRESSES, No. 65 Toledo OBI
PRESSES, No. 65 Toledo OBI
PRESSES, No. 65 Toledo OBI
PRESSES, No. 654 Ferracute knuckle Joint
PRESS, No. 245½ Hamilton s.s. therod frame
PRESS, No. 2654 Ferracute knuckle Joint
PRESS, No. DA8411 Hamilton double action toggle
PRESS, No. DA8411 Hamilton double action toggle
PRESS, 100 ton HPM hydraulic
RIVETERS, large variety
ROLL, 20"x3/16" Farnham bending
SLOTTER, 16" Bement Miles crank
SAWS, Three 816S Kalamazoo metal cutting band
SAW, 7" No. 14 Higley cold-cutting
SHAPER, 16" Bement Miles crank
SAWS, Three 816S Kalamazoo metal cutting band
SAW, 7" No. 14 Higley cold-cutting
SHAPER, 24" Ohio Dreadnaught
SHAPER, 22" Morton draw cut
SHEAR, 38" throat No. 17F New Duty
STRAIGHTENER, No. 0 Sutton for bars
SWAGER, No. 154 Etna
TAPPERS, Two No. 71 Ettep
TAPPERS, Two No. 71 Ettep
TAPPER, 19" Hammond sensitive drilling & tapping
TESTER, 230,000 inch-pound Tinius-Olsen No. 2
torsion

TESTER, 250,000 ib. Richle tensile & compression torsion TESTER. 100,000 ib. Richle tensile & compression THREADERS, 2" Landis pipe threading and cutting THREADERS, Two 34" Landis, double spindle THREADERS, 2" Oster rotary head UPSETTER. 3" National air clutch UPSETTER. 3" National air clutch UPSETTERS, Two 4" Ajax heary duty, twin-gear WELDER, 100 KVA Thompson automatic spot WELDER, 100 KVA National Flash WELDERS, 12" and 14", 12 KVA American Electric Fusion Co. spot.

WRITE FOR CATALOG NO. 193 FOR COMPLETE LISTING

MILES MACHINERY CO.

2025 E. Genesee Ave. SAGINAW, MICHIGAN RE-NU-BILT

ELECTRIC POWER EQUIPMENT

		D.0	C. MOTORS		
Qu.	H.P.	Make	Type	Volta	
1	2200	G.E.	MCF	600	400/500
1	1750	White.		600	550/740
1	1500	Whse.		525	600
- 1	940	Whae.	QM	250	140/170
1	600	Al. Ch.		250	400/800
2 1 1	500	Whise.	CC-216	600	300/900
2	450	Whse.		550	415
1	400	G.E.	MCF	550	300/1050
1	350	Cr. Wh.	CCM-151H	230	1100
1	335	Whse.	MQ	250	300/900
1	200/300	G.E.	MPC	230	360/920
1	200	Rel.	1970T	230	720
1	150	G.E.		600	250/750
1 1 1	150	Rel.	1400 T	230	400/1200
	150	Cr. Wh.	65H	250	1150
10	150	Cr. Wh.	83H-TEFC	230	960
2	150	Whse.	SK151B	230	900/1800
1	150	Whse.	8K-201	230	360/950
2	50/120	G.E.	MCF	230	250/1000
2	100	Whae.	SK-181	230	450/1000
1	100	G.E.	CDP-115	230	1750
		MI	LL & CRANE		
1	50	G.E.	CO-1810	230	725
1	33	Whae.	K-8	230	505
1 1 2 1 4 8 1 8	30	G.E.	MD-104% A.	A 550	700
1	20	Whse.	IX - 5	230 230	975
4	15	Whae.	K-5	230	630
8	10	C.W.	SCM-AH	230	1150
1	10	G.E.	MD-104	230	400/800
	6.25	Whse.	K-3	230	680
- 4	3	C.W.	SCM-FF	230	1750
3	3	Whae.	HK-2	230	835
1	214	Whee.	K-1	230	835

A.C. MOTORS

3 phase-60 cycle

		SL	IP RING		
Qu.	H.P.	Make	Type	Volts	Speed
1	1800	G.E.	MT-498	2300	360
1	1500	ABB		2300	720
1	1200	O.E.	MI,	2300	275
1	500	Whee.	CIL	550	350
1	500	G.E.	IM	440	900
1	500	G.E.	M-574-Y	6600	900
1	500	G.E.	1P	550	505
1	400	Whae.	CAL	410	514
1	350	G.E.	MT-442Y	2200/4000	
1	800	Al. Ch.		440	505
	250	G.E.	MT-424-Y	4000	257
1	250	G.E.	MT-5598	2200	1800
	250	Al. Ch.	NI 1 -0300	550	600
1	200	Cr. Wh.	260B	440	565
3	200	G.E.	13117	550	585
8	200	G.E.	131-17	440	non
1	200	G.E.	131	440	435
î	200	G.E.	MTP	440	1170
í		ised) Whee.	CW	2300	
î	125	Al. Ch.	C 22	440	435
4	125	G.E.	MT-566Y		720
2	100	G.E.	1M	440/2200	
5	100	17. E.		410	609
1	100	A.C. G.E.	ANY	440	695
1	100	White.	TM-16 CW-868A	2200	435
T	100			440	700
			RREL CAGE		
2	650	G.E.	FT-559BY	440	3570
3	450	Whae.	CS-1420	2300/4150	
1	300	Al. Ch.		2200	385
1	200	G.E.	IK-17	440	580
1	200	G.E.	115	440	865
8	200	G.E.	KT-557	440	1900
1	150	Whee.	FS 8568	440	9×0
1	150	Whee.	CS	440	586
1	150/75	G.E.	IK	440 90	007450
8	125	Al. Ch.	ARW	2200	1750
1	125	G.E.	KF-6328-Z	440/2200	
1	125	White.	318	440	485
		SYNO	CHRONOUS		213,7
2	8500	G.E.	TS	2300	957
2	2100	G.E.	ATT	2200	200
3	1750	O.E.	ATI	2300	3600
2	2000	Whse.	WII	2300	120
	735	G. 16.	ATI	2200/1200	
1	450	Whee.	WIL	2200/1200	430
9	950	C E	TPO	9900	4.50

2 850 G.E. TS 2200 150

	MI-	b Sels -	-3 P	h. 60 C	Y.
Qu.	K.W.	Make	RPM	D.C. Volts	A.C.
3	2000	G.E.	500	660	11000*
1	2000	G.E.	514	600	6600/13200
8	1500	G.E.	514	250	6600/13200
1	1500	G.E.	720	600	6600/13200
1	1500	G.E.	360	275	4400
-	1500	G.E.	600	600	4160
3	1000	Whse.	900	600	4180
1	1000	G.E.	900	280	6600
1	1000(311)	G.E.	900	250	2200
1	750	Whise.	900	275	4160
1	500	G.E.	720	125	2300
1	500	Whee.	900	125/250	440
1	500	Whse.	900	250	6600/13200
1	500	Whee.	1200	125/250	2300
1	400	Whee.	1200	250	2300
1	400 (377)	Cr. 7771.	1200	125/250	2300
1 1	858	G.E.	900	125	2300/4160
1	200	Al. Ch.	1200	125/250	2300
1	150	Whee	1200	275	2300
1	140(31)	Cr. 77h.	690	125/250	440/2300
1	100	Delco	1200	120/240	2300
1	100	G.E.	1170	125	220/440
. 2	Cycle				

FREQUENCY CHANGER SETS

Qu.	KW	Make	Freq.	Voltages
1	3000	G.E.	25/60	2300/2300/4000
9	2500	G.E.	25/62,5	2300/2300
1	1000	G.E.	25/58.8	4400/2300
1	500	Al. Ch.	2560	11000/2300

BELYEA COMPANY, INC.

47 Howell Street, Jersey City 6, N. J.

CIMCO MACHINE TOOLS AT BARGAIN PRICES

Giddings & Lewis 4" bar boring mill
King 42" Vertical Boring Mill, 2 heads
Niles 36-44 Vertical Boring Mill, motor driven, I rail and
I side head
Concinnati = 3 Vertical Mill, single pulley drive
Niles 42"-50" Burnisher, Facer and Box Borer, late type,
motorized
Cincinnati-Bekkord 4"11" column Radial gear box on base.
Festlew 6"15" Radial Drill
Fellows 612 Spur Gear Shaper
Columnati 24" Back Geared Shaper
Columbia 28" Back Geared Crank Shaper
Gould 4. Eberhardt 16" Back Geared Shaper
Gould 4. Eberhardt 24" Back Geared Shaper
Gould 4. Eberhardt 24" Back Geared Crank Shaper
Gould 4. Eberhardt 28" Back Geared Crank Shaper
Gould 4. Eberhardt 26" Back Geared Crank Shaper
Gould 4. Eberhardt 26" Back Geared Crank Shaper
Gould 4. Eberhardt 32" Back Geared Crank Shaper
Gould 4. Eberhardt 60BM Gear Rougher
Cincinnati = 2 Centerless Grinder
Fitchburg 48" Spline Grinder, late
Heald = 50 Internal Grinder, late
Heald = 50 Internal Grinder
Heald 70A Internal Grinder, late type
Heald 78 Centerless, Internal & Cylindrical Grinder
Jones 6. Lamson 8 x 31 Thread Grinder
Landis 26" x 108" Plain Cylindrical Grinder
Landis 7 Type C Plain Grinder, late type
Landis 16" x 72 Plain Grinder, late type
Sellers 4T Tool Grinder, late type
Oster 601 Rapiduction Turret Lathe
Jodge 6 Shipley, 16" x 126" centers, Timken bearing, late
type, complete with taiper attachment
Lodge 6 Shipley, 16" x 126" centers, Timken bearing, late
type, complete with taiper attachment
Lodge 6 Shipley, 16" x 126" centers, Timken bearing, late
type, complete with taiper attachment
Lodge 6 Shipley, 16" x 126" centers, Timken bearing, late
type, complete with taiper attachment
Lodge 8 Shipley, 16" x 126" centers, Timken bearing, late
type, complete with taiper attachment
Lodge 8 Shipley, 16" x 126" centers, Timken bearing, late
Type, complete with taiper distance, taper attachment
Lodge 8 Shipley, 16" x 126" centers, Timken bearing, late
Type, complete with taiper a



This Is A Partial Liss Of Our Stock. Send Us Your Inquiries.

CINCINNATI MACHINERY COMPANY, INCORPORATED 209 E. Second Street CINCINNATI 2. OHIO

Barber-Colman Model 5 Gear Hobbers. Gleason 3" Straight Bevel Gen. 1942. Hardinge Model MD47 Bench Lathes, 3/4". Thomas No. 6A O.B.I. Press, 1947.

D. E. DONY MACHINERY CO. Rochester 9, N. Y. 47 Laurelton Road

FLANGERS. 3,3" & 1,2" McCabe (2)
RADIAL DRILL, 5' 15" Col. Amer. Tri. Purp., M.
RADIAL DRILL, 5' 14" Col. Amer. Tri. Purp., Gear
RADIAL DRILL, 3' 2' Morris, 9½" col.
LATHE, GAP, 28 50" x 16' Rahn Larmen M.D.
LATHE, 14" x 6' Bed Amer., T.A., M. D.
LATHE, 14" x 6' Bed Amer., 18", Sw., T.A., M.D.
SLOTTER, 20" Bement Miles. M.D.
LETCHER W. BENNETT & SONS

P. O. Box 544 CLIFTO PHONE—PRESCOTT 9-8998 CLIFTON, N. J.

RAILROAD EQUIPMENT — FOR SALE

USED

AS IS

RECONDITIONED

STANDARD GAUGE FREIGHT CARS

Box, Double Sheathed, 50-Ton Capacity Box, Single Sheathed, 50-Ton Capacity Gondolas, Composite, 40-Ton Capacity Gondolas, Composite or All-Steel, 50-Ton Hoppers, Covered, All-Steel, 70-Ton Hoppers, Twin, All-Steel, 50-Ton, Cross Dump Hoppers, All-Steel, 70-Ton, Cross Dump Tank, 3,000-Gallon, High Pressure Tank, 8,000-Gallon, Coiled and Non-Coiled

EXTRA LONG FLAT CARS

40 & 50-Ton Capacity, Length 70' and 74'

CABOOSE CARS Eight Wheel, Cupola Type

OTHER EQUIPMENT **Locomotive Cranes Overhead Cranes**

STANDARD GAUGE AIR DUMP CARS Side Dump, 20-Yd., 40-Ton, Lift Door End Dump, 20-Yd., 50-Ton, Drop Door End Dump, 10-Yd., 30-Ton, Lift Door

Railroad Track Scales

STANDARD GAUGE DIESEL-ELECTRIC ROAD SWITCHING LOCOMOTIVE

1500 H.P., 120-Ton, Type 0-4-4-0

Send us your inquiries

We Buy Freight Cars for Dismantling

Send us your offerings

IRON & STEEL PRODUCTS, INC.

REPAIR PARTS All Types of Freight Cars

General Office 13496 S. Brainard Ave. Chicago 33, Illinois

New York Office 50-b Church Street Phone: BEekman 3-8230 Phone: BAyport 1-3456 New York 7, N. Y. "ANYTHING containing IRON or STEEL"

STORAGE TANKS 6,000 Gallon 8,000 Gallon 10,000 Gallon

Castern Rebuilt Machine Tools THE SIGN OF QUALITY—THE MARK OF DEPENDABILITY

HAND MILLING MACHINES

chuck

rning.

, fate

drive

meter

List d Us

3/4".

M.D.

. J.

AGE

No. 3 Garvin, m.d. No. 1 U. S. Hand Miller, m.d.

MANUFACTURING TYPE MILLING MACHINES

MANUFACTURING TYPE MILLING MACHINES

No. MM-1-6 U. S. Multi-Miller, m.d.
Rowbottom Cam Milling Machine
Model 1403 Milwaukee Simplex Production Milling Machine, m.d.
3A Sundstrand Copy Rigidmill, m.d.
Type F Ohio Mfg., m.d.
4" Pratt & Whitney Spline, m.d.
No. 33 Kempsmith, s.p.d.
18", 24" Cincinnati Plain Automatic, m.d.
18", 24" Cincinnati Plain Automatic, m.d.
No. 21 Brown & Sharpe Automatic, s.p.d.
48" x46" x120" Ingersoll Fixed Rail Milling Machine, for tank work.
48" x16" Newton Stab Miller, m.d.
54" x 30" x 17" Ingersoll Stab Miller, m.d.

PLAIN MILLING MACHINES

PLAIN MILLING MACHINES
No. 0 Brown & Sharpe, cone
No. 1B Milwaukee, m.d.
No. 1M Cincinnati, m.d.
No. 1 Brown & Sharpe, cone, motorized
No. 3 Yan Norman Duplex, s.p.d.
No. 3B Milwaukee, m.d.
No. 2 Rockford, m.d.
No. 2G LeBlond, belted m.d.
No. 4 Ohio, cone

THREAD MILLING MACHINES

Hall Planetary, m.d.

6x14", 6x20", 6x48", 6x80" Pratt & WI
10x24" Hanson Whitney, m.d., latest 6x80" Pratt & Whitney

SURFACE GRINDERS

Arter Model A-1-8" Rotary, m.d. No. 16—26" Blanchard Vertical, m.d. No. 121 Hanchett Production Face Grinder, type No. 121 Hanchett Production Face Grind BD, m.d.
No. 22—12" Heald Rotary, m.d.
No. 33 Abrasive Vertical, m.d.
No. 260—16" Heald Rotary, belt
14" Pratt & Whitney Vertical, m.d.
22" Pratt & Whitney Vertical, m.d.
84" Diamond H.D. Face Grinder, m.d.
No. 3 Abrasive, &x18" Magnetic chuck
Model DA—12" O.S. Walker, m.d.

TOOL & CUTTER GRINDERS

12x72" Thompson Automatic Flat Broach Grinder, m.d., late Gleason Cutter, m.d. No. 28 Sellers, m.d. No. 2 Lumsden Oscillating Tool Grinder, belted m.d. m.d.
No. 47 Sellers Tool, m.d., latest
No. 1 J & 8 Tap Grinder, m.d.
Pratt & Whitney Deep Hole Drill Sharpener, m.d.
Gould & Eberhardt Gear Cutter Grinder, 2 step
cone pulley belt drive
Sellers Wet Drill Grinder, m.d.
Gisholt Universal Tool Grinder, belt
No. 51 Oliver Drill Pointer, motor driven
No. 1 Le8lond Tool & Cutter Grinder, belted
m.d. No. 91A Covell Tool & Cutter, m.d.

UNIVERSAL MILLING MACHINES

No. 2A Brown & Sharpe, s.p.d. No. 3 Kempsmith, cone No. 4 Cincinnati, m.d.

VERTICAL MILLING MACHINES

Sundstrand Rigidmill, m.d., vertical spindle
No. 08 Cincinnati, m.d., late
No. 3V Toledo, s.p.d.
No. 6 Becker, cone
Newton Vertical Miller, rotary table
54" Ingersoll Single Spindle Adjustable Rotary
Mill, m.d.

MILLING MACHINE ATTACHMENTS

16" Cincinnati Circular Milling Table, p.f.
Kearney & Trecker Attachment for Milling Bridge
Reamers, 62" long x 24" wide
11/4" Cincinnati Rack Mill. Attach. for No. 3
Dial Type Miller
Vertical Attachment for Milwauxee Mfg. Type
Miller
Cincinnati Vertical Attachment

Cincinnati Vertical Attachment for use on latest type No. 2L or 2MH rectangular overarm Millers

Millers
16" Kearney & Trecker Rotary Table, p.f.
16" Cincinnati Rotary Table, p.f.
20" Rotary Table for 4H Milwaukee Vertical
Miller
Rack Cutting Attachment for No. 4 Cincinnati
High Power Miller, s.p.d.
36" Cincinnati Power Feed Rotary Table

PIPE MACHINES

2" Forbes Type Curtis & Curtis Pipe Machine, m.d.



EASTERN MACHINERY COMPANY

We carry an average stock of 2,000 machines in our 11 acre plant at Cincinnati. Visitors welcome at all times.

1002 Tennessee Avenue, Cincinnati 29. Ohio

THE CLEARING HOUSE

GUARANTEED TOOLS

16"x78" SIDNEY Toolroom Lathe, chuck,

60"x20" NILES-BEMENT-POND Geared Head Engine Lathe, rapid traverse

27"x12" MONARCH Geared Head Englee Lathe, taper attachment, AC-MD

24"x72" centers BOYE & EMMES Hea Geared Head Engine, chuck, AC-MD

No. 28 FOSTER Geared Head Turret Lathe, rapid traverse, AC motors

No. 3L GISHOLT Turret Lathe. 61/4" hole in spindle, bar feed, chuck, tooling, new 1945

42" BULLARD New Era Type Vertical Turret Lathe, AC-MD

36" BULLARD Vertical Turret Lathe converted to Spiral Drive, AC-MD

1½" LANDIS Double Head Bolt Threader, with leadscrews, MD

i DOUGLAS Plain Horizontal Milli, e 8"x32", power feeds, motor in base, 40 taper, new 1942

No. 2 VAN NORMAN Plain Horizontal Mill, power rapid traverse, No. 50 taper, new 1942

No. 3-24 CINCINNATI Plain Hydromatic

5-13" column CARLTON Radial Drill AC motor on arm, 15 to 1500 RPM

AMERICAN High Speed Sensitive Radial

No. 914 W. F. & John BARNES Hydraulic Drill, No. 6 Morse taper, 15HP motor, new

3 Spindle FOSDICK Drill Press, Individual AC motors for each spindle, 1942

No. 6 TOLEDO O.B.I. Press, 56 Tons

Brand New Model FH-4C01 DENNISON Hydraulic Presses, 4 Ton. 8" throat (3)

10"x24" NORTON Hydraulic Surface Grinder, 1942

25A HEALD Rotary Surface Grinder, 24" diameter, magnetic chuck

36" OHIO Dreadnaught Shaper, AC-MD

75 Ton HENRY & WRIGHT Double Crank Dieing Machine, roll feed & Scrap cutter

No. 22 MURCHEY Threader

No. 135 CLEVELAND Rigidhobbers



6' American Radiai Drili—Seriai \$55592
\$81A Felicus Gear Shaper—Seriai \$21252
\$83 Gishelt Yuret Lethe—Seriai \$22252
\$83 Gishelt Yuret Lethe—Seriai \$22807-1
16" Gould & Eberhardt Shaper
90" Hanchett Face Grider
Lodge & Shipley Lathe—Seriai \$29051
\$2 Norten Teel & Cutter Grinder—Seriai \$3855
8D Potter & Johnston Autematic Chucker—Seriai
\$70393
72" King Heavy Duty Vertical Bering Milli Seriai
No. Let 38—2175
Rewbottem Cam Miller—Seriai 135/49. Rebuilt &
gusranteed

gustantee Cam Miller—Serial 135/49. Rebuilt & gustantee 20" Knight Rotary Table Rebuilt No. D-8 Colbura Heavy Duty Drill Press—Serial #155
Rebuilt No. 314 Baker 24" Heavy Duty Drill Press—Serial #2-4598
Defiames 3% Table Type Horizontal Bering Mill—Serial #870-38

Hazard Brownell Machine Tools, Inc. Providence 6, R. I. LATE TYPE MACHINERY

LATE TYPE MACHINERY

AUTOMATIC, 134"—4 Spin, Gridley Model G
BOLT THREADER, 11/2" Reliance Williams
VERT, Attaen, for Boring Mach, for 330T G. & L.
Mill & Outer Support
BORING MACH, 31/4" bar Defiance Tible, Type
BORING MACH, 11/4" S. Bar Lucas, Table Type
BORING MILL, 10/4" N. Ber., 12/4" bas, M.D.
BORING MILL, 10/4" N. Ber., 14/4" bas, M.D.
BORING MILL, 72" N.B.P., 2 Hels., M.D.
RADIAL DRILL, 4'15" eol. Amer., M.-on-Arm, T.I.
RADIAL DRILL, 5'14" Col. Amer., M.-on-Arm, T.I.
RADIAL DRILL, 5'14" Col. Amer., M.-on-Arm, T.I.
RADIAL DRILL, 5'14" Col. Amer., M.D.
RADIAL DRILL, 5'14" Col. Amer., M.D.
RADIAL DRILL, 3'15" eol. Amer., M.D.
RADIAL DRILL, 3'16" col. Amer., M.D.
RADIAL DRILL, 3'16" col. Amer., M.D.
RADIAL DRILL, 5'16" col. Amer., M.D.
RADIAL DRILL, 8'16" col. Amer., M.D.
GRINDER, CYL., 4"18" col. Col. Col. Rel.
RADIAL DRILL, 8'16" col. Rel.
RADIAL DRILL, 8'16" c

BENNETT MACHINERY CO.

375 Allwood Rd., Clifton, New Jersey Phone: PRescett 9-8996 N. Y. Phone LOngacre 3-1222

I—Waste Acid Neutralizing Plant, agi-tator 12' x 12' x 6', complete with Bins, bin signals, material elevator, truck hopper, gravimetric feeder, rotary bin gate. lime slacker, dust and vapor removable unit and all accessories. THIS IS A NEW UNIT.

-3000 HP, G.E. Motor, 120 RPM, 3 phase, 60 cycle, 2300 volt, Induction. No controls.

1-150 Ton Niles Crane, 64'41/2" span, two trolley, no motors or controls.

Lou F. Kinderman Box 182 - Niles, Ohio - Phone 29876

PUNCH & SHEAR COMBINATION

HILLES & JONES #5, 24"/30" throat, ARR. MOTOR DRIVE.

S. M. DAVIS 510 LaSalle St. St. Louis 4, Mo.

HYDRAULIC PRESS

100 Ton, 4 Column Press 36 x 52 Bed Area Manufactured 1945 Complete with 3 Air Cushions

WINSTON MACHINERY CO., INC. 326 West Ohio St. Indianapolis 2, Ind. 6000 Lb. Chambersburg double frame Steam Forging Hammer.

Multiple Punch No. 30-A W. W. 600-tons. Multiple Punch No. 6 Cleveland 750-tons. Multiple Punch Size G. L. & A. 940-tons. 300 Ton Oil Geared High Speed 2-Column

Hydraulic Press, Stroke 18", ram 27" x 23". 750 Ton Williams White Self-Contained Down Moving Hydraulic Press, Bed 36'

x 42", practically new.

Nipple Threading Machines (3), New 1950. ½", 1¼", 2". Roller Pipe Cutter.

Kane & Roach #24 Angle Bender, Capacity 6 x 6 x 1

Ajax Upsetting & Forg. Machs. twin gears, twin flywheels, susp. slides. ", 2", 3", 4" Ajax Upsetters, suspended

slides. National Upsetting & Forg. Machs. I", 4"

Ajax and Acme Upsetting & Forg. Machs., not susp. slides, sizes from 1" up.
filliams White Horizontal Bend
Straightener, Capacity 15" beams. Williams Bender &

W.W. Bulldozers, #22, #3, #4, #29-U, 50 ton W.W. Hydraulic.

Chambersburg Board Drop Hammers, 800 lb., 1200 lb., 2000 lb., 3000 lb.

Single & Double End Punch Presses, various capacities.

Nazel Air Forg. Hammer #6-B, 7" sq. Bradley Hammers, Cushioned Helve, Upright & Compact.

Bar Shear #12 B. C. Buffalo 5" Rd. Bar Shears, Open End., Table cast on

Slant; also Guillotine 11/2" to 3". Knuckle Joint Press 200-ton, 6" str.; EG-54 Ferracute 400-ton.

600-ton R. D. Wood Incl. Hydr. Locomo-tive Wheel Press, 96" betw. bars. #50-A Quickwork Whiting Rot. Shear 3/4 Tensile Testing Machines, 50,000, 100,000, 200.000 300.000.

BOLT, NUT & RIVET MACHINERY, COLD HEADERS, THREAD ROLLERS, THREADING MACHINES, TAPERS, COLD BOLT TRIMMERS, SLOTTERS, HOT HEADERS AND TRIMMERS, COLD AND HOT PUNCH NUT MACHINES, POINTERS.

DONAHUE STEEL PRODUCTS CO. 1913 W. 74th Street, Chicago 36, III.

500 TON SOUTHWARK HYDRAULIC PRESS

Stroke 12" Daylight 28" Platen 56 x 56 A-1

LANG MACHINERY COMPANY
h ST. & A.V.R.R. Pittsburgh 22, Pa.

BENDING ROLLS

Initial-Pinch Type. 12' x 1" Capacity. New 1950, like new. 2 motors-Drop end. Photos on request.

KINGS COUNTY MACHINERY EXCHANGE 408 Atlantic Ave. Brooklyn 17, N. Y. TR. 5-5237

KNOX AIR COMPRESSORS FULLY GUARANTEED EARLE E. KNOX COMPANY

OFFERING

IIII BACON STREET

Combination Punch & Shears

-Buffalo—Size No. 1/2 with Notcher New 1946 -R. Sontag—Size 16 with Notcher For further information write or phone

FISHER ASSOCIATES 297 Morris Avenue New York 51, N. Y. MOtt Haven 5-3600

350 Waterman St.

UNUSUAL LATHES FOR SPOT DELIVERY!

AMERICAN 36" x 33' centers geared head; high duty; heavy

ns.

mn

6

a.

ed

8

300

ari-

Jp-

no-

000,

RS, ES,

111.

Pa.

itv.

nd. GE Y.

1946

. Y.

AGE

LEHMANN 25" x 96" centers geared head; heavy; Timken


LODGE & SHIPLEY 24" x 96" centers; geared head; Timken; Late type

NILES 30" x 46' and 30" x 50' Single End Boring; Timken; Late type

LoSWING (SENECA FALLS) 8"x108" centers; Production; steel ways; Late type

LeBLOND #16 Automatic Turning; hydraulic; Timken; Late type

and many others



LATE TYPE

NILES 30" x 96" centers "Time-Saver" Lathe

Ask for catalog of AMERICA'S LARGEST STOCK

... for machine tools!

MOREY MACHINERY CO.,

Manufacturers • Merchants • Distributors

410 BROOME ST.

NEW YORK 13, N. Y.

Telephone: CAnal 6-7400

IMMEDIATE DELIVERY FROM STOCK

AUTOMATICS

2%" CONOMATIC, 6 Spd1., Ser. 2891 SE and 3464 SE, chip conveyor, threading spindle (2) 1%" RAB ACME GRIDLEY, 8 Spd1., Ser. 85013, threading spindle 1½" RAB ACME GRIDLEY, 6 Spd1., Serial 40603, threading spindle,

chip conveyor 1/4" R6 ACME GRIDLEY, 6 Spdl., threading spindle (2) 1" RA6 ACME GRIDLEY, 6 Spdl., Ser. 23455 and 23333, chip con-veyor, threading spindle (2) 9/16" RA6 ACME GRIDLEY, 6 Spdl., Ser. 22965A, No. 22700 AM.

chip conveyor (2)

No. 676 NEW BRITAIN CHUCKER, 6 Spdi., Ser. 23003, with chucks
25% MODEL F ACME GRIDLEY, 4 Spdi., Ser. 7769 stock stand reel
134" CONE 4 Spdi., Ser. 33, stock stand, reel
200 and #2 BROWN & SHARPE, front and rear tool slides
8x 89/5 GOSS & DELEEUW Chucker, 5 Spindle, with threading spindle,
1942 Machine

BROACHES

AMERICAN, 6 Ton, 24" stroke, Vertical, Serial #4463, 3 Way, Push, Pull and Surface
AMERICAN 8 Ton, 24" stroke, Vertical, Serial #2684, 3 Way, Push, Pull and Surface. FOOTEBURT, 3 Ton, 40" stroke, Vertical, Dual Ram LAPOINTE, 71/2 Ton, 24" stroke, Model HP, Horizontal

DRILL PRESSES

SNYDER Sgl. Spdl., No. 3 M.T., Dial Type, Powerfeed BARNES H-3 Sgl., Hydram, Vertical No. 288 EDLUND Sgl. Spdl., No. 2 M.T., NEW

GEAR MACHINERY

#58 FARREL SYKES Herringbone Gear Generator, 61" dia., 1942 Machine
#3A FARREL SYKES Herringbone Gear Generator, 26" dia...
#140 CLEYELAND Rigidhobber, 1945 Machine
#7125A FELLOWS Gear Shaper, Late
#12 FELLOWS Gear Shaver, Late
#15 and #25 GLEASON Gear Quenching Press

No. Al-12 ARTER Rotary Surface, Serial #1506, with 12" Mag. Chuck 14 x 30, 17 x 42, and 17 x 48 NORTON Crankshaft, with Pot-Type #81 HEALD Internal #72A3 HEALD Internal #112 RIVETT Internal

LATHES

10 x 24 JACKSON MELLING Crankshaft Turning 10 x 32" ATLAS, with chuck and gears 11 x 30 SEBASTIAN, Chuck and face plate R-14 SENECA FALLS, Lo-Swing, 16/2" swing GISHOLT SIMPLIMATIC, Air Operated Chuck and Air Cylinder, 34" swing over ways

PRESSES

PRESSES

#2ET-10-86 BLISS Triple Action Toggle, Capacity of Plunger 650

Ton, Blankholder 400 Ton, Lower Ram 350 Ton, Bed area 52 x 86, 39"

Stroke of plunger, 28" of blankholder

#410A BLISS Double Action Toggle, Capacity of Plunger 525 Ton,
Blankholder 290 Ton, Bed area 60 x 84, 25" stroke of drawing silde,
17" of blankholder slide, D.B.G.
#774 1/28 TOLEDO Double Action Toggle, Capacity of Plunger
200 Ton, Blankholder 120 Ton, Bed area 45 x 72", 18" stroke of
drawing silde, 12" stroke of blankholder D.B.G.
#78-D TOLEDO, Double Crank, S.S., 255 Ton, 6" stroke, 30" shut
height, 51 x 87" bed area
65, 55 and 38 ton WALSH O.B.L. NEW, immediate delivery
50 Ton, HENRY & WRIGHT Dieing, with Double Roll Feed, scrap
cutter

MISCELLANEOUS

MCKAY ROLLER LEVELLER, 1/2" to 2" 4-High, 15" dia. rolls x 72" wide (2)
No. 10M2 TISHKEN ROLL FORMER, 10 stand, with AUTOMATIC CUTOFF
TOLHURST OIL SEPARATOR, 48" cap., Serial #116390
No. 1 BAKEWELL TAPPER, Serial #712
No. 2G MOREY, Serial #803, with 3 Jaw Chuck, Cross slide
No. 1 WARNER & SWASEY, Serial 582809, 1/8" Capacity, Bar Feed

PAUL'S MACHINERY COMPANY

6111 VERMONT, DETROIT 8, MICHIGAN



FOR SURPLUS STEEL PLANT EQUIPMENT

- 1-2½" & 20" x 7½" Reversing Cold Reduction Mill (Steckel Type), complete otor, Motor Generator Set, Spare Parts. Complete unit
- 1-20" Dia. x 30" 2-High Balanced Twin Rolling Mill, complete with Ryertex Bearings, Pimori Stands, Drive, and 500 H.P. Motor, 2300 volt, 3 phase, 60 cycle, and
- 1—15" Dia. x 30" 2-High Mill, complete with 75 H.P. Motor, 2-00 volt, 3 phase, 60 cycle, and Controls

Write for the Curry List of available steel plant

-2000 H.P. General Electric Slip Ring Mill Type Motor, 237 RPM, 3 phase, 60 cycle, voit, complete with Liquid Slip Reg-Mater In and Out Plugging, and all other Controls for mill type operation

1-U.E. & F. Co. No. 31/2 Vertical Bar Shear, complete with Motor and Controls.



- 1-50,000 Lb. Drawbench Single Chain, nage Return and Unloading Arms. Draw speed 17 to 50 feet per minute.
- 1-1500 H.P. Gear Reduction Set, complete with Flywhaels, ratio 570 to 35 RPM.
- 1-1000 H.P. Gear Reduction Set, triple reduction, complete with Flywheels, ratio 585 to 20.18 RPM.
- 1-11/4" x 48" Lewis Plate Shear, complete with Holddown, Drive, and 40 H.P. 3/60/220 volt Motor.

Cable Address: CURMILL-PITTSBURGH

IMMEDIATELY AVAILABLE

- 4 LIBBY 1H5 Turret lathes. Manufactured 1940-41. SERIALS 642-1028. 839-1241 1039-142-A. 1241. PRICE EACH \$7280 FOB
- I LIBBY 1H6 Turret, SERIAL 129A. PRICE \$8750 FOB

Excellent condition with extensive equipment. For fuller details and actual photographs, contact

J. B. MACHINE TOOL Co. Ltd.

312 BRADFORD STREET

BIRMINGHAM 5, ENGLAND

Cable Address-JABEMACHIN

Immediately Available ROLL FORMING MACHINES

Kane & Roach 15 stand, 30" wide, 41/3" dla. shaft 75 H.P. M.D. Yoder 14" stand, 24" wide, 21/2" dia. shaft, 25 H.P. M.D. Tishkin M-2 Ten stand Yoder with AC-2 Cutoff Rafter Tube Forming Machines, 5 & 7 Stand Yoder 5 stand vertical, with AC-1 Cutoff

PARTIAL STOCK LISTING

"The most diversified stock of machinery in the country. If it's machinery we have it." National Machinery Exchange 128 Mott Street New York 13, N. Y. CAnal 6-2470

FOR SALE

30 K.W. Lepel high frequency induction melting unit, complete with necessary controls, one (1) type F-30 melting furnace and one (1) tilt table. Melting capacity 35# steel. Current 220/3/60. In excellent condition, used very little.

LEBANON STEEL FOUNDRY

LEBANON, PENNA.

AUTOMATIC CHAIN MACHINE FOR SALE

Complete business for sale—consisting of completely automatic chain machine with all dies, fixtures, tools, and enough steel to manufacture 259,000 bicycle chains. Machine will manufacture 1000 bicycle chains a day, one shift.

OUR PRICE—ONLY A FRACTION OF ORIGINAL COST

ORIGINAL COST-\$500,000.00

ADDRESS BOX S-877, CARE THE IRON AGE, 100 E. 42nd St., NEW YORK 17

DIESEL GENERATOR SETS

- 3—Brand New 65 KW, 250 volt DC Diesel Cummins, Generator G. E. 65 KW with controls. Engine 90 HP, 6 cyl., 4 cy.. 1600 RPM
- F. H. GRAWFORD & COMPANY, INC. 30 Church Street New York 7, N. Y

#26 Buffalo Forge Armour Plate Slitting Shear, 11/4" Round Cap. 10HP. #1 Buffalo Forge Wrapping Rolls, M. D.

FALK MACHINERY COMPANY 18 Ward St. Baker 5887 Rochester 5, M. Y.

ELECTRIC FURNACE to 1850°

8 x 12 x 15 Inside with Auto, Temperature Control 4.5 K.W. Stiding door, cheap to operate. Substantial, Dependable for Machine Shop-Tool Room New. \$250.

E. H. WILLIAMS, Box 9042 Huntington, W. Va.

Boring Mills, 48" and 72" Gishelt Header or Upsetter, 3" Ajax, M. D. Grinder, Thompson, 10 x 36 Univ. M. D. Lathe, 60" x 25" c. Mackintosh-Hemphill, Millers, Plain, Nos. 3, 4, and 5B. Planer 48" x 48" x 12" Gray, Spur Gear Drive Press, Trimming No. 6 W&W, and =73-5, Blis

WEST PENN MACHINERY COMPANY 1210 House Bldg. Pittsburgh 22, Pa.

DRAVO HEATING UNITS

Direct Fired
4—Units—1,750,000 B.T.U., each #5 Oil—220
Volt, 3 Ph. 60 Cycle. Completely Rebuilt.

ATLAS MARINE FABRICATORS, INC. 25 Scott Ave. ve. South Amboy, N. J. 1-0291

FOR SALE

Complete Slitter Line

Less than One Year Old, In **Excellent Operating Condition** - consisting of -

ete

tio

0

S

220

GE

1. Heavy Duty Slitter— 18" wide, 6" arbor, capacity 6 cuts 3/16" Mild Steel, 15 h.p. U.S. Motor with varidrive unit.

2. 36" Pay-Off Reel-Hydraulically expanding drum 12" minimum O.D., with 6" expansion.

3. 18" Recoiling Unit-" diameter with mechanically collapsible drum.

4. Cowles Knives and Spacers—

Complete set. EQUIPMENT CAN BE INSPECTED IN OPERATION

CASH PRICE - \$17.500 F.O.B. OUR WAREHOUSE TERMS IF DESIRED

RICH STEEL COMPANY

8011 Beach St. L.A. 1, Calif. Tel. - LOgan 8-3301

HOT STRIP ROUGHER OR PLATE MILL

Heating furnaces and mills to roll 90" wide plate or break down slabs for 90" continuous hot strip mill.

This installation is capable of rolling 60,000 tons of steel per month and consists of:

SOAKING PITS.

2-HIGH 30" x 100" REVERSING SLABBING MILL WITH TABLES. HYDRAULIC SLAB SHEAR, 6" x 60" CAPACITY, WITH TABLES. SLAB CONVEYOR TO CHARGING PLATFORM OF FURNACES. TWO CONTINUOUS SLAB HEATING FURNACES. 27" x 90" FINISHING SCALE BREAKER. 3-HIGH PLATE MILL, 34" & 22" x 100", WITH VERTICAL EDGER; TILTING TABLES ON ENTERING AND DELIVERY SIDES.

Send For Illustrated Circular

FRANK B. FOSTER, INC.

2220 Oliver Building, Pittsburgh 22, Pa.

Cable: "Foster Pittsburgh"

Telephone ATlantic 1-2780

BORING MILL—84" (New)
BORING MILL—200" (New)
DRILLS, Radial—4', 5', 6', up (New)
FURNACE (2)—Tocco, Jr. 20KW, 2 Sta.
FURNACE—Roller Hearth,
I.D. 15'8" x 3'6" x 11"
GRINDER—Rotary, 84" diam.
GUN BORING LATHE—64" x 65'0"
LATHE—32" x 21' c/c Bridgeford G.H.
MILLER VERT.—28" x 72" and
36" x 118" (New)
PRESS—2000 Ton, Knuckle Joint
PRESS—Plate Bending, 2000 Ton for forming cyl. shells, 14' W x 21/2" Thick
PRESSES—Hydraulic, 1000-4000 Tons
PRESSES—Hydraulic, 1000-4000 Tons

PRESSES-Hyd. 100-2800 Tons for

105 mm shells RIVET HAMMER—6B Hi-Speed STRAIGHTENING PRESS-2000 Tons

NUT-TAPPERS-34", 6 Spindles (2)

MAXWELL MACHINERY CORP. 1775 Broadway New York 19, N. Y. Plaza 7-3471


FOR SALE

2—GE SYNCHRONOUS MOTORS 600 HP-2300 Volt-3 phase-60 cycle-360 RPM. Purchased new 1948

JOHN D. McGUIGAN, INC. 616 S. Michigan Avenue, Chicago S, Illinois

WORLD'S LARGEST STOCK STAMPING PRESSES

BLISS . CLEARING . CLEVELAND FERRACUTE . HAMILTON . L & J NIAGARA . TOLEDO . V & O



SQUARING SHEARS . PRESS BRAKES REBUILT and GUARANTEEL

JOSEPH HYMAN & SONS

TIOGA LIVINGSTON & ALMOND STS. PHILADELPHIA 34, PA. Phone REGENT 9 /727

FOR SALE

3" O.D. x .095 WALL x 15 FT. LGTHS. CR. EW-PRIME-PRESS. TEST 4000# PBI. 40,000 FT. IMMEDIATE DELIVERY FROM OUR PLANT BELOW MILL PRICE Wallack Bros., 7400 S. Damen Ave., Chicago 36, 111.



OUR BUSINESS

WE BUY - Idle machines take up valuable space — Let us convert them into cash. You'll be amazed at the money they will bring.

WE SELL — Finest inventory of machine tools in the Midwest. Many like new - all in top working order. Write for catalog.

WE TRADE — If you contemplate a changeover, contact us immediately. We can supply machine tools of all types in any quantity and we'll take surplus machines in trade. All dealings strictly confidential.

MANDEL- CAMRAS MACHINERY COMPANY, INC.

1326 West Randolph Street Chicago 6, Illinois Telephone: MOnroe 6-2180

TUBING MACHINES

Two—Tube forming machines, made by Maple wood Co., used less than one year, excellent condition, immediate delivery, priced right.

GREAT PIPE & STEEL CORP. 1007 S. Hill Street Los Angeles 15, Calif.

USED — GUARANTEED CONSTRUCTION EQUIPMENT RAILROAD EQUIPMENT RAILS

0 ten Whiteomb Dissel Electric, 0-4-4-0, std. ga.
5 ten Whiteomb dissel elec. 0-4-4-0 std. ga.
0 ten Whiteomb dissel elec. 0-4-4-0 std. ga.
10 ten Whiteomb dissel elec. 0-4-4-0 std. ga.
10 ten Dawenport dissel mesh. 0-8-0 std. ga.
10 ten Januard dissel mesh. 0-8-0 std. ga.
10 ten Januard dissel mesh. 0-8-0 std. ga.
10 ten dissel mesh. 0-8-0 std. ga.
10 ten dissel mesh. 0-8-0 std. ga.
10 ten dissel dissel mesh. 0-8-0 std. ga.
10 ten dissel ten dissel mesh. 10 ten dissel ten ten dissel ten dissel ten dissel ten dissel selectric dissel ga.
10 ten dissel selectric dissel mesh. 10 ten dissel selectric dissel mesh. 10 ten dissel dissel ten dissel selectric dissel ga.
10 ten dissel dissel mesh. 10 ten dissel dissellation dissella

Railroad Equipment

30# Relaying Rail 60# Relaying Rail 70# Relaying Rail 75# Relaying Rail # Relaying Rail 85# Relaying Rail

90# Relaying Rail

100# Relaying Rail Used Creosoted Ties

Used Tie Plates

Allis-Chalmers Tractors

International Tractors

Caterpillar Tractors

NW25 Shovel Fronts

NW6 Shovel Fronts

80D Shovel Fronts

HYMAN-MICHAELS COMPANY

122 SO. MICHIGAN AVE., CHICAGO 3, ILL. Car Repair Parts For All Types of

WAbash 2-4911

TANK CAR TANKS

PUBLIC AUCTION SALE

Single Lots Only No Confirmation Necessary

MACHINERY and EQUIPMENT of \$2,000,000.00 CHEMICAL PLANT 1348 BLOCK STREET, BALTIMORE, MD.

on the premises

Thursday, Dec. 4, 1952 at 10:00 A.M. (E.S.T.)

ROTARY KILNS, ROTARY DRYERS, RO-TARY VACUUM FILTER, APRON OR PAN CONVEYORS, 404 HP BOILER, MOTORS, GEAR REDUCERS, SCREW CONVEYORS, BUCKET ELEVATORS, STEEL TANKS, BINS, HOPPERS, JACKET-ED AGITATOR KETTLES, STRUCTURAL STEEL SUPPORTS, RUNWAYS, PLATE, PIPING, POWER CABLE and CONDUIT, ELECTRICAL EQUIPMENT.

MISCELLANEOUS: 1-4 Ton Shepard Niles Monorail Crane, complete with motors, controls and bucket; also 100 Tons structural steel monorail supports. Dorr Classifier, Duplex 6'x20'. 1—Dorr Thickener, 18' dia. x 22'. 5—Vacuum Pumps, 74, 196, 400 CFM, also Nash size 4. 4—ruller Lehigh Pulverizers, each driven by 75 HP vertical motor. 3—4'x5' #38 Tyler Hummer Screens. 5-Fuller Kinyon Air Compressors. 1—Jeffrey Traylor Vibrating Grizzly. 2—Jaw Crushers, 10''x 16", Buchanan Type B, 10"x14" Farrel. 1-Pneumatic Airveying System, including 225' of 3" pine and hoppers. 4—Buffalo Weigh Hoppers, 4' dia, with suspension scales, I—Rotary Batch Blender, 66 cu. ft., capacity 4100#. I—Vertical Lime Kiln pacity 4100#. I—Vertical Lime Kiln about 30' high. I—Cottrell Precipitator. I—Rotary Lime Slaker, 6'6" ID x 12' long, I—18"x85' Belt Conveyor, 32—Centrifugal Pumps, various sizes, including two Dorrco. Standard Gauge Ore Cars, etc.

Send for SALE CATALOG INSPECTION: From Nov. 20th to DATE OF SALE

BERNARD MAGRILL, Auct'r. OFFICE: 194 Broadway, Brooklyn 11, N. Y. PHONES: STagg 2-4574-4575

For Sale O.H.STEEL PLATES

SAE 1020

Immediate Shipment Exclusive CMP Regulations

1/4" — 60" x 240" 3/6" — 60" x 240"

F.O.B. Cars Baltimore

PACIFIC INTERNATIONAL CORP.

42 Broadway, N. Y. 4, N. Y. Tel. WHitehall 3-3223

50-TON INDUSTRIAL LOCOMOTIVE CRANE

100 Ft. Boom, Standard gauge with new CUMMINS DIESEL ENGINE And Magnet Generator Immediate Delivery Attractive Price

INDUSTRIAL EQUIPMENT DIVISION Phone WAlnut 1-3300

P. O. Box 1647

Pittsburgh 30, Pa.

FOR SALE

LOCOMOTIVE CRANE-OHIO-25 Ton Cap.

Coal Fired Model E Weight about 130,600#

ANGLE SHEAR - HILLES & JONES

Cap. 6 x 6 x 3/4 and 12 x 5/8 PLATE
Double Head—complete with electrical equipment CAN BE SEEN AT OUR PLANT

BETHLEHEM CONTRACTING CO. BETHLEHEM, PENNSYLVANIA
'PHONE—University 7-5879 — 7-5870

3-10-ton Shaw Overhead Cranes, 67' 1" span, 230 VDC, box girders, structural end trucks, cage type Shaw motors and control, mechanical and electrical brake on hoist — heavy type — good condition — stored inside — ready to ship. PRICE f.o.b. Pittsburgh, Pa. \$9,500.00 each

SEND ME YOUR CRANE INQUIRIES -200 other cranes, various tonnages. spans and current.

JAMES P. ARMEL — Crane Specialist 710 House Bldg. Pittsb: Telephone: Grant 1-4449 Pittsburgh, Pa.

SALE OR RENT

-10-10n Link Bett Model 35 wagon Crane Pneumatic Tire mounted -Northwest 25 Shovel Attachment -10-7on Stiff Leg Derrick -40-Ton Orton Diesel Loco. Crane -40-Ton Industrial Brownhoist Oil Fired Loco. Crane. New 1943.

B. M. WEISS CO.

Girard Trust Co. Bldg., Phila. 2. Pa. Rittenhouse 6-2311

WE BUY AND SELL USED OVERHEAD TRAVELING CRANES STRUCTURAL BUILDINGS

Your Offerings and Inquiries Solicited BENKART STEEL & SUPPLY CO. CORAOPOLIS, PA.

WORLD'S LARGEST INVENTORY



P. O. BOX 51, ROCHESTER 1, N.Y.

OFFERING

BRIDGE CRANES

ARNOLD HUGHES COMPANY 765 Penobscot Bidg. Detreit, Mich. WOodward 1-1894

THE IRON AGE

MOTORS - M. G. SETS - TRANSFORMERS

ENGINEERED AND REBUILT BY SPECIALISTS IN OUR MODERN PLANT

			MOTORS-23	
Qu	HP	Make	Туре	RPM
1	285/200	G. R.	MDP-420	850/410
(Spa	re armature	anti-	friction bearings	for above
	(TOP)			
1	150/200	Whae.	MCB-100	870/300
1	150	Whse.	MT-5	350
1	100/140	Whse.	MCB-90	500/415
4.	100/140	G. E.	MDA-108	430/500
8	100/130	G. E.	CO-1831	675/600
3	85/65	Whee.	K-10	635/700
3 1 1* 5	75/60	Whae.	K-10	425/470
ï.	75/100	Whse.	CK-10	500/675
D	79/90	Whee.	MCA-70 MCB-70	440/400
2	70/90	Whise.	FW	440/400
A.	50/80	C. W.	CO-1829	575/480 750
1	50/65	Whee,	MCLA-131	500/450
	50/65	Whse.	MCA-60	475/425
	50/63	G. E.	CO-1810	725
2	65/85	G. E.	CO-1830	700/650
1	65/85	G. E.	CO-1811	600/500
1 4	45/57	Whee.	K-9	515/470
i	45/57	Whan.	KG-9	515/470
9	35/45	G. E.	CO-1810	500/450
10	35	G. E.	MDA-10436	650
î	30	C. W.	EH	750
î	25/35	G. B.	CO-1829	750/450
1 1 2 2	2736	Whee.	K-6	1050
2	25/33	G. E.	MDS-408	575/509
2	23/30	G. E.	MDP-408	800/415
8.	20/28	Whas.	MCA-40	600/470
	19/15	Whas.	K-5	630/560

Qu	HP	M	ake	Туре	RPM
8	16/19	C.	W.	BM.	620/560
1	16/18	G.	E.	MDS-406	615/700
1	15	G.	E.	CO-2505	700
1	15/19	G.	E.	CO-1807	600/525
1.	13/17	G.	E.	MDA -103	645/725
1.	18/17	G.	E.	MDB-103	645/725
All	motors	series	wound	except those	marked (*)
which	are com;	; bauoq	can fur	mish these for	series opera-
tion.			PONO		

3-Phase -60-Cycle P.F. 100 100 80 100 100 100 80 80 100 Volta RPM 90

Motor Generators of modern design, complete with control—ctill on their original foundations—available for immediate shipment.

(a)—G.E. 1500-KW, 230-VDC, 514 R.P.M., epd., Interpole, pole face windings, 2100-HP sys. motors, 8-PF, 18,200-V, 3-p, 80-cy, will resented to 6600 V, or 4180-V.

Lua	HP	Make	Тура	Volts	RPM
1	1800	G.E.	MT-498	2300	857
1 **	1200	G.E.	MT-26	2200	377
200	1000	Al. Ch.	ANY	2200	235
l	800	G.E.	MT	2200	648
	600	G.E.	MT-20	2200	360
	500	G.E.	1-16-M	2300	450
	400	Al. Ch.	ANT	2200	514
1	400	G.E.	MT-413	2200	450
	250	Whie.	CW-937	440	1309

	MC	OTOR GI	ENERA	TOR SETS	
Qu	KW	Make	RPM	Velta	Volts
1(8-U) 3 4	2400 1000 1000 1000	Whse. Whse. G.E. G.E.	720 514 514 514	600 600 600	2400/4800 11000/6600 11000/6600 2300
1 1(8-U)	500 500 500 250	C.W. Whse. C.W. Whse.	720 1200 720 1200	275 250 575 125/250	2300/448 440 2300/448 2300
1 1 2	200 155 150	Ridgway G.E. Whse.	900 720 1200	275 250 250	2300 2300/440 2300

We can furnish any of these sets with exciters and VARIABLE VOLTAGE CONTROL engineered and rebuilt to your requirements.

ELECTRIC TRAVELING GANTRY CRANE

10-ton Champion 100' span between ground rails, 31' overhang one end, 23'9" other end, 45' lift, with 1200' of 100# rail, Now 550-VAC, will arrange for 220/440-VAC or 230-V.D.C. AVAILABLE FOR IMMEDIATE INSPECTION AND SHIPMENT. In excellent condition. The kind of crane that is seldom on the market.

MAC CABE COM

We Sell!

PLATE

SHEET

ROD

PIPE

One Of The

LARGEST

STOCKS In

The East. Immediate De-

livery -Warehouse

Stock. One

4302 CLARISSA STREET

CABLE ADDRESS "MACSTEEL" PHILADELPHIA, PA. . PHILADELPHIA 40, PENNA.

PHONE **DAVENPORT 4-8300**

1000 K.W. Allis-Chalmers 275 Volt DC. Synchronous Motor **Generator Set** 720 R.P.M. Late Type—Modern 2300/4000 Volts A.C. with

Automatic Reduced Voltage Starting Gear and D.C. Panel Board

IMMEDIATE SHIPMENT!

Please Send Us Your Inquiries

L. J. LAND, INC.

150 GRAND STREET, NEW YORK 13, N. Y.

Established 1910 MILL DISTRIBUTORS) 131 BRUCKNER BLVD., N. Y. 54, N. Y. CAngl 6-6976 Phone: Cypress 2-5617

MOTOR GENERATOR SETS

Two 75 KW. GE 250/125 v. 3 wire-125 HP. GE "K" 220/440 v., 1200 RPM with AC and DC Switchgear. Also TURBO GENERATOR UNITS 500 to 3500 KW. Also BOILERS 100 to 500 HP.

POWER PLANT EQUIPMENT CO.

41 Cortlandt St. NEW YORK, N. Y

Pound To A Carload. Sub. mit Your **TUBES** Inquiry. BAR JANDRU Steel Corp. MOTOR GENERATOR SETS 600 V.-3/60/2300 v. 250 V.-2300/4000 v. 250 V.-2300/4000 v. 125 V.-2300/4000 v. 250 V.-2300/4000 v. 250 V.-2300/4000 v. 250 V.-220/440 v. 125 V.-220/440 v.

A. C. MOTORS SPEED

Large stock of smaller A.C. motors Also 230 V. DC motors rated 400-200-125-75-60 HP

MOORHEAD ELECT. MACH'Y. CO. P. O. Box 7991A - Pittsburgh 16, Pa.

FOR SALE

Freight car repair parts Relaying rails Steel storage tanks Freight cars and Locomotives

Also

Contracting Equipment Cranes—Tractors Ditchers—Compressors **Diesel Engines** and Generating Sets

THE PURDY COMPANY

8754 S. Dobson Ave. Chicago 19, Illinois

Empire State Bldg. New York 1, N. Y.

GE

THE CLEARING HOUSE

RAILS NEW and

Your exact trackage needs filled "Faster From Foster"
Track Tools & Accessories are properly matched and fabricated to meet all requirements and shipped from a reliable source.



"FASTER from FOSTER" RENT STEEL SHEET **PILING**

TRACK ACCESSORIES . PIPE . WIRE ROPE LB LAUSTIFF co.

Pittsburgh 30, Pa. Chicago 4, III.

New York 7, N.Y. Houston 2, Tex.

100# ARAA RAILS

500 tons 100 # ARA Type A first class relaying rail with angle bars. Immediate shipment.

Also other sections 60 # and up, spikes, bolts, frogs, switches, tieplates avail-

M. K. FRANK

480 Lexington Ave., New York, N. Y. 401 Park Bldg., Pittsburgh, Pa.

RAILS New and Relaying



TRACK MATERIALS AND ACCESSORIES CARRIED IN STOCK

SWITCH MATERIAL SPIKES & BOLTS - TRACK
TOOLS - TIES - TIE
PLATES - BUMPERS COMPLETE SIDE TRACKS

BUILDERS STEEL SUPPLY CO.



Keep'em rolling ... not rusting

FOR SALE

New-Used-Reconditioned railroad freight cars . car parts . locomotives • tank cars • steel storage

MARSHALL RAILWAY EQUIPMENT Corporation

50 Church St., New York 7, N. Y. COrtlandt 7-8090 Cable MARAILQUIP

FOR SALE

Round Steel Stapling Wire.
Standard Coils, Barrel Packed.
8 tons 18 Gauge 10 tons 2
4 tons 19 Gauge 10 tons 2 10 tons 20 Gauge 10 tons 22 Gauge

AMERICAN STEEL EXPORT CO., INC. 347 Madison Ave. New York 17, N. Y. Tel.: MU 6-2100

EVERYTHING FOR THE TRACK FROM SWITCH TO BUMPER

NEW & RELAY RAILS

in stock

12# THRU 130# SECTIONS

ACCESSORIES & SWITCH MATERIALS INQUIRIES SERVICED PROMPTLY



New RAILS Relaying

Railway Track Accessories

STANDARD IRON & STEEL CO.

Office & Yards: Knoxville, Tennessee

LIFTING MAGNETS

A complete magnet service. Magnets, new & rebuilt, generators, controllers, reels, etc.

Magnet specialists since 1910

Goodman Electric Machinery Co. Newark 2, N. J.

FOR SALE

-12 YD. WESTERN DUMP CARS.

-JORDAN STD. GA. R.R. SPREADER.

1 TON IND. GAS. LOCO. CRANE.

-65 TON & 4-100 TON G.E. DIESEL ELECTRIC
LOCOMOTIVES.

-10 TON DAVENPORT & 1-20 TON WHITCOMB
GAS LOCOMOTIVES.

1 TON IND. STEAM LOCO. CRANE.

DARIEN, 60 E. 42nd St., N. Y. 17, N. Y.

FQUIPMENT AND MATERIALS

WANTED

WANTED

50 used open hearth charging boxes. Contact: Mr. A. Flores

LA CONSOLIDADA, S. A.
120-Tel 497 Eagle Pass, Texas

Box 120-Tel 497

WANTED

11/2" LATE MODEL ACME OR NATIONAL UPSETTER

ADDRESS BOX 8-912 Care The Iron Age, 100 E. 42nd St., New York 17

AIR RECEIVER TANK WANTED

300 or 400 cubic feet capacity. Must be to ASME Specifications and bear such label. Advise dimensions, price and location.

The Federal Foundry Supply Company
4600 East 71st Street Cleveland, Ohio (Zone 5)

WANTED SURPLUS STEEL WALLACK BROTHERS 7400 S. Damen Ave. Chicago 36, Illinois

WANTED **BRIDGE CRANES**

ARNOLD HUGHES COMPANY 765 PENOBSCOT BLDG. DETROIT, MICH. WOodward 1-1894

BUSINESS OPPORTUNITIES

SEALED PROPOSALS FOR THE PUR-CHASE OF 1854 TONS FERROUS SCRAP INCLUDING 1100 TONS HEAVY MELT-ING STEEL, CIRCULAR #14, FOR SALE BY PANAMA CANAL COMPANY will be received by Purchasing Agent, Panama Canal Company, 24 State St., New York 4. N. Y. and by Superintendent of Storehouses, Balboa, Canal Zone, until 10:30 A.M. E.S.T. December 29, 1952. Blanks and information available at 24 State St., New York 4 N. Y.

. . DON'T HIDE YOUR LIGHT UNDER A BUSHEL . . .

Have something new on the market or do you just want to bell why your product does the job better? Either way, your advertisement in The Iron Age carries more weight and reaches more of your prospects.

WEISS STEEL CO. INC. 600 WEST JACKSON BLVD.

CHICAGO &, ILLINOIS Buyers of Surplus Steel Inventories 32 Years of Steel Service

CONTRACT MANUFACTURING

THE DIRECTORY OF PRODUCTION SERVICES

This section appears in the first and third issues of each month. See advertisers index in these

Carrying the announcements of plants offering specialized experience and facilities for the production of STAMPINGS, SPINNINGS, WELDMENTS, WIRE FORMS, SPRINGS, SCREW MACHINE PRODUCTS, FORGINGS, CASTINGS, GEARS, DIES, ASSEMBLIES, SPECIAL MACHINERY; and services such as MACHINE WORK, HEAT TREATING, SPECIAL MACHINERY; and so PLATING, GALVANIZING, etc.

EMPLOYMENT EXCHANGE

The meeting place for employers and men qualified for positions in the metalworking industry.

Help Wanted Rates Employment Service Rates Representatives Wanted Rates **Accounts Wanted Rates**

Set	Solid-50 words or less	\$10.00
	Each additional word	25ε
All	capitals—50 words or less	
	Each additional word	32c
All	capitals, leaded-50 words or less.	

Situation Wanted Rates Payable in Advance

Set	solid-25 words or	less	 		 	.\$2.50
	Each additional	word	 0 0		 	. 10
All	capitals-25 words	or less.	 		 	.\$3.75
	Each additional	word	 		 	. 15
All	capitals, leaded-2	5 words	F	les	 	.\$5.00
	Each additional	mard				78

COUNT SEVEN WORDS FOR KEYED ADDRESS

EMPLOYMENT SERVICE

Immediate Openings for Metallurgists and Foundry Men

20.

w &

o. I. J.

TRIC

OMB

PUR-

RAP

ELT-

SALE

ill be

nama

York

tore-

10:30

Blanks

e St.,

SHT

better? ge car-sepecta.

AGE

We now have positions available in practically all fields, including technical service and sales. Salaries open. Positions available in all sections of the country. Write or phone for full particulars. Your inquiry held in confidence

EMPLOYERS SERVICE BUREAU

Phone: Financial 6-1155 6 N. Michigan Ave. Chicag Chicago 2, III.

SALARIED PERSONNEL \$3,000-\$25,000—This confidential service, established 1927, is geared to needs of high-grade men who seek a change of connection under conditions assuring, if employed, full protection to present position. Send name and address only for details. Personal consultation invited. JIRA THAYER JENNINGS, Dept. K, 241 Orange St., New Haven 10, Conn.

SALARIED POSITIONS \$3,500 to \$35,000. We offer the original personal employment service (established 42 years). Procedure of highest ethical standards is individualized to your personal requirements. Identity covered; present position protected. Ask for particulars, R. W. BIXBY, INC., 274 Dun Bldg., Buffalo 2, N. Y.

HELP WANTED

TOOL ROOM SUPERINTENDENT

Man with ability to supervise the building of roll form dies, flat bed dies and bending lixtures for the fabrication of metal moldings. Also ability to esti-mate tooling cost desired. Salary commensurate with ability and experience.

ADDRESS BOX S-907 Care The Iron Age, 100 E. 42nd St., New York 17

SALES ENGINEER, FOUNDRY: UNUSUAL OPPORTUNITY FOR AGGRESSIVE MECHANICAL AND FOUNDRY SALES ENGINEER IN SOUTHERN STATES. GROWITH THE NATION'S FASTEST GROWITH THE NATION'S FASTEST GROWING INDUSTRIAL AREA. SEND COMPLETE QUALIFICATION RECORD TO PERSONNEL DIRECTOR, SAVANNAH MACHINE & FOUNDRY CO., P. O. BOX 590, SAVANNAH, GEORGIA.

ESTIMATOR—Midwest steel and alloy plate fabrication shop desires a mechanical engineer, experienced in estimating labor and material of tanks, piping, ducts, etc. Confidential. State age, former employers, education, experience and salary required. Address Box S-888, Care The Iron Age, 100 E. 42nd St., New York 17.

METALLURGICAL ASSISTANT — Opening in Metallurgical Dept. of large Midwest Automotive parts manufacturer. Prefer recent college graduate interested in production and process metallurgy. Write, stating age, school, and salary expected. Address Box S-885, Care The Iron Age, 100 E. 42nd St., New York 17.

HELP WANTED

HYDRAULIC SALES ENGINEER

Excellent opportunity with prominent Midwest manufacturer.

Must have sound engineering knowledge, preferably in hydraulics. Sales background helpful. Must be willing to travel.

Replies will be held strictly confidential. Give full details of experience and current earnings.

ADDRESS BOX S-908

Care The Iron Age, 100 E. 42nd St., New York 17

HELP WANTED

ALLOY STEEL SALES DIVISION MANAGER

Have exceptional opportunity for high caliber, widely experienced man to take charge of alloy steel sales division. New electric furnace steel plant with very latest equipment and spectrographic laboratory. Mill will special-ize in quality grades. Plant and head-quarters at Seattle, Washington. Plant beginning production this month — ex-cellent growth and future of this mill are assured. Interested in the highest caliber man available only. Salary open. Apply by sending full personal and ex-perience record, references and picture. Inquiries will be strictly confidential.

Frank V. Seidelhuber, Jr., President SEIDELHUBER STEEL ROLLING MILL CORP. 3693 East Marginal Way Seattle 6, Washington

ACCOUNTS WANTED

MANUFACTURERS AGENT

Accounts wanted by established reliable Manu-facturers Sales Engineers calling on Industrial accounts throughout northern Ohlo, with offices in Cleveland, Akron and Toledo.

ADDRESS BOX P-209 Care Iron Ago, 814 Park Bldg., Pittsburgh 22, Pa.

SITUATIONS WANTED

FORGING SUPERVISOR, 30 years administrative and Engineering experience. Thoroknowledge modern techniques, practical know how, aggresive. Wish connection with progressive concern producing small and medium forgings, all metals. Address Box S 909, care The Iron Age, 100 E. 42nd St., New York 17.

SALES ENGINEER—M. F. Available for Chicago & Mid-West. Executive calibre, closer, mature, Londable. Diversified background. High tech. competence in perishable tools & furnaces. High competence hiring & field training. Norris 915 W. Carmen, Chicago 40, Ill. Phone ED 4-5325.

INDUSTRIAL RELATIONS, position desired. College graduate, 33, Veteran, aggressive, energetic, flexible, mature. 4% years shop experience basic steel. 21 months Industrial Relations experience. Locate anywhere. Address Box S-910, care The Iron Age, 100 E. 42nd St., New York 17.

EXECUTIVE—experienced in shop operations plant and industrial engineering, industrial relations and administration. Forging, foundry melting, machining, assembly, Address Box S-893 care The Iron Age, 100 E, 42nd St., New York 17.

METALLURGIST

With thorough knowledge of tool steels and their applications, specialty steels and alloys.

Promising opportunity for man 28 to 36 years of age with ability to warrant further advancement. Location New York

Please give full information, age, education, experience, etc., in first letter,

ADDRESS BOX S-899 Care The Iron Age, 100 E. 42nd St., New York 17

Topnotch Sales Executive and Salesman

with experience in the selling of strip steel and steel strapping needed by old, well-established producer and distributor. Salary and incentive. Give full details.

ADDRESS BOX 8-891 Care The Iron Age, 140 E. 42nd St., New York 17

REPRESENTATIVES WANTED

REPRESENTATIVE WANTED

For Chicago area, a manufacturer of pneumatic chisels, requires an aggressive representative. Must be experienced in pneumatic tool or tool steel sales and well acquainted with territory. Exclusive representation on salery and commission basis. Write for application blank.

ADDRESS BOX S-903

Care The Iron Age, 100 E. 42nd St., New York 17

WEBB WIRE



NEEDLE and STAINLESS



THE CARPENTER STEEL CO.

Webb Wire Div. NEW BRUNSWICK, N. J.



J. BOYNTON AND CO.

CONSULTING ENGINEERS

109 N. Wabash Ave., Chicago 2, III.

7abor ABRASIVE CUTOFF MACHINES

and shapes

3-H.P. line—wet and dry cutting, bevel or rt. angle. Capacity. ²/₄" solids; 2" tubing; 2" x 6" lt. sheet formed sections; ¹/₂" x 1" flats.

10-H.P. line—wet cutting, rt. angle or bevel Capacity: 2½," solids: 3" x ½," angles; 4½;" tubing: ¾," x 3" flats. Write for literature. Specify shape, size and material to be cut.

TABOR MANUFACTURING CO.

6222 Tacony Street, Phila, 35, Pa.





THE EASTERN MACHINE SCREW CORP., 21-41 Borclay Street, New Hoven, Coan.
Pacific Coast Representative: A. C. Berbringer, 334 N. San Pedro St. Los
Angeles, California Canada: F. P. Barber Machinery Co., Toronto, Canada



43 Standard Sizes

DIES Punching and Forming for All Makes and Sizes of Press Brakes.



MANUFACTURING COMPANY 7430 S. Leemis Blvd., Chicage 36, Illinois

ADVERTISERS IN THIS ISSUE

	G
Accurate Perforating Co. 153	Goodman Electric Machinery Co. 168
Air Reduction 101	Goodrich, B. F., Co., The Indus- trial & General Products Div 4
Allis-Chalmers Mfg. Co. 5 Amercan Brass Co., The 35, 36	Gordon, Claud S., Co. 124
American Brass Co., The 35, 36	Goss & DeLeeuw Machine Co. 154
American Chemical Paint Co 47 American Screw Co	Gray Iron Founders' Society, Inc. 151
American Steel & Wire Div.	Great Lakes Steel Corp. 56
United States Steel Co.	Great Lakes Steel Corp. 56 Great Pipe & Steel Corp. 165
17, 18, 19, 20, 21, 22	Griffin Manufacturing Co
American Steel Export Co., Inc. 148	Gulf Oil Corp. 99
Armco Steel Corp. 6 Armel, James P. 166	Gulf Refining Co. 99
Atlas Marine Fabricators, Inc. 164	
Automatic Steel Products, Inc. 125	н
	Hayward Company, The . 154
	Hindley Manufacturing Co. 170
	Howell Electric Motors Co. 153
Babcock & Wilcox Co., Refrac-	Hubbard, M. D., Spring Co. 153 Hughes, Arnold Co. 166, 168
tories Div. 96	Hyman, Joseph, & Sons 165
tories Div. 96 Baker Bros., Inc. 30	Hyman-Michaels Co. 166
Basic Ketractories Inc. 176	Hynes Steel Products Co. 77
Belyea Co., Inc. 160	
Benkart Steel & Supply Co	
Bennett Machinery Co	Industrial Equipment Div. 166
Bethlehem Contracting Co 166	Industrial Equipment Div. 166 Inland Steel Co. 102 International Nickel Co., Inc., The 131
Bethiehem Steel Co	International Nickel Co., Inc., The 131
Bixby, R. W., Co	Iron & Steel Products, Inc 161
Black & Decker Mfg. Co., The 55	
Boynton, A. J., & Co	
Brandt, Charles T., Inc. 46 Brownell, Hazard Machine Tools,	Jandry Steel Corp. 147
Inc	Jennings, Jira Thaver 169
Browning, Victor R., & Co., Inc., 171	Jandru Steel Corp. 167 Jennings, Jira Thayer 169 Johns-Manville Corp. 34
Builders Steel Supply Co. 168 Bunting Brass & Bronze Co. 62	
Bunting Brass & Bronze Co. 62	
	Kaiser Steel Corp. 139
	Keystone Steel & Wire Co
С	Kinderman, Lou F
Carborundum Co., Refractories	Kinderman, Lou F
Div. 8 Carpenter Steel Co., The 133	Kings County Machinery Exchange 162
Carpenter Steel Co., The	Knox, Earl E., Co. 162
Carpenter Steel Co., The Webb Wire Div. 170 Central Steel & Wire Co. 123 Chicago Congreta Breeking Co. 24	
Central Steel & Wire Co. 123	L.
Chicago Concrete Breaking Co	La Consolidada 168
Cincinnati Bickford Tool Co., The 12	Land, L. J., Inc 167
Cincinnati Machinery Co., Inc. 160	Lana Machinery Co. 167 Lansing Stamping Co. 88
The LAA LAC	Lansing Stamping Co. 88
Cincinnati Milling Machine Co., The 144, 145 Cleveland Steel Tool Co., The 171	Lebanon Steel Foundry 164
Cleveland Tapping Machine Co. 125	Leeds & Northrup Co
Columbia - Geneva Steel Div.	Leland-Gifford Co. 154
United States Steel Co.	Leschen, A., & Sons Rope Co. 13
17, 18, 19, 20, 21, 22 Crawford, F. H., & Co., Inc. 164	Lucas Machine Div., The New Britain Machine Co 64
Cross Company, The 10 Curry, Albert, & Co. Inc. 164	Luria Bros., & Co., Inc. 135
Curry, Albert, & Co. Inc. 164	cand bross, a cos, me.
	M Paradair Co. 99
D	McCabe T & Co. 167
D Darien 168	MacCabe, T. B., Co. 167 Machine, J. B., Tool Co., Ltd. 164
Davis, Samuel M. 162	Macwhyte Company 32
Diamond Manufacturing Co. 171	Magnaflux Corp. 73
Donahue Steel Products Co. 162 Dony, D. E., Machinery Co. 160	Magnaflux Corp. 73 Magrill, Bernard, Auch'r. 166 Mandel-Camras Machinery Co.
Dow Furnace Co 100	Mandel-Camras Machinery Co., Inc. 165
	Marshall Railway Equip. Corp. 168
Du Pont de Nemours, E. I., & Co.,	Master Electric Co., The
Inc., Electrochemicals Dept. 143	Inside Back Cover
	Master Products Co. 89 Mathews Conveyer Co. 171
	Maxwell Machinery Corp 165
E	McGuigan John D. Inc. 165
Eastern Machine Screw Corp., The 170	Midvale Company 91
Eastern Machinery Co., The 161	Miles Machinery Co. 160 Moorhead Elect. Mach'y. Co. 167
Eastern Tool & Mfg. Co 154	Moorhead Elect. Mach'y. Co 167
Electric Equipment Co. 166	Morey Machinery Co., Inc. 153, 163 Morgan Construction Co. 31
Electric Equipment Co. 166 Elox Corporation of Michigan 154	Morrison Railway Supply Corp. 168
Employers Service Bureau 169	Motch & Merryweather Machinery
Engineering Mfg. Co 157	Co
Erie Enameling Co., The 98	Mundt, Chas., & Sons
Espen-Lucas Machine Works, The 171	
	N
	National Machinery Exchange 164
F	National Steel Corp. 56
Falk Machinery Co 164	National Tube Div., United States Steel Co17, 18, 19, 20, 21, 22
Farval Corp Inside Front Cover	New Britain-Gridley Machine Div.,
Federal Fdry. Supply Co., The 168	New Britain Machine Co., The
Fisher Associates	New Britain Machine Co., The
Foster, L. B., Co	Back Cover
Frank, M. K	
(Continued of	



SALES AGENTS:

WM. H. LEONORI & CO., Inc., 30 Howard St., New York 13. N. Y.; CHARLES L. LEWIS, 1355 Market St., San Francisco 3, Cal.; J. J. LAMBERT, 323 Huntington Ave., Buffalo, N. Y.; CENTRAL STEEL & WIRE COMPANY, 13400 North Mt. Elliott, Detroit 12, Mich.; 3000 West 51st St., Chicago 50, Ill.; Box 148 Annex Station, Cincinnati 14. Obso 12, Mich.; 30 80, Ill.; Box nati 14, Obso

GRIFFIN MANUFACTURING CO. . ERIE, PA.



LOCOMOTIVE CRANES

171

154 170 153

153 168 165

166

102

162

162

162

13

135

168

165

26, 27

GE



THE OHIO LOCOMOTIVE CRANE CO. BUCYRUS. OHIO

CLEVELAND STEEL TOOL

Punches, Dies, Chisels, Rivet Sets 660 E. 82nd St., Cleveland, O. If it's RIVETED you KNOW it's safe

lly located for export AND WATER RATES, EAST AND WEST



Cutting Off Machines for Smring All Kinds of Metals

THE ESPEN-LUCAS MACHINE WORKS FRONT AND GIRARD AVE., PHILADELPHIA, PENNA.


. . . Don't Hide Your Light Under A Bushel . . .

Have something new on the market or do you just want to tell why your product does the job better?

Either way, your advertisement in The Iron Age carries more weight and reaches more of your prospects.



Washers are "big business" with Whitehead. Production is fast, economical. Big runs from automatic presses. U. S. Air Corps Standard washers, U. S. and S.A.E. Standards, etc. WRITE FOR CATALOG.



WHITEHEAD STAMPING CO.

1669 W. Lafavette . Detroit 16. Mich.

Since 1905. Engineers and manufacturers of Conveyers and Conveyer Systems for the Metal-Working Industries.

Three modern plants. Engineering Offices in All Principal Cities. There's an Engineering Sales Office near you.



MATHEWS CONVEYER CO.

ELLWOOD CITY . . . PENNSYLVANIA SAN CARLOS CALIFORNIA PORT HOPE . . ONTARIO, CANADA



COPPER—BRASS—BRONZE PERFORATED

TO YOUR REQUIREMENTS SEND US YOUR DRAWINGS FOR PRICE

PERFORATED METALS

FOR ALL INDUSTRIAL USES ALL SIZE AND SHAPE HOLES—ALL METALS ARCHITECTURAL GRILLES

DIAMOND MFG. CO.

BOX 28 Write for Catalog 35 WYOMING, PA.



THE KING

A hardness tester particularly adapted for use on CASTINGS and FORGINGS

Puts an actual lead of 3000kg on a 10mm ball. Throat, 4" deep. Gap. 10" high. Weight, 26 lbs.

Can be used in any position—even upside

Equally accurate as portable or stationary Test head removable for testing larger pieces beyond the capenity of the standard base.

ANDREW KING

Box 606, Ardmore, Pa.



The grinding department has them stepping!



SIMONDS ABRASIVE CO.

Grinding Wheels



More assemblers needed . . . and it's simply a matter of cause and effect. The cause-Simonds Abrasive Company Grinding Wheels! The effect-more production turned out faster. Put more "prod" in your production with Simonds Wheels. They're part of a complete line including grinding wheels of all shapes and sizes, mounted wheels and points, segments and abrasive grains . . . accurately specified for your jobs ... and made by Simonds Abrasive Company, a major grinding wheel producer for almost 60 years. Write for grinding data book and name of your distributor.

SIMONDS ABRASIVE CO., PHILADELPHIA 37, FA. BRANCH WAREHOUSES: CHICAGO, DETROIT, BOSTON DISTRIBUTORS IN PRINCIPAL CITIES

Division of Simonds Saw and Steel Co., Fitchburg, Mass. Other Simonds Companies: Simonds Steel Mills, Lock-port, N. Y., Simonds Canada Saw Co., Ltd., Montreal, Que. and Simonds Canada Abrasive Co., Ltd., Arvida, Que.

ADVERTISERS IN THIS ISSUE

(Continued from Page 170)

*
0
O'Connell Machinery Co. 162
Ohio Locomotive Crane Co., The 171
Orton Crane & Shavel Co. 72
Ottemiller, Wm. H., Co.
P
Pacific International Corp. 165
Page Steel & Wire Div., American Chain &
Cable Co., Inc. 88
Panama Canal Co. 168
Paul's Machinery Co. 163 Pheoli Mfa. Co. 9
Pheoli Mfg. Co. 9 Pittsburgh Gear Co. 83
Power Plant Equipment Co. 167
Pratt & Whitney Div., Niles-Bement-Pond Co.
14, 15
Public Service Electric & Gas Co. 86
Purdy Company, The
R
Reliance Steel Div., Detroit Steel Corp. 137
Republic Steel Corp
Revere Copper & Brass, Inc. 53
Rich Steel Co. 165 Ritterbush & Co., Inc. 158, 159
Ritterbush & Co., Inc. 158, 159 Russell Russell & Ward Rolt & Nut Co. 75
Russell, Burdsall & Ward Bolt & Nut Co. 75
S
Sciaky Bros., Inc. 155
Sharon Steel Corp. 79, 80, 81, 82
Shenango-Penn Mold Co. 78
Simonds Abrasive Co. 172
Smith, A. O., Corp. 92, 93 Southern Galvanizing Co. 171
Standard Iron & Steel Co. 168
Stuart, D. A., Oil Co., Ltd.
Sturtevant, P. A., Co. 88
Superior Steel Corp. 128
Surface Combustion Corp. 24, 25
7
Tabor Manufacturing Co., The 170 Tennessee Coal & Iron Div., United States Steel Co., 17, 18, 19, 20, 21, 22 Texas Company The 58 Timken Roller Bearing Co., The Front Cover
Tennessee Coal & Iron Div. United States
Steel Co. 17, 18, 19, 20, 21, 22
Texas Company The
Tracerlab, Inc.
Treadwell Engineering Co. 85
Turchan Follower Machine Co 60
U
United States Steel Export Co. 17, 18, 19, 20, 21, 22
United States Steel Co. 17, 18, 19, 20, 21, 22
Universal Ball Co 52
Venedium Corn of America
Yanadiani Co p. or A no rea
Vickers, Inc 23
W
Wallack Bros
Warner & Swasey Co. 71
Webb Corp., The
Weiss, B. M., Co
Weiss Steel Co. Inc. 169 West Penn Marhinery Co. 164
West Penn Marhinery Co. Western Felt Works
Western Felt Works Westinghouse Electric Corp. 28, 29
Whitehead Stamping Co
Williams, Edward Hale, Mfg. Engr 164
Winston Machinery Co., Inc
Y
Yale & Towne Mfg. Co. 51
Youngstown Foundry & Machine Co. 68

CLASSIFIED SECTION


Business Opportunities	158-	
Clearing House	130-	100
Contract Manufacturing. Appears in first third issue of each month. See Nov. Nov. 20.	and 6 &	
Employment Exchange		169
Wanted		168

21, 22 21, 22 52

. 149

5, 168 ... 71 ... 157 ... 166 ... 169 ... 164 ... 11 228, 29 ... 171 ... 164 ... 162

58-169 d



STILL THE ALL-AMERICAN FIRST

Master Gearmotors have given more millions of hours of satisfactory service in the field than all other makes . . . COMBINED.



THE MASTER ELECTRIC COMPANY . DAYTON 1, ONIO




NEW PRODUCT DESIGNS DEMAND NEW MACHINING METHODS

This New Britain Automatic developed for contour facing jet compressor wheels

AUTOMATIC BAR AND CHUCKING MACHINES - PRECISION BORING MACHINES

LUCAS HORIZONTAL BORING, DRILLING AND MILLING MACHINES






NEW PRODUCT DESIGNS DEMAND NEW MACHINING METHODS

This New Britain Automatic developed for contour facing jet compressor wheels

AUTOMATIC BAR AND CHUCKING MACHINES - PRECISION BORING MACHINES
LUCAS HORIZONTAL BORING, DRILLING AND MILLING MACHINES





Tough" is the word for the job being machined here. But it's "all in the day's work" for this versatile 62" standard KING."

Just check over the things required in a boring mill to efficiently, economically machine this job. You need:

- 1. A speed range wide enough to turn the small diameter center post and still do turning and form tool work on the large outside diameter—both at efficient cutting speeds.
- 2. The right feed to provide acceptable surface finishes.
- 3. Hand controls sensitive enough to permit easy feeding of a large radius form tool.

- 4. Extra weight and rigidity that are necessary to provide chatter-free finishes.
- 5. Accuracy that will check out with a contour gauge.

Because KING mills have all of these advantages they meet all the requirements of this intricate job—just as they meet the boring, facing, and turning requirements of any other work, simple or complicated.

That's why, today as for half a century past, KING is industry's first choice for fast, accurate, profitable production. For full details see the King distributor in your locality, or write us direct.

King Vertical Boring & Turning Machines are made in 10 sizes —30", 36", 42", 52", 62", 72", 84", 100", 120", and 144".

American Steel Foundries

KING MACHINE TOOL DIVISION

CINCINNATI 29, OHIO



THE LIBEARY OF CONGRESS
PHOTODLIPLICATION SERVICE
WASHINGTON 25, D. C.

TELET TELET OF 6 8 2 9 5 5 E Z T